

# AUDITORIUM - UIT UNIVERSITY KARACHI



BILL OF QUANTITIES FOR INTERIOR FINISHING WORKS June, 2025



## INTERIOR FINISHING WORKS OF AUDITORIUM - UIT UNIVERSITY KARACHI

#### **MAIN SUMMARY**

S/No.	Description	I.D Works Amount Rs.
i	Demolition Work	
ii	Layout Marking	
iii	Civil & Interior Design Work	
	Total	

### UIT UNIVERSITY, KARACHI

#### Introduction

UIT University (UITU), established under The UIT University Act, 2017 [Sindh Act No. XXXIV of 2018], is a testament to our commitment to providing quality education. UITU received the NOC from the Higher Education Commission (HEC) in 2021. Our academic programs are duly accredited by regulatory bodies including PEC, NCEAC, and NTC. UIT University is a project of Usman Memorial Foundation (UMF). UMF was established in 1973 with the objective to establish a state-of-the-art educational project to meet the ever growing education needs of the society. The University's city campus is located in Gulshan-e-Iqbal whereas a purpose built main campus in the District Malir is in the phase of development.

UITU has earned its esteemed status by consistently upholding high standards of education. Our commitment to adapting courses in response to evolving technologies ensures that our graduates are not only competent professionals but are also well-versed in staying abreast of industry trends.

At UITU, we pride ourselves on our inclusive approach to education. We welcome meritorious students from diverse backgrounds and are committed to providing equal opportunities for all applicants, irrespective of gender, religion, color, creed, race, class, or domicile.

The University is the culmination of three decades of progressive and successful operation of the Usman Institute of Technology (UIT) which was established in the year 1994. UIT has provided more than 5,000 graduates serving governments, industries, trades and businesses as professionals, experts and entrepreneurs within the country and abroad.

In the pursuit of excellence for seeking and disseminating knowledge, the University is committed to intensify its footprint in the area of quality education, research and community service by implementing best practices, adopting emerging technologies and engaging qualified and experienced human resources.



ŧ	Description	Unit	Qty	Rate	Amount			
т	Note: (Applied on Complete BOQ)	Onic	Qty	Nate	Anount			
	As part of the bidding process, please be advised of the following important requirements and conditions:-							
	1) Base Rates of Material Mentioned in BOQ:-	ricing from	the color	tion of motor	iala will be adjust			
	All base rates are inclusive of GST. Any cost difference a according to the purchase/invoice rates.	rising from	the select	tion of mater	iais will be adjuste			
	2) 5% marginal contingencies in quantities:-							
	The quantities provided in this Bill of Quantities inclu		0	•				
	drawings. This 5% margin is intended to account for pot	•	•	-				
_	work. It is important to note that this margin is not intend 3) Mandatory Site Visit:	ied to cover	material	wastage or ic	osses incurred			
	All contractors are required to visit the project site befo	re nrenaring	and sub	mitting their	hids. The site visit			
	crucial for understanding the project scope, site condition			-				
	work.	ins, and any	potentia	r entanenges t	inde may impace of			
	It is the contractor's responsibility to thoroughly inspe	ect the site	and gath	ner all neces	sary information			
accurately estimate the cost and resources needed for the project.					,			
	Site visits can be coordinated with the following team me		T Univers	ity:				
	1. Hari Lal: +92 333 2274029							
2. Muhammad Kamran Jamil: +92 300 2927138								
	4) No Variation After Bidding:							
	Once the bid has been submitted and accepted, no v	ariations or	adiustm	ents to the	hid amount will h			
	considered under any circumstances.		aujustin					
	This clause applies to all possible situations, including ch	anges in ma	terial cos	ts. overtime	labor availability.			
	any other factors that may arise during the project execu	-		,	,,,			
	By submitting a bid, the contractor acknowledges and ag		ollowing:					
	a) The site has been visited and inspected in person.		Ū					
	b) All relevant factors have been considered in the bid.							
	c) No claims for additional compensation or extension	s of time w	ill be ent	ertained afte	er the bid has bee			
	accepted.							
	Pre-bid Meeting: 16 <sup>th</sup> July 2025							
	<ul><li><u>5) Compliance:</u></li><li>a) Failure to comply with the site visit requirement may response to the site</li></ul>	ocult in the d	licqualific	ation of your	hid			
	b) It is imperative that you document your site visit and a		•					
	preparation.	any mungs			innuenced your b			
	c) Only debris is allowed to be taken away by t	he contrac	tors. all	doors. win	dows, railing, gri			
	electrical/plumbing fittings & fixtures and all useable tile							
		,	,	e property				

#					
_	Description	Unit	Qty	Rate	Amount
	Note:-	1			<b>6</b> 11 - 11
	a) Before quoting the rates please detail visit of site, drawin	gs and thor	roughly study the	e material and na	ture of dismantling
	demolishing and repairing work. b) All methods for removing/dismantling of below items cov	ver all labor	r equinment and	techniques and	disposal of all deb
	out side the building limits or as directed by the Architect/En		, equipment and	teeninques and	
	c) All work to be carried out as per instruction and satisfaction	-	tect. All dismantl	ing/Demolition/ r	emoval will be do
	carefully and make sure not to Damage the Existing building				
	the work.		0		
<u> </u>	Demolition Works				
	a) Dismantling/Removing of block masonry wall of				
	any thickness & size with plaster (at any level or				
	height), including cost of disposal of rubbish material				
	out side the building limits or as directed by the				
	Architect/Engineer. complete in all respect and				
	conforming to the requirement of drawings,				
	specification and to the entire satisfaction of the				
	Architect/Engineer.				
	b) Removal of all type of tile cladding on wall with				
	base (of any thickness) over block masonry wall (at				
	any level or height) including cost of removing of				
	skirting , disposal of rubbish material out side the				
	building limits or as directed by the				
	Architect/Engineer. complete in all respect and				
	conforming to the requirement of drawings,				
	specification and to the entire satisfaction of the				
	Architect/Engineer.				
	c) Removing of doors with frame any size, shape &				
	material (at any level) including cost of disposal of				
	rubbish material out side the building limits or as				
	directed by the Architect/Engineer. complete in all				
	respect and conforming to the requirement of				
	drawings, specification and to the entire satisfaction				
	of the Architect/Engineer.				
	d) Removal of floor tiles with base (of any thickness)				
	(at any level) including cost of disposal of rubbish				
	material out side the building limits or as directed by				
	the Architect/Engineer. complete in all respect and				
	conforming to the requirement of drawings,				
	specification and to the entire satisfaction of the				
	Architect/Engineer.				
	e) Removal of CC floor base (of any thickness) (at any				
	level) including cost of disposal of rubbish material				
	out side the building limits or as directed by the				
	Architect/Engineer. complete in all respect and				
	conforming to the requirement of drawings,				
	specification and to the entire satisfaction of the				
	Architect/Engineer.				

#### **BILL OF QUANTITIES**

Demolition Works - AUDITORIUM # Description Unit Qty Rate Amour							
	Description	Unit	Qty	Rate	Amount		
	f) Removing / scraping of existing paint from ceiling,						
	projection and wall, including disposal of rubbish out						
	side the building limits or as directed by the						
	Architect/Engineer. complete in all respect and						
	conforming to the requirement of drawings,						
	specification and to the entire satisfaction of the						
	Architect/Engineer.						
	g) Removing of False Ceiling or framing of any						
	material with its hanging systems/ frame etc at any						
	level & height including cost of disposal of rubbish						
	material out side the building limits or as directed by						
	the Architect/Engineer. complete in all respect and						
	conforming to the requirement of drawings,						
	specification and to the entire satisfaction of the						
	Architect/Engineer.						
	h) Dismantle & Removing of Vanity with Slab of any						
	thickness at any level or height including cost of						
	proper cutting of reinforcement (where required),						
	cleaning of steel reinforcement bar (where required),						
	disposal of rubbish material out side the building						
	limits or as directed by the Architect/Engineer.						
	complete in all respect and conforming to the						
	requirement of drawings, specification and to the						
	entire satisfaction of the Architect/Engineer.						
	i) Demoval of UNAC line with handing system						
	i) Removal of HVAC line with handing system						
	including removal of pipes, fixtures, fittings, cable						
	tray, etc for Construction Area/Renovated Area or as						
	specified by Architect/Engineer including cost of						
	disposal of rubbish material out side the building						
	limits or as directed by the Architect/Engineer.						
	complete in all respect and conforming to the						
	requirement of drawings, specification and to the						
	entire satisfaction of the Architect/Engineer.						
	j) Removal of Electrical power supply wiring, pipes,						
	fixtures, fittings, cable tray, electrical appliances,						
	lights, fan etc for the Construction Area/Renovated						
	Area or as specified by Architect/Engineer including						
	cost of disposal of rubbish material out side the						
	building limits or as directed by the						
	с ,						
	Architect/Engineer. complete in all respect and						
	conforming to the requirement of drawings,						
	specification and to the entire satisfaction of the						
	Architect/Engineer.						

	Demolition Works - AUDITORIUM						
S.#	Description	Unit	Qty	Rate	Amount		
	k) Removal of Water Supply fittings, fixtures, pipes etc for the Construction Area/Renovated Area or as specified by Architect/Engineer including cost of disposal of rubbish material out side the building limits or as directed by the Architect/Engineer. complete in all respect and confirming to the requirement of drawings, specification and to the		~~				
	entire satisfaction of the Architect/Engineer. I) Removal of Sewerage and Other Supply lines fittings, pipes etc for the construction area/Renovated area or as specified by Architect/Engineer including cost of disposal of rubbish material out side the building limits or as directed by the Architect/Engineer. complete in all respect and confirming to the requirement of drawings, specification and to the entire satisfaction of the Architect/Engineer.	Job	1				
	Total						

#### **BILL OF QUANTITIES**

#### Layout Marking Work - AUDITORIUM

S.#	Description	Unit	Qty	Rate	Amount
1	LAYOUT MARKING				
	Providing and marking layout on site by approved marking materials (Tap, Chalk, Paint, etc.) as per drawing and specification at any level or height including cost of all fixing accessories, arrangements, etc., complete in all respects conforming to the requirements of drawings and specification and to the entire satisfaction of the Architect/Engineer.				
	a) Auditorium	Job	1		
	Total				

S.#	Description	Unit	Qty	Rate	Amount
Α	Wall Finishes				
1	Block Work				
	Provide and lay machine made Hollow/Solid Block Masonry with minimum compressing strength of 1000 Psi, setting the blocks in 1:4 cement sand mortar, raked joints including curing, scaffolding, reinforcing & anchors from RCC columns (if required) & grouting with cement sand mortar), hacking of existing surface for bonding where necessary, wastage, etc., complete job with all necessary arrangements, as per drawing/detail and as directed by the Architect.				
	a) 4'' Thick Solid Block work	Sft	Rate only		
	b) 6'' Thick Solid Block work	Sft	27		
	c) 8'' Thick Solid Block work	Sft	Rate only		
2	Plaster Work				
	Provide and apply 1:4 cement sand plaster of minimum thickness as specified on RCC Members / Block Walls / Ceiling surface including making all grooves, edges, bends, corners, jambs of doors and windows / patta, & recesses finished smooth including G.I corner beads/plaster stops upto 9'-0" height from FFL to all horizontal and vertical exposed corner edges (for protection of corner & edges), 1' wide galvanized metal lathe of 18 SWG at the junctions of concrete and block masonry, conduit chases, etc., fixed with nails and G.I. sheet strip/washer, rounded edges where required, drip core recesses and grove making smooth / foam finished, smooth finished in line, level, plumb, curing, scaffolding, hacking / chipping of existing surface for bonding where necessary, etc., complete in all respect. (For Payment exposed area will be measured)		114.00		
	b) 3/4" thick Plaster Work	Sft	Rate only		

S.#	Description	Unit	Qty	Rate	Amount
3	HDF Wall Claddind on Wall with G.I Internal Framing				
	Providing, making and fixing of HDF board cladding on wall up to any height and floor comprising of cladding of HDF board (of specified thickness & approved brand) on wall with backing support of G.I Internal framing system of 18 & 20 SWG, closing all end openings with same cladding material, fixing of G.I frame on wall, floor & tie with structural slab/beam, including all fixing accessories and arrangements, scaffolding, making openings, cutting of electric switch board, lights, etc., as shown in drawing & details, complete in all respect and as instructed by the Architect. (This job will be coordinated with all MEP works electrical, plumbing and air-conditioning, etc.) Note:- "No additional payment will be provided for strengthening the internal reinforcement or framing of any size or gauge, anywhere on-site, for any reason."				
	a) HDF board cladding using 1/2" thick HDF board approved brand (From ZRK, Merbok, Alnoor, Lasani or equivalent) in panels. (For Payment exposed cladding area will be measured without any depth and thickness).	Sft	2,360		
4	Acousting Wall Penling (Option-1)				
	Providing, making and fixing of Acoustic Paneling on wall, fixed over existing Wall of any kind, fixed with adhesive/screw as shown in drawings & details, including cutting, fixing, hardware's, wastage, adhasive of approved quality, lifting, all fixing accessories and arrangements, scaffolding, making openings, cutting of electric switch board, lights, etc., as shown in drawing & details, complete job in all respect as per drawing/detail and as directed by the Architects. (This job will be coordinated with all MEP works electrical, plumbing and air-conditioning, etc.) a) Acousting Wall Penling <b>(Option-1).</b>				
	(Only Acoustic Panels are OFM) (For Payment Exposed Area will be measured without any depth and thickness)	Sft	1,327		

S.#	Description	Unit	Qty	Rate	Amount
5	Fabric Paneling on wall with Foam Cushioning & MDF				
5	Backing (For Acoustic Purposes) (Option-2)				
	Providing, making and fixing of Fabric Paneling on wall with				
	Foam Cushioning & MDF Backing on wall, consisting of MDF				
	board Paneling on existing walls using 1/2" thick MDF board				
	of approved brand (ZRK/Merbok/Al-Noor/Lasani) cushioning				
	on MDF with foam of approved thickness (by Master foam)				
	and pasting of fabric (as per approved sample) on foam with				
	approved adhesive, including the cost of solignum treatment				
	to all wood surfaces, fixing of panels on existing Wall of any				
	kind, fixed with adhesive/screw as shown in drawings &				
	details, including cutting, fixing, hardware's, wastage,				
	adhasive of approved quality, lifting, all fixing accessories and				
	arrangements, scaffolding, making openings, cutting of				
	electric switch board, lights, etc., as shown in drawing &				
	details, complete job in all respect as per drawing/detail and				
	as directed by the Architects.				
	(This job will be coordinated with all MEP works electrical,				
	plumbing and air-conditioning, etc.)				
	a) Fabric Paneling on wall with Foam Cushioning & MDF				
	Backing (For Acoustic Purposes) (Option-2)				
	(Base Rate of Fabric Rs.300/- Per Sft)	Sft	Rate only		
	(For Payment Exposed Area will be measured without any		nace only		
	depth and thickness)				
	Wooden Light Cove on Wall in Polish Finish Around Acoustic				
6	Paneling with Backing of Partal Wood Framing.				
	(Option-1) (HDF+Oak Veneer)				
	Providing, making and fixing of Wooden Light Cove on wall in				
	Polish finish around Acoustic Paneling or any where required,				
	comprising of 1/2" thick HDF board cove of required size				
	fixed on wall with partal wood concealed framing structure,				
	pasting of 1/8" thick Oak Veneer on all external/exposed				
	surfaces of cove fixed through approved adhesive, polishing				
	on all veneer surfaces with approved polish with preparing				
	surface as shown in drawing up to any height, floor and				
	depth, including all fixing accessories and arrangements,				
	scaffolding, polishing with approved polish, solignum				
	treatment to all wooden surfaces, making openings, cutting				
	of electric switch board, lights, etc., as shown in drawing &				
	details, complete in all respect and as instructed by the				
	Architect.				
	(This job will be coordinated with all MEP works electrical,				
	plumbing and air-conditioning, etc.)				
	(For Payment Running length will be measured with-out any				
	depth and thickness.)				
	a) 3" wide and 5" Deep Wooden Light Cove. (Option-1)				
	(HDF+Oak Veneer)	Rft	946		
					L

S.#	Description	Unit	Qty	Rate	Amount
7	Wooden Light Cove on Wall in Polish Finish Around Acoustic Paneling with Backing of Partal Wood Framing. (Option-2) (Plywood)				
	Providing, making and fixing of Wooden Light Cove on wall in Polish finish around Acoustic Paneling or any where required, comprising of 1/2" thick Plywood board (imported) cove of required size fixed on wall with partal wood concealed framing structure, polishing on all exposed, external surfaces with approved polish with preparing surface as shown in drawing up to any height, floor and depth, including all fixing accessories and arrangements, scaffolding, polishing with approved polish, solignum treatment to all wooden surfaces, making openings, cutting of electric switch board, lights, etc., as shown in drawing & details, complete in all respect and as instructed by the Architect. (This job will be coordinated with all MEP works electrical, plumbing and air-conditioning, etc.) (For Payment Running length will be measured with-out any depth and thickness.)				
	a) 3" wide and 5" Deep Wooden Light Cove. (Option-2) (Plywood)	Rft	Rate only		
8	Wooden Light Cove on Wall in Polish Finish Around Acoustic Paneling with Backing of Partal Wood Framing. (Option-3) (Solid Oak Wood)				
	Providing, making and fixing of Wooden Light Cove on wall in Polish finish around Acoustic Paneling or any where required, comprising of of 3/4" thick solid Oak wood for making cove of required size fixed on wall with partal wood concealed framing structure, polishing on all exposed & external surfaces of Oak wood with approved polish with preparing surface as shown in drawing up to any height, floor and depth, including all fixing accessories and arrangements, scaffolding, polishing with approved polish, solignum treatment to all wooden surfaces, making openings, cutting of electric switch board, lights, etc., as shown in drawing & details, complete in all respect and as instructed by the Architect. (This job will be coordinated with all MEP works electrical, plumbing and air-conditioning, etc.) (For Payment Running length will be measured with-out any depth and thickness.)				
	a) 3" wide and 5" Deep Wooden Light Cove. (Option-3) (Solid Oak Wood)	Rft	Rate only		

S.#	Description	Unit	Qty	Rate	Amount
9	Engraving Logo by CNC Machine on 1/2" thick Oak Veneer in polish finish as per design. 3ft dia & 1/4" Deep.				
	Providing and making engraved Logo on 1/2" thick Oak Veneer/Ply By CNC Machine of required size and depth, pattern and shape as shown in drawings & details, including polisheing with approved polish after preparing the surfaces & primer coat, engraving by CNC, cutting, hardware's, wastage, glues, lifting, all fixing accessories and arrangements, scaffolding, making openings, cutting of electric switch boards and lights, solignum treatment, etc., as shown in drawing & details, complete job in all respect as per drawing/detail and as directed by the Architects. (This job will be coordinated with all MEP works electrical, plumbing and air-conditioning, etc.)				
	a) Engraving Logo by CNC Machine on 1/2" thick Oak Veneer in polish finish as per design. 3ft dia & 1/4" Deep.	Job	2		
10	Cladding of Oak Veneer on Wall in Polish Finish and Making Groov Lines as per Design				
	Providing, making and fixing of Oak Veneer of specified thickness cladding on wall in polished finish with making groov lines as shown in drawing up to any height, floor and depth, comprising of Oak Veneer of specified thickness cladding on existing surface of HDF, fixed through approved adhesive/screws, including all fixing accessories and arrangements, scaffolding, polishing with approved polish with primer, making openings and cutting for electric switch boards and lights, making groove lines of approved depth in polish finish, etc., as shown in drawing & details, complete in all respect and as instructed by the Architect. (This job will be coordinated with all MEP works electrical, plumbing and air-conditioning, etc.) (For Payment exposed area will be measured with-out any depth and thickness.)				
	a) Cladding of 1/2" thick Oak Veneer on Wall in Polish Finish and Making Groov Lines as per Design.	Sft	306		
i	b) Cladding of 1/4" thick Oak Veneer on Wall in Polish Finish and Making Groov Lines as per Design.	Sft	721		
	c) Cladding of 1/8" thick Oak Veneer on Wall in Polish Finish and Making Groov Lines as per Design.	Sft	32		

S.#	Description	Unit	Qty	Rate	Amount
11	Solid Paneled Door in Polish Finish				
	Providing, making and fixing in position Openable Door 2" thick Solid wooden panel door shutter (Both side paneling) of Oak wood (using seasoned and termite proofing) with 6" wide & 2" thick door frame (Chowkhat) of Oak wood, polishing complete door i/c door frame with approved polish with applying primer and solignum treatment, as per drawing/detail including fixing, lock set, S.S Screw, SS handle, wastage, etc. all types of fittings, complete as per drawings and as directed by the Engineer. (For payment, one side frame to frame door elevation area will be measured)				
	a) Solid Paneled Door in Polish finish (Double Shutter) (Base Rate of Hardware's Rs.25,000/- Per Door)	Sft	119		
12	2" thick Solid Core Flush Door in Polish Finish with Aluminum Frame				
	Providing, making & fixing of Wooden Door, consisting of 2" thick solid core flush shutter (for flush door shutters partal wood infill framing) using approved 1/4" thick Oak Ply on both sides of shutter over rough wood structure frame with 1/2" thick wood lipping polish finish, including 6" wide & 1- 1/2" thick Aluminium door frame in paint finish, including fixing, lock set, S.S Screw, SS handle, wastage, approved hardware's, seasoning, termite proofing in wooden surface area, etc. complete in all respect as per drawings, specifications and instructions of the Architect. (For payment, one side net exposed door elevation area will be measured.)				
	a) 2" thick Solid Core Flush Door with Aluminum Frame in Polish finish (Single Shutter) (Door's Hardware will be from JB Saeed.) (Base Rate of Hardware's Rs.15,000/- Per Door)	Sft	38		
13	Internal Glazing with 12mm thick Tempered Glass with Powder Coated M.S Framing.				
	Providing, fabrication and installation in position fixed glazing, consisting of 12mm tempered cleared glass of approved brand (Ghani, Tariq Float) with powder coated M.S framing of approved section fixed on Floor/wall/overhead beam, etc., as per shown in drawing including all hardware's, neoprene gasket, rubber gasket seal & silicone sealant, fixing arrangements, etc., complete in all respect. Door area will be deducted. (For payment Frame to Frame one side elevation area will be measured.)	Sft	104		

S.#	Description	Unit	Qty	Rate	Amount
14	Glass Doors With Powder Coated M.S Framing of Door & Panels)				
	Providing, fabrication & installation in position Glass door, consisting of 12mm thick tempered glass of approved brand (Ghani, Tariq Float) door with powder coated M.S framing for Door & panels of approved section, all fitting with hinges of approved quality, locking arrangements, as per approved customized M.S handles as per design on both sides of shutter including all hardware's, wastage, silicon sealant, lifting, cutting, fixing, etc., complete as per drawing, hardware schedule and instruction of the Architect. (For payment Frame to Frame one side elevation area will be measured.)				
	a) Glass door 12mm Tempered Glass with powder coated M.S framing for Door & panels of approved section. (Single Shutter) (Base Rate of Hardware's from JB Saeed Rs.20,000/-)	Sft	16		
15	M.S. Framing for SMD/LED Screen.				
13	Providing, fabricating and fixing M.S framing for SMD/LED Back Support, comprising of 4mm thick M.S Plate size 6"x6" and fixing 14-Guage thick vertical M.S Section Pipe size 3" x 1- 1/2" fixing and supporting with flooring to ceiling, M.S framing specified size consisting of M.S pipe/Section, M.S plate, M.S angle iron, U-channel and all required sections, where required as per the drawing & detail, including anti rust paint / Red Oxid Paint of approved colour (ICI, Berger, Jotun, Nippon), complete job with cutting, bending, welding, drilling, grinding, fabrication, hardware, wastage, lifting, scaffolding, and erecting in position, etc., complete job with all necessary arrangements, as per drawing/detail and as directed by the Architect. (This job will be coordinated with all MEP works electrical, plumbing and air-conditioning, etc.) (Frame to frame one side elevation area will be measured)	Sft	151		

S.#	Description	Unit	Qty	Rate	Amount
16	Matt Enamel Paint On Wall.				
	Provide and applying three coats of Matt enamel paint on Wall of approved make (ici / Jotun), shade and quality to finished surfaces at location shown on drawings or as directed by the Architect including rubbing the surface with sand paper/carborundum stone and making the surface smooth up to required height and level, including filling the depression with wall putty including primer coat of approved quality, scraping with sand paper, cleaning the surface, all to be done in strict accordance with the manufacturer's specification and conforming to the requirements of drawings, and to the entire satisfaction of the Project consultant. (For Payment Exposed area will be measured).				
	a) Matt Enamel Paint On Wall of Approved color	Sft	575		
17	Installation of chairs with driling floor, fixing ficher bolts with epoxy.				
	Installation of foldable chairs on floor in Auditorium Hall by using approved hardware's and fittings, complete job with all necessary fixing arrangements, all fixing hardware's, wastage, cutting, fabrication, welding, lifting, drilling, clipping, scaffolding, epoxy filler of approved brand, etc., complete in all respect as per drawings, specifications and as instructed by the Architect.	Nos	166		
10					
18	Veneer Pressed Wooden Hand Rail				
	Provide, making and install 6" high Veneer Polish finish Hand rail comprising of 5mm thick Oak Veneer polish finish pressed over rough wood framing (size 1-1/2"x1-1/2") structure fixed on top of plastered Brick wall of stairs with bolt. All wood should be seasoned and termite treated. Complete job with all fixing hardware, nail, glue, scaffolding, wastage, cutting, lifting etc., complete in all respect as per drawing / detail and as instructed by the architect. (For payment net Length will be measured)	Rft	26		
19	MS HAND RAIL				
	Providing and constructing MS Hand rail railing comprising 2"Ø handrail, 6" high 1/2" Ø Vertical solid bars @ 2ft c/c specing. All MS works to be treated with red oxide and 3 coats of Matt Enamel paint finished. Complete in all respect as per drawing, details and instruction by the Architect.	Rft	Rate only		

S.#	I.D Works - AUDITORIUM Description	Unit	Qty	Rate	Amount
20	3/4" dia Brass pipe hand rail with brass Cap & 1.5"x1.5" wooden molding Polish finish				
	Providing & fixing handrail of 3/4" dia Brass pipe with 1" dia brass cap fixed on existing wall with fixing of 1-1/2"x1-1/2" wooden molidng of solid Oak wood in polish finish, including all fixing accessories and arrangements, cutting, drilling where required, wastages, joints cleaning, etc. complete in all respect and as per drawings, details & directions of the Architect. (For Payment net Running lenght will be measured with-out depth & thickness)	Rft	Rate only		
21	Oak Wood Coping/Ledge				
	Providing, making & fixing Wooden Coping/Ledge in Polish finish, consisting of Solid Oak Wood (using proper seasoned and termite treated wood) coping/Ledge of required shape, size and thickness with making edging & nosing as shown in drawing fixed with approved adhesive, hardware, including all fixing accessories and arrangements, hardware's, wastages, joints cleaning, polishing with approved polish, lifting, cutting, solignum treatment to all surfaces of wood, etc. complete in all respect and as per drawings, details & directions of the Architect. (For Payment net Running length will be measured with-out depth & thickness)				
	a) Solid Oak Wood Coping/Ledge on planter wall in Polish finish Size 9" wide & 1-1/2" thick.	Rft	40		
В	Floor Finishes				
22	C.C Cast in situ 1:2:4 using fiber of approved size and weight				
	Provide and lay cast in situ work of C.C 1:2:4 cement concrete in any thickness and shape with smooth finished as per site specification and limitation, using approved quality cement, approved quality sand, approved quality crushed gravel including the cost of formwork, mixing. lifting, compacting, vibrating, curing, etc., including the cost of Fiber reinforcement of approved size and ratio, complete in all respect. (This job will be coordinated with all MEP works electrical, plumbing and air-conditioning, etc.)	Cft	50		

S.#	Description	Unit	Qty	Rate	Amount
23	C.C Flooring Base (Kacha)				
	Provide and lay 1:2:4 cement concrete flooring in any thickness, smooth finished in required depth as per site specification and limitation, laid in panels of approximately 2.5 SM Area, including shutting, curing, hacking of existing surface for bonding where necessary, etc., including the cost of Fiber reinforcement of approved size and ratio, complete in all respect. (This job will be coordinated with all MEP works electrical, plumbing and air-conditioning, etc.) (For Payment Net installed Flooring top area will be				
	measured without any depth and thickness)	Sft	2 1 4 7		
	a) 2.5" Thick (Avg.) C.C 1:2:4 Flooring Base (Kacha).	Sit	2,147		
24	3/4" thick Plaster Work on Wall/Vertical Surfaces of Floors & Platforms.				
	Provide and apply 1:4 cement sand plaster of minimum thickness as specified on RCC Members / Block Walls / Ceiling / vertical surfaces of floors, including making all grooves, edges, bends, corners, jambs of doors and windows / patta, & recesses finished smooth including G.I corner beads/plaster stops to all horizontal and vertical exposed corner edges (for protection of corner & edges), 1' wide galvanized metal lathe of 18 SWG at the junctions of concrete and block masonry, conduit chases, etc., fixed with nails and G.I. sheet strip/washer, rounded edges where required, drip core recesses and grove making smooth/foam finished in line, level, plumb, curing, scaffolding, hacking / chipping of existing surface for bonding where necessary, etc., complete in all respect. (For Payment exposed area will be measured) a) 3/4" thick Plaster Work on Wall/Vertical surfaces of floor.		311		
25	1/2" thick Self Leveling Compound Layer				
	Provide and laying 1/2" thick Self Leveling Compound Layer (F.Ball Red Bag U.K, Sika Level, Hardtop T100 SL, AQUAFIN or as approved) over existing C.C flooring (thickness may be vary as per required FFL), including hacking of existing surface for bonding where necessary, proper cleaning the existing surface before applying the layer, curing, wastage, etc. complete in all respect as per manufacturers specifications or as directed by the Architect. (This job will be coordinated with all MEP works electrical, plumbing and air-conditioning, etc.) (For Payment Net installed Flooring top area will be measured without any depth and thickness)	Sft	2,147		
	(Under Carpet & Vinyl Flooring)				

S.#	Description	Unit	Qty	Rate	Amount
26	Vinul Elegring On Stage (Ontion 1)				
20	Vinyl Flooring On Stage (Option - 1)				
	Providing & laying Vinyl Flooring of approved sample over				
	C.C flooring fixed with approved adhesive/bond in proper				
	manners, including cutting, lifting, wastage, cleaning,				
	including solid wooden edging, etc. complete in all respect as				
	per manufacturers specifications or as directed by the				
	Architect.				
	(For Payment Net installed Vinyl area will be measured)				
	a) Vinyl Flooring (V-01)	Sft	258		
	(Vinyl is OFM)				
27	Pre Finished Wooded Flooring On Stage (Option - 2)				
	Providing and laying Pre-Finished Wooden flooring of				
	approved sample with approved color, quality and make, laid				
	in approved pattern, setting the tiles with approved				
	adhesive, cutting of tile as per specified size & pattern as				
	shown in the drawings, cleaning, hacking / chipping of	Sft	Rate only		
	existing surface for bonding where necessary, etc. Complete	511	Rate only		
	in all respect and conforming to the requirements of				
	drawings, specification and to the entire satisfaction of the				
	Architect/Engineer.				
	(For Payment Net Wood tile area will be measured.)				
28	Carpet Flooring				
	Provide & lay in line and level Carpet of approved sample on				
	existing floor finish with approved adhesive, including				
	cutting, lifting, wastage, etc., complete in all respect, as per				
	drawing and instruction of the Architect.				
	(For Payment Net installed Carpet tile area will be measured)				
	a) Carpet Flooring (CT-01)	<b>C</b> th	2.050		
	(Carpet is OFM)	Sft	2,950		

S.#	Description	Unit	Qty	Rate	Amount
	M.S Light Cove Alongwith Floor Steps of Hall and Stage with				
29	HDF Toping				
	Providing, fabrication and fixing in position of M.S Cove Alongwith Floor Steps of Hall and Stage, consisting of M.S Angle/channel of approved shape, size and gauge fixed with existing steps of hall and stage with the support of approved hardware's and fittings, including applying two coats of anti rust coating of approved brand to all M.S work & painting to all MS work with approved paint, Colour & shade, 1/2" thick HDF fixing on top & front of M.S cove as shown in drawings, complete job with all necessary fixing arrangements, all hardware's, all hardware's, wastage, cutting, fabrication, welding, lifting, drilling, clipping, scaffolding, painting, epoxy filler of approved brand, etc., complete in all respect as per drawings, specifications and as instructed by the Architect. (For Payment Net weight of Installed M.S members will be measured (except hardware's and fittings) as per approved shop drawings and B.B.S.)	Rft	564		
С	Ceiling Finishes				
30	Gypsum Suspended False-Ceiling.				
	1/2" thick (Elephant brand, Thermec or equivalent) best quality gypsum sheet, fixed at required ceiling level hanged and supported with G.I framing system including the cost of galvanized iron adjustable clutch wire hanging system with lindapters, horizontal and vertical framework of approved material, fiber tape on joints, making (cove/Bulkheads/pelmet) of any size, shape & depth by using any approved material (MDF, HDF, Cement board, PU foam board of approved thickness), making provision of openings for all lights fixtures and providing aluminum flush band for protection of edges/corners where ever required as shown in detail drawing, applying three coats of Matt enamel paint on Wall of approved make (ICI / Berger/ Nippon), shade and quality to finished surfaces at location shown on drawings or as directed by the Architect including rubbing the surface with sand paper/carborundum stone and making the surface smooth up to required height and level, including filling the depression with wall putty including primer coat of approved quality, scraping with sand paper, cleaning the surface, complete job with all necessary fixing arrangements, all hardware's, lifting, cutting, making, fixing, scaffolding, tools, wastage, etc., as per drawing/detail, specifications and as directed by the Architects. (For payment only net horizontal surface area (L x B) will be	Sft	285		
	measured with out any depth and thickness)				
	(Ceiling Above Stage & Control room)				


S.#	Description	Unit	Qty	Rate	Amount
31	Acoustic Panel False Ceiling in Curved & Streight Shapes (Option-1)				
	Providing and installing in position Acoustic Panel False Ceiling in Curved & Streight shapes as per required design pattern, consisting of Acoustic Panels of approved brand with backing of 1/2" thick Plywood fixed at required ceiling level hanged and supported with G.I framing system including the cost of galvanized iron adjustable clutch wire hanging system with lindapters, horizontal and vertical framework of approved material, fiber tape on joints, making (cove/Bulkheads/pelmet) of any shape & size of same material, making provision of openings for all lights fixtures and providing aluminum flush band for protection of edges/corners where ever required as shown in detail drawing complete job with all necessary fixing arrangements, all hardware's, lifting, cutting, making, fixing, fabrication, welding, scaffolding, tools, wastage, etc., as per drawing/detail, specifications and as directed by the Architects. (Only Acoustic Panels are OFM) (For payment only net horizontal surface area (L x B) will be measured with out any depth and thickness)	Sft	1,733		

S.#	I.D Works - AUDITORIUM Description	Unit	Qty	Rate	Amount
	Fabric Finished False Ceiling in Curved & Streight Shapes				
32	(Option-2)				
	Providing and installing in position Fabric Panel False Ceiling				
	in Curved & Streight shapes as per required design pattern,				
	consisting of 1/2" thick Plywood with pasting of foam				
	cushioning of approved thickness (by Master foam) and				
	pasting of fabric (as per approved sample) on foam with				
	approved adhesive to all required surfaces of false ceiling,				
	including the cost of solignum treatment to all wood				
	surfaces, fixing of false ceiling at required ceiling level hanged				
	and supported with G.I framing system including the cost of				
	galvanized iron adjustable clutch wire hanging system with				
	lindapters, horizontal and vertical framework of approved				
	material, fiber tape on joints, making				
	(cove/Bulkheads/pelmet) of any shape & size of same	Sft	Rate only		
	material, making provision of openings for all lights fixtures				
	and providing aluminum flush band for protection of				
	edges/corners where ever required as shown in detail				
	drawing complete job with all necessary fixing arrangements,				
	all hardware's, lifting, cutting, making, fixing, fabrication,				
	welding, scaffolding, tools, wastage, etc., as per				
	drawing/detail, specifications and as directed by the				
	Architects.				
	(Base Rate of Fabric Panel Rs.300/- Per Sft)				
	(For payment only net horizontal surface area (L x B) will be				
	measured with out any depth and thickness)				
33	Drop Beam of Cement Board/MDF				
	Providing, making and fixing Drop Beam, using MDF				
	board/Cement board of specified thickness of approved				
	brand on both side of M.S Internal framing system of min. 14				
	SWG or as approved, closing bottom side of beam and all end				
	openings with same cladding material, fixing of frame				
	tie/hanged with structural slab/beam, including all fixing				
	accessories and arrangements, scaffolding, making openings,				
	cutting of electric switch board etc., as shown in drawing $\&$				
	details, complete in all respect and as instructed by the				
	Architect.				
	(This job will be coordinated with electrical/plumbing and air-				
	conditioning works.)				
	Note:- "No additional payment will be provided for strengthening the				
	internal reinforcement or framing of any size or gauge, anywhere on-site,				
	for any reason."				
	a) 4" thick drop beam of 1/2" thick Cement board of				
	approved brand (From SCG, Eltoro, or equivalent) (For Payment exposed Cladding area will be measured	Sft	86		
	without any depth and thickness).				
					I

S.#	Description	Unit	Qty	Rate	Amount
	<ul> <li>b) 4" thick drop beam in curved shape of 1/2" thick MDF board of approved brand (From ZRK, Merbok, Alnoor, Lasani or equivalent)</li> <li>(For Payment exposed Cladding area will be measured without any depth and thickness).</li> </ul>	Sft	Rate only		
34	Suspended M.S Framing For Projector				
	Providing, fabrication and fixing in position of suspended M.S Framing hanged with ceiling for Projector, consisting of M.S pipe framing structure of approved size and gauge fixed/hanged with existing RCC ceiling from top with the support of approved hardware's and fittings, including applying two coats of anti rust coating of approved brand to all M.S work & painting to all MS work with approved paint, Colour & shade, complete job with all necessary fixing arrangements, all hardware's, all hardware's, wastage, cutting, fabrication, welding, lifting, drilling, clipping, scaffolding, painting, epoxy filler of approved brand, etc., complete in all respect as per drawings, specifications and as instructed by the Architect. (For Payment Net weight of complete structure will be measured as per approved shop drawings and BBS)	Kg	32		
	Total Rs.				

# NAJMI BILGRAMI COLLABORATIVE (PVT)LTD

14-C, Lane 7, Main Kh-e-Bukhari Commercial, Phase - VI, D.O.H.A, Karachi, Pakistan. T +92-21-35242629,35242642,35857957, 35857990 F +92-21-35857986 W www.najmibilgrami.com



# **UIT UNIVERSITY AUDITORIUM**



# **TENDER DRAWINGS**

20-06-2025

# 

Η

## REGISTER OF DRAWINGS AND ISSUE

# NAJM BLGRAM COLLABORATIVE (PVT)LTD

THE FOLLOWING DRAWINGS ARE ATTACHED (check and advise sender if a


## Interior Design

0	
DRAWING NO.	DRAWING TITLE :
I-0.01	Title Sheet
I-0.02	List of Drawing
MASTER PLANS	
I-1.0.01	Master Plan
GENERAL ARRANGEME	NT PLANS (AUDITORIUM)
I-1.1.01	Conorol Arrangement Plan (Auditorium
1-1.1.01	General Arrangement Plan (Auditorium
DIMENSION PLAN (AUDI	
I-1.2.01	Dimension & Wall Finishes Plan (Audito
FURNITURE LAYOUT PL	AN (AUDITORIUM)
I-1.3.01	Furniture layout Plan (Auditorium)
I-1.3.02	Furniture layout Plan (Auditorium)
FIX FINISHES PLAN (AU	DITORIUM)
I-1.4.01	Fix Finishes Plan (Auditorium)
REFLECTED CEILING PL	AN (AUDITORIUM)
I-1.5.01	Reflected Ceiling Plan (Auditorium)
GENERAL ARRANGEME	NT PLANS (BACK ALLY)
I-1.1.02	Conoral Arrangement Plan (Back Ally)
1-1.1.02	General Arrangement Plan (Back Ally)
INTERIOR ELEVATIONS	
I-2.01	Building Elevation - A & B
I-2.02	Building Elevation - C & D
MISCELLANEOUS DETA	LS
I-3.01	Miscellaneous Details
I-3.02	Miscellaneous Details
I-3.03	Miscellaneous Details
I-3.04	Miscellaneous Details
DOOR DETAIL	
I-4.01	Door Detail

ALL DE**SIGNE**: AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.


	Project Name :	UIT	UN	IVEF	RSIT	Y AL	JDIT	ORIL	JM, ł	(AR/	ACH	<u> </u>	
	Project No. :	I-C	0-28	803-U	IT U	NIVE	RSIT	Υ					
any missing)		DATE		ISSUF	•								
					•								
		05-06-2025											
	SCALE :	REVIS	SION	S	I					1			
	N.T.S.												
	N.T.S.												
	3/16"												
	1/4"												
						<u> </u>	<u> </u>	<u> </u>					
rium)	1/4"												
,													
	1/4"           1/4"												
	4 (4)												
	1/4"												
	1/4"												
	1/4"												
	1/4"           1/4"												
	AS SHOWN AS SHOWN												
	AS SHOWN AS SHOWN												
	AS SHOWN												
	· · ·			-			-						

		erence to Finish		
AA		erence to Finish ecification.		Reference to Elevation Drawing. —Elevation Reference
		ex Reference sh Reference	-1.00	Drawing No. Zone Reference
		erence to tail Drawing.	$\bigcirc$	
		tail No. Iwing No.		
		erence.		
WALL L	ECEND			
<u>88</u>		Existing Wall		Structural Column
		Curtain Wall		△ Partition Wall
		Fixed Glazing		Proposed Wall
	RAL NOTE			
STRU	CTURAL, MEP	P, FURNITURE, CEIL		CHITECTURAL, TRE SAFETY, AND ALL AND DETAIL DOCUMENT
CONT PRIO	RACTOR MUS	ST VERIFY ALL DIM NCEMENT OF ANY	ENSIONS, LEVELS, A WORK. ANY DISCR	AND SITE CONDITIONS EPANCIES, OMISSIONS, C
CLAR	IFICATION AN	& CLARIFICATION	DRE PROCEEDING.	THE ARCHITECT FOR
IN TH THE S	E EVENT THA	T A CONSTRUCTIO SIBILITY OF THE CO	N DETAIL IS NOT SHONTRACTOR TO REC	IOWN OR PROVIDED, IT I QUEST THE REQUIRED
EXEC	UTION SHALL	NOT BE USED AS A	A BASIS FOR ANY CL	ICH DETAILS PRIOR TO AIMS OR EXTENSIONS OI ONSIDERED A VALID
EXCU 3. LEAK	SE. AGE PREVENT	TION & WATERPRO	DOFING	
SPEC	FIED WATERF	PROOFING SYSTEM	IS. CONTRACTOR TO	NES TO BE TREATED WITH O ENSURE NO LEAKAGE NCLUDING POND TESTS
WHE ARCH	RE APPLICABL IITECT/CONSU	E) MUST BE COND	UCTED AND VERIFI	
ALL V		FACES TO BE TREA	TED WITH ANTI-TE SITE DELIVERY OR	RMITE SOLUTION AND
DOCL PROD	JMENTED PRO OUCT DATA SH	DOF OF TREATMEN HEETS) TO BE SUBN	IT APPLICATION (IN /IITTED FOR APPRO	ICLUDING MSDS AND VAL. UNTREATED OR
CONT	OPERLY TREA RACTOR'S RE SED METAL E	SPONSBILITY	SE REJECTED AND R	EPLACEMENT SHALL BE
ALL E FITTI	XPOSED MET	AL SURFACES (INC TURES) TO BE COA	TED WITH ANTI-RU	AL, JOINERY SUPPORTS, IST PRIMER AND FINISH
TO BE		ROVED SAMPLE AN		TIONS. FINAL PAINT FINIS ECTS SUCH AS PEELING,
6. HAZA NO H	AZARDOUS, S	ERIALS & SAFETY I HARP, TOXIC, OR I	NFLAMMABLE MAT	TERIALS ARE TO BE LEFT
NON-	COMBUSTIBL	E (UNLESS SPECIFI	IT. ALL MATERIALS ED OTHERWISE), CI I LOCAL HEALTH, SA	HILD-SAFE (WHERE
ENVI SUBN	RONMENTAL S	STANDARDS. CERT RT OF HANDOVER.	IFICATES OF CONFO	
ALL C	ONSTRUCTIO			COMPLIANCE WITH LOCA
PERS0 CONT	ONAL PROTEC	CTIVE EQUIPMENT ENSURE BARRICAD	(PPE) IS MANDATC ING, SAFETY SIGNA	ORY FOR ALL WORKERS. AGE, FIRE EXTINGUISHERS
8. APPR	OVALS & MO			AND APPROVED PRIOR T
MASS	EXECUTION.	ANY WORK CARRI RIALS, COLOURS, S	ED OUT WITHOUT AMPLES, AND JOIN	
9. DRAV	VING UPDATE	TION AT THE CONT ES & RECORD KEEF MAINTAIN A PRINT	PING	
GOOI ADJU	D-FOR-CONST STMENTS TO	RUCTION DRAWIN BE NOTED AND SH	IGS ON SITE. ANY N IARED WITH ARCHI	MARK-UP OR REDLINE ITECT ON WEEKLY BASIS.
10. STA	NDARDS & D	OCUMENTATION	OVIDED AT PROJEC	I CLOSEOUT.
	ΛΔΤΕΡΙΔΙ 5 ΔΝ			FRE TO MANUFACTURER
GUID REFEI	ELINES AND C R TO THE PRO	CONSTRUCTION IN	DUSTRY BEST PRAC	
GUID REFEI STAN	ELINES AND C R TO THE PRO DARDS. LATES	CONSTRUCTION IN DIECT SPECIFICATION	DUSTRY BEST PRAC	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND
GUID REFEI STAN	ELINES AND C R TO THE PRO DARDS. LATE:	CONSTRUCTION IN DIECT SPECIFICATION	DUSTRY BEST PRAC IN MANUAL FOR AI (R DATASHEETS, M: PT ON SITE FOR REI	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND
	ELINES AND C R TO THE PRO DARDS. LATE:	CONSTRUCTION IN DIECT SPECIFICATIC ST MANUFACTURE IDELINES TO BE KE	DUSTRY BEST PRAC IN MANUAL FOR AI (R DATASHEETS, M: PT ON SITE FOR REI	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND
	ELINES AND C R TO THE PRO DARDS. LATE:	CONSTRUCTION IN DIECT SPECIFICATIC ST MANUFACTURE IDELINES TO BE KE	DUSTRY BEST PRAC IN MANUAL FOR AI (R DATASHEETS, M: PT ON SITE FOR REI	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND
	DNS	CONSTRUCTION IN DIECT SPECIFICATIC ST MANUFACTURE IDELINES TO BE KE	DUSTRY BEST PRAC IN MANUAL FOR AI (R DATASHEETS, M: PT ON SITE FOR REI	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND
GUID REFEI STAN INSTA	DNS Date	Descrip	DUSTRY BEST PRAC IN MANUAL FOR AI (R DATASHEETS, M: PT ON SITE FOR REI	TICES. CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
GUID REFEI STAN INSTA	DNS Date	Descrip	DUSTRY BEST PRAC ON MANUAL FOR AI (R DATASHEETS, M: PT ON SITE FOR REP ON SITE FOR REP	TICES. CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
GUID REFEI STAN INSTA	DNS Date	Descrip		TICES. CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
GUID REFEI STAN INSTA	DNS Date	Descrip		TICES: CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
GUID REFEI STAN INSTA	DNS Date	Descrip		TICES: CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
GUID REFEI STAN INSTA	DNS Date	Descrip		TICES: CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
GUID REFEI STAN INSTA	DNS Date	Descrip		TICES: CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
GUID REFEI STAN INSTA	DNS Date UIT UI	Descrip	DUSTRY BEST PRAC IN MANUAL FOR AL IN MANUAL FOR AL FIT ON SITE FOR REF	TICES: CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
GUID REFEI STAN INSTA	DNS Date UIT UI UIT UI	Descrip	DUSTRY BEST PRAC IN MANUAL FOR AL IN MANUAL FOR AL FIT ON SITE FOR REF	TICES. CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
GUID REFEI STAN INSTA	DNS Date UIT UI		DUSTRY BEST PRAC DN MANUAL FOR AL IN MANUAL FOR AL PT ON SITE FOR REF PT ON SITE FOR PT ON SITE FOR REF PT ON SITE FOR PT ON SITE FOR REF PT ON SITE FOR PT ON SITE FOR PT ON SITE FOR REF PT ON SITE FOR PT	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND FERENCE. TORIUM,
GUID REFEI STAN INSTA	DNS Date Date UIT UI	Descrip Descri	DUSTRY BEST PRAC DN MANUAL FOR AN IR DATASHEETS, MI PT ON SITE FOR REF DT ON SITE FOR REF DT AUDIT CACHI.	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND FERENCE. TORIUM,
GUID REFEI STAN INSTA	DNS Date Date UIT UI UIT UI	Descrip Descri	DUSTRY BEST PRAC DN MANUAL FOR AN IR DATASHEETS, MI PT ON SITE FOR REF DT ON SITE FOR REF DT AUDIT CACHI.	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND FERENCE. TORIUM,
GUID REFEI STAN INSTA	DNS Date Date UIT UI UIT UI	Descrip Descri	DUSTRY BEST PRAC DN MANUAL FOR AN IR DATASHEETS, MI PT ON SITE FOR REF DT ON SITE FOR REF DT AUDIT CACHI.	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND FERENCE. TORIUM,
GUID REFEI STAN INSTA	DNS Date Date UIT UI UIT UI	Descrip Descri	DUSTRY BEST PRAC DN MANUAL FOR AN IR DATASHEETS, MI PT ON SITE FOR REF DT ON SITE FOR REF DT AUDIT CACHI.	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND FERENCE. TORIUM,
GUID REFEI STAN INSTA	DNS Date Date UIT UI UIT UI	Descrip Descri	DUSTRY BEST PRAC DN MANUAL FOR AN IR DATASHEETS, MI PT ON SITE FOR REF DT ON SITE FOR REF DT AUDIT CACHI.	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND FERENCE. TORIUM,
GUID REFEI STAN INSTA	DNS Date Date UIT UI UIT UI	Descrip Descri	DUSTRY BEST PRAC DN MANUAL FOR AN IR DATASHEETS, MI PT ON SITE FOR REF DT ON SITE FOR REF DT AUDIT CACHI.	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND FERENCE. TORIUM,
GUID REFEI STAN INSTA	DNS Date Date UIT UI UIT UI	Descrip Descri	DUSTRY BEST PRAC DN MANUAL FOR AN IR DATASHEETS, MI PT ON SITE FOR REF DT ON SITE FOR REF DT AUDIT CACHI.	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND FERENCE. TORIUM,
REVISION No.	DNS Date Date UIT UI UIT UI	Descrip Descri	DUSTRY BEST PRAC DN MANUAL FOR AN IR DATASHEETS, MI PT ON SITE FOR REF DT ON SITE FOR REF DT AUDIT CACHI.	TICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND FERENCE. TORIUM,
REVISION No.	DNS Date Date Content Date Date Date Date Date Date Date Dat	Descrip Descri	etion	TICES. CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
REVISION No.	DNS Date Date Content Date Date Date Date Date Date Date Dat	Descrip Descri	DUSTRY BEST PRAC DN MANUAL FOR AN IR DATASHEETS, MI PT ON SITE FOR REF DT ON SITE FOR REF DT AUDIT CACHI.	TICES. CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
REVISION No. Job Title	DNS Date Date Content Date Date Date Date Date Date Date Dat	Descrip Descri	etion  TY AUDIT ACHI.  CRAWIN  T CORAWIN  T	TICES. CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
REVISION No.	DNS Date Date Content Date Date Date Date Date Date Date Dat	Descrip Descri	etion  TY AUDIT ACHI.  CRAWIN  T CORAWIN  T	TICES. CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
REVISIC No. JOb Title Des STA	DNS Date Date Date Control Control Date Date Control Control Date Control Date Date Control Date Control Date Control Control Date Control Date Control Date Control C	Descrip	etion  TY AUDIT ACHI.  CRAWIN  T CORAWIN  T	TICES. CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.
REVISIC No. JOD Title	DNS Date DNS Date UIT UI G G G G G G G G G G G G G G G G G G G	Descrip	etion  TY AUDIT ACHI.  CRAWIN  T CORAWIN  T	TICES. CONTRACTOR TO LI TECHNICAL SDS, FIRE RATINGS, AND FERENCE.




ALL DESIGNE: AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.

	Ref	erence to Finishe		Reference to
		ecification.		Elevation Drawing. -Elevation Reference
		ex Reference sh Reference	I-1.00	Drawing No. –Zone Reference
		erence to ail Drawing.		
		ail No. wing No.		
	Ref	erence.		
L WALL L	EGEND			
Ers	চা চার্ডার প্রাণ্ট	Eviating Wall		Structural Column
		Existing Wall Curtain Wall		Structural Column
		Fixed Glazing		<ul> <li>Partition vvali</li> </ul>
				x Hoposod Han
GENE	RAL NOTE	S		
1. COOF	RDINATION &	VERIFICATION		
STRU	CTURAL, MEP	, FURNITURE, CEIL		CHITECTURAL, IRE SAFETY, AND ALL AND DETAIL DOCUMENTS
PRIO	R TO COMME	NCEMENT OF ANY	WORK. ANY DISCRE	ND SITE CONDITIONS EPANCIES, OMISSIONS, OI THE ARCHITECT FOR
CLAR	IFICATION AN	D DIRECTION BEFO	DRE PROCEEDING.	
THE S	SOLE RESPONS	SIBILITY OF THE CO	NTRACTOR TO REC	OWN OR PROVIDED, IT IS QUEST THE REQUIRED CH DETAILS PRIOR TO
EXEC TIME	UTION SHALL . "NOT AWAR	NOT BE USED AS A	BASIS FOR ANY CL	AIMS OR EXTENSIONS OF DISIDERED A VALID
	AGE PREVENT			
SPECI POIN	IFIED WATERF TS ARE LEFT U	PROOFING SYSTEN INSEALED. MOCK-	IS. CONTRACTOR TO UP AND TESTING (IN	IES TO BE TREATED WITH DENSURE NO LEAKAGE NCLUDING POND TESTS
WHE ARCH	RE APPLICABL IITECT/CONSU	E) MUST BE COND	UCTED AND VERIFIE	
ALL V		FACES TO BE TREA	TED WITH ANTI-TEF	RMITE SOLUTION AND
DOCL PROD	JMENTED PRO DUCT DATA SH	DOF OF TREATMEN IEETS) TO BE SUBN	IT APPLICATION (IN 1ITTED FOR APPROV	CLUDING MSDS AND /AL. UNTREATED OR
CONT	OPERLY TREA TRACTOR'S RE	SPONSBILITY	de rejeuied AND Ri	EPLACEMENT SHALL BE
ALL E FITTI	XPOSED MET NGS, AND FIX	AL SURFACES (INC TURES) TO BE COA	TED WITH ANTI-RU	AL, JOINERY SUPPORTS, ST PRIMER AND FINISH
TO BE		ROVED SAMPLE AN		TONS. FINAL PAINT FINISI
6. HAZA NO H	ARDOUS MAT	ERIALS & SAFETY F HARP, TOXIC, OR I	NFLAMMABLE MAT	ERIALS ARE TO BE LEFT
NON-	COMBUSTIBL	E (UNLESS SPECIFI	IT. ALL MATERIALS <sup>-</sup> ED OTHERWISE), CH I LOCAL HEALTH, SA	HILD-SAFE (WHERE
ENVI SUBN	RONMENTAL S	STANDARDS. CERT RT OF HANDOVER.	IFICATES OF CONFC	
ALL C	ONSTRUCTIO			COMPLIANCE WITH LOCA REQUIREMENTS.
PERS0 CONT	ONAL PROTEC	TIVE EQUIPMENT	(PPE) IS MANDATO ING, SAFETY SIGNA	RY FOR ALL WORKERS. GE, FIRE EXTINGUISHERS,
8. APPR	OVALS & MO	CK-UPS		AND APPROVED PRIOR TO
INCLU	JDING MATER			PRIOR APPROVAL, ERY DETAILS, SHALL BE
9. DRAV	WING UPDATE	ES & RECORD KEEF	ING	
GOOI ADJU	D-FOR-CONST STMENTS TO	RUCTION DRAWIN BE NOTED AND SH	IGS ON SITE. ANY M	IARK-UP OR REDLINE TECT ON WEEKLY BASIS.
10. STA	NDARDS & D	OCUMENTATION		ERE TO MANUFACTURER
REFE	R TO THE PRO	JECT SPECIFICATIO	N MANUAL FOR AL	TICES. CONTRACTOR TO L TECHNICAL DS, FIRE RATINGS, AND
			PT ON SITE FOR REF	
REVISIO	DNS			
REVISIO No.	DNS Date	Descrip	tion	
	1	Descrip	tion	
	1	Descrip	tion	
	Date	Descrip	ition	
No.	Date			ORIUM,
No.	Date	NIVERSI		ORIUM,
No.	Date	NIVERSI	TY AUDIT	ORIUM,
No.	Date	NIVERSI	TY AUDIT ACHI.	ORIUM,
No.	Date	NIVERSI	TY AUDIT	ORIUM,
<sub>No.</sub> Job	Date	NIVERSI KAF	ry audit Rachi. R Plan	ORIUM,
<sub>No.</sub> Job	Date	NIVERSI	ry audit Rachi. R Plan	ORIUM,
No. Job Title	Date UIT UI	NIVERSI KAR MASTE	er plan	ORIUM,
No. Job Title	Date Date		TY AUDIT PACHI. ER PLAN	
No. Job Title	Date UIT UI : ign Co NA BII		er plan	I
No. Job Title	Date Date	NIVERSIT KAR MASTE Onsultant	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E E E E E E E	Т тр
No. Job Title	Date	MASTE	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E E E E E E E	Т тр
No. Job Title	Date	NIVERSI KAR MASTE Onsultant	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E E E E E E E	Т тр
No. Job Title	Date	MASTE	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E E E E E E E	Т тр
No. Job Title	Date	MASTE	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E E E E E E E	Т тр
No. Job Title	Date	MASTE	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E E E E E E E	Т тр
No. Job Title	Date	MASTE	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E E E E E E E	Т тр
No. Job Title Des	Date	MASTE	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E E E E E E E	Т тр
No. Job Title Des	Date	MASTE	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E E E E E E E	Т тр
No. Job Title Des	Date	NIVERSI KAR MASTE Onsultant JIVI BORAT Kh-Bukhari Commerc JS24242,35857957, 3 amicom sultant :	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E E E E E E E	TD rD (arachi, Pakistan.
No. Job Title Des	Date	NIVERSI KAR MASTE Onsultant JIVI BORAT Kh-Bukhari Commerc JS24242,35857957, 3 amicom sultant :	FY AUDIT ACHI. ER PLAN : : ER PLAN : : ER PLAN : : : : : : : : : : : : : : : : : : :	TD rD (arachi, Pakistan.
No.	Date	NIVERSI KAR MASTE Onsultant JIVI BORAT Kh-Bukhari Commerc JS24242,35857957, 3 amicom sultant :	FY AUDIT ACHI. ER PLAN : : ER PLAN : : ER PLAN : : : : : : : : : : : : : : : : : : :	TD rD (arachi, Pakistan.
No. Job Title Des MEI	Date Date UIT UI : UIT UI : : DIT UI : : DIT UI : : : : : : : : : : : : : : : : : : :	NIVERSI KAR MASTE Onsultant JIVI BORAT Kh-Bukhari Commerc J35242642,35857957, 3 amicom sultant :	FY AUDIT ACHI. ER PLAN : : ER PLAN : : ER PLAN : : : : : : : : : : : : : : : : : : :	TD starachi, Pakistan.
No. Job Title Des C MEI	Date Date	NIVERSITKAR MASTE ONSULTANT JIVI BORAT SULTANT : NDER	TY AUDIT ACHI. ER PLAN T : E E E E E E E E E E E E E	TD starachi, Pakistan.
No. Job Title Des C MEI	Date Date	NIVERSIT KAF	TY AUDIT ACHI. TR PLAN T: E E E E E E E E E E E E E	TD starachi, Pakistan.




ALL DE SNOTE: AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.

	Def			Peference to
		erence to Finish ecification.	es A	Reference to Elevation Drawing.
		ex Reference sh Reference	(I-1.00)	-Elevation Reference Drawing No. -Zone Reference
		erence to ail Drawing.		-zone kelerence
		ail No. wing No.		
	~/	erence.		
WALL LE	EGEND			
385		Existing Wall		Structural Column
		Curtain Wall		Cement Board Partition Wall
		Fixed Glazing		Proposed Wall
GENEF	RAL NOTE	S		
ALL DF	RAWINGS TO		UNCTION WITH ARC	
SPECIA	LIST CONSU	LTANT DRAWINGS	5, SPECIFICATIONS, A	RE SAFETY, AND ALL AND DETAIL DOCUMENTS ND SITE CONDITIONS
CONFL	ICTS SHALL	BE BROUGHT TO T	WORK. ANY DISCRE HE ATTENTION OF T DRE PROCEEDING.	PANCIES, OMISSIONS, O HE ARCHITECT FOR
2. MISSI	NG DETAILS	& CLARIFICATIONS	5	OWN OR PROVIDED, IT IS
DETAI	L FROM THE	ARCHITECT. FAILU	IRE TO REQUEST SUG	UEST THE REQUIRED CH DETAILS PRIOR TO AIMS OR EXTENSIONS OF
	"NOT AWAR		/N" WILL NOT BE CO	
ALL W	ET AREAS, RO		S, AND SERVICE ZON	ES TO BE TREATED WITH
POINT	S ARE LEFT L	INSEALED. MOCK-		ENSURE NO LEAKAGE ICLUDING POND TESTS D BY THE
ARCHI 4. WOOI	TECT/CONSU DEN ELEMEN	JLTANT PRIOR TO	COVERING.	
ALL W FIRE-R	OODEN SUR ETARDANT C	FACES TO BE TREA COATING PRIOR TO	O SITE DELIVERY OR I	MITE SOLUTION AND NSTALLATION. CLUDING MSDS AND
PRODU IMPRC	JCT DATA SH DPERLY TREA	IEETS) TO BE SUBI TED WOOD WILL I	MITTED FOR APPROV	
5. EXPOS	ED METAL E			
FITTIN COAT	GS, AND FIX <sup>-</sup> SUITABLE TO	TURES) TO BE COA SPECIFIED ENVIR	TED WITH ANTI-RUS	AL, JOINERY SUPPORTS, ST PRIMER AND FINISH IONS. FINAL PAINT FINISI
TO BE RUST,	AS PER APPF OR DISCOLO	ROVED SAMPLE AN RATION.	ID FREE FROM DEFE	CTS SUCH AS PEELING,
NO HA	ZARDOUS, S			ERIALS ARE TO BE LEFT O BE
NON-C	COMBUSTIBL CABLE), AND	E (UNLESS SPECIFI COMPLIANT WITH	ED OTHERWISE), CH I LOCAL HEALTH, SA IFICATES OF CONFO	ILD-SAFE (WHERE FETY, AND
SUBM	ITTED AS PAI	RT OF HANDOVER.		RMANCE TO BE
ALL CO BUILD	ONSTRUCTIO	N WORKS SHALL E OSHA STANDARDS	BE CARRIED OUT IN C 5, AND SITE SAFETY R	
CONTR	RACTOR TO E		ING, SAFETY SIGNAG	RY FOR ALL WORKERS. GE, FIRE EXTINGUISHERS,
8. APPRO	OVALS & MO	CK-UPS		AND APPROVED PRIOR TO
INCLU	DING MATER			RIOR APPROVAL, RY DETAILS, SHALL BE
9. DRAW	ING UPDATE	ES & RECORD KEEI		
GOOD ADJUS	-FOR-CONST TMENTS TO	RUCTION DRAWIN BE NOTED AND SI	IGS ON SITE. ANY M	ARK-UP OR REDLINE ECT ON WEEKLY BASIS.
10. STA	NDARDS & D	OCUMENTATION		RE TO MANUFACTURER'
GUIDE REFER	LINES AND C TO THE PRO	ONSTRUCTION IN	DUSTRY BEST PRACT	TICES. CONTRACTOR TO
			PT ON SITE FOR REF	DS, FIRE RATINGS, AND ERENCE.
REVISIO	NS			
REVISIO No.	NS Date	Descriț	otion	
		Descrip	otion	
No.	Date	Descrip	otion	
	Date	Descriț	otion	
No.	Date :	NIVERSI		ORIUM,
No.	Date :	NIVERSI		ORIUM,
No.	Date : UIT UI	NIVERSI		ORIUM,
No. Job	Date : UIT UI :	NIVERSI	TY AUDIT( RACHI.	
No. Job	Date : UIT UI : NERA		TY AUDIT( RACHI.	ENT PLAN
No. Job Title	Date : UIT UI : NERA (	NIVERSI KAF	TY AUDIT RACHI. ANGEME ID FLOO	ENT PLAN
No. Job Title	Date : UIT UI : NERA (		TY AUDIT RACHI. ANGEME ID FLOO	ENT PLAN
No. Job Title GE	Date : UIT UI : : NERA ( gn Co	NIVERSI KAF	TY AUDIT RACHI. NGEME D FLOO	ENT PLAN
No. Job Title GE Desi	Date : UIT UI : :NERA ( gn Co	NIVERSI KAF AL ARRA GROUN onsultan	TY AUDIT RACHI. NGEME D FLOO t :	ENT PLAN R
No. Job Title GE Desi	Date : UIT UI : : : : : : : : : : : : : : : : : : :	NIVERSI KAF GROUN onsultan	TY AUDIT RACHI. NGEME D FLOO	ENT PLAN R
No. Job Title GE Desi C I	Date : UIT UI : NERA ( ) SIL A C, Lane 7, Main	NIVERSI KAF	TY AUDITO RACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R
No. Job Title GE Desi C I I I	Date	NIVERSI KAF	TY AUDITO RACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R
No. Job Title GE Desi C I I I	Date	NIVERSI KAF	TY AUDITO RACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R
No. Job Title GE Desi C I I I	Date	NIVERSI KAF	TY AUDITO RACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R
No. Job Title GE Desi C I I I	Date	NIVERSI KAF	TY AUDITO RACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R
No. Job Title GE Desi C I I I	Date	NIVERSI KAF	TY AUDITO RACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R
No. Job Title GE Desi C I I I	Date	NIVERSI KAF	TY AUDITO RACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R
No. Job Title GE Desi C C MEF	Date	NIVERSI KAF	TY AUDITO RACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R
No. Job Title GE Desi C I I I	Date	NIVERSI KAF	TY AUDITO RACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R
No. Job Title GE Desi C C MEF	Date	NIVERSI KAF	TY AUDITO RACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R I I arachi, Pakistan.
No. Job Title GE Desi C C MEF	Date	NIVERSI KAF	TY AUDIT ACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R I I arachi, Pakistan.
No. Job Title GE Desi C C MEF	Date	NIVERSI KAF	TY AUDIT ACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R I I arachi, Pakistan.
No. Job Title GE Desi C MEF	Date	NIVERSI KAF AL ARRA GROUN onsultan JIN Borat Khe-Buthat Commerce 35242642,35857957, 3 amicom sultant :	TY AUDIT ACHI. ANGEME ID FLOO t : E E E E E E E E E E E E E E E E E E E	ENT PLAN R T T arachi, Pakistan.
No. Job Title GE Desi Job MEF	Date  Date Date	NIVERSI KAF AL ARRA GROUN onsultan JINI BORAT Sultant : NDER	TY AUDIT ACHI. ANGEME ID FLOO t : <b>EXIVE</b> IV E (PYT) L Idl Phase - VI, D.O.H.A, K 35857990 DRAWIN	ENT PLAN R T T arachi, Pakistan.
No. Job Title GE Desi C MEF	Date  Date Date	NIVERSI KAF	TY AUDITO ACHI. ANGEME ID FLOO t : <b>EATVE</b> IVE (PVT)L IJ, Phase -VI, D.O.H.A, K S5857990 DRAWIN	ENT PLAN R TD arachi, Pakistan.



ALL DE SNOTE: AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.

AA				Reference to
L'	000 Specif	ence to Finish lication.		Elevation Drawing. —Elevation Reference
		Reference Reference	I-1.00	<ul> <li>Drawing No.</li> <li>Zone Reference</li> </ul>
		ence to Drawing.		
	Detail			
	Refere	ence.		
WALL LE	GEND			
		xisting Wall		Structural Column
		urtain Wall		Partition Wall
		nou oldeling		
	RAL NOTES	RIFICATION		
STRUC	TURAL, MEP, F	URNITURE, CEII		RCHITECTURAL, FIRE SAFETY, AND ALL AND DETAIL DOCUMENTS
CONTI PRIOR	RACTOR MUST \ TO COMMENCI	/ERIFY ALL DIM EMENT OF ANY	ENSIONS, LEVELS, WORK. ANY DISCF	AND SITE CONDITIONS REPANCIES, OMISSIONS, O THE ARCHITECT FOR
CLARI		DIRECTION BEF	ORE PROCEEDING.	THE ARCHITECT FOR
IN THE THE SO	EVENT THAT A	CONSTRUCTIO	N DETAIL IS NOT SHONT REPORT	HOWN OR PROVIDED, IT IS QUEST THE REQUIRED
EXECU	ITION SHALL NO	T BE USED AS A	A BASIS FOR ANY C	JCH DETAILS PRIOR TO LAIMS OR EXTENSIONS OF ONSIDERED A VALID
	GE PREVENTIO			
SPECIF	IED WATERPRC	OFING SYSTEM	IS. CONTRACTOR T	NES TO BE TREATED WITH O ENSURE NO LEAKAGE INCLUDING POND TESTS
WHER ARCHI	E APPLICABLE) I TECT/CONSULT	MUST BE COND	UCTED AND VERIF	
ALL W			TED WITH ANTI-TE SITE DELIVERY OR	RMITE SOLUTION AND
DOCU PRODU	MENTED PROOF JCT DATA SHEE	F OF TREATMEN TS) TO BE SUBN	IT APPLICATION (II NITTED FOR APPRO	NCLUDING MSDS AND WAL. UNTREATED OR
CONT	DPERLY TREATED RACTOR'S RESPO SED METAL ELEN	ONSBILITY	SE NEJECTED AND F	REPLACEMENT SHALL BE
ALL EX FITTIN	(POSED METAL : GS, AND FIXTUR	SURFACES (INC RES) TO BE COA	TED WITH ANTI-RU	RAL, JOINERY SUPPORTS, JST PRIMER AND FINISH
TO BE		/ED SAMPLE AN		ITIONS. FINAL PAINT FINIS ECTS SUCH AS PEELING,
6. HAZAF NO HA	R <b>DOUS MATERI</b> ZARDOUS, SHA	ALS & SAFETY I RP, TOXIC, OR I	NFLAMMABLE MA	TERIALS ARE TO BE LEFT
NON-C APPLIC	COMBUSTIBLE (I CABLE), AND CO	UNLESS SPECIFI	LOCAL HEALTH, S	CHILD-SAFE (WHERE AFETY, AND
ENVIR SUBM	ONMENTAL STA	NDARDS. CERT OF HANDOVER.	IFICATES OF CONF	
ALL CO		VORKS SHALL B		COMPLIANCE WITH LOCA REQUIREMENTS.
PERSO CONT	NAL PROTECTIV	/E EQUIPMENT URE BARRICAD	(PPE) IS MANDATO ING, SAFETY SIGNA	ORY FOR ALL WORKERS. AGE, FIRE EXTINGUISHERS
8. APPRO	OVALS & MOCK	-UPS		AND APPROVED PRIOR T
INCLU		LS, COLOURS, S	AMPLES, AND JOIN	PRIOR APPROVAL, IERY DETAILS, SHALL BE
9. DRAW	ING UPDATES 8	& RECORD KEEF		
GOOD ADJUS	-FOR-CONSTRU STMENTS TO BE	CTION DRAWIN NOTED AND SH	IGS ON SITE. ANY M	MARK-UP OR REDLINE ITECT ON WEEKLY BASIS. CT CLOSEOUT.
10. STA	NDARDS & DOC	UMENTATION		IERE TO MANUFACTURER
GUIDE REFER	LINES AND CON TO THE PROJEC	ISTRUCTION IN	DUSTRY BEST PRAC	CTICES. CONTRACTOR TO
			PT ON SITE FOR RE	
REVISIO	NS			
REVISIO	NS Date	Descriț	tion	
		Descrip	tion	
No.	Date	Descrip	tion	
	Date	Descrip	otion	
No.	Date :	IVERSI	ry audit	ŌRIUM,
No.	Date :	IVERSI		ORIUM,
No.	Date : UIT UN	IVERSI	ry audit	ŌRIUM,
No.	Date : UIT UN	IVERSI	ry audit	
No.	Date : UIT UN : DI	IVERSI <sup>T</sup> KAF	ry audit Rachi.	٨N
No. Job Title	Date : UIT UN : DI G	IVERSI KAF MENSI	ry audit Rachi. On Pl <i>a</i> D Floc	٨N
No. Job Title	Date : UIT UN : DI	IVERSI KAF MENSI	ry audit Rachi. On Pl <i>a</i> D Floc	۸N
No. Job Title	Date : UIT UN : DI G	IVERSI KAF MENSI ROUN	TY AUDIT RACHI. ON PLA D FLOC	۸N
No. Job Title	Date : UIT UN : G gn Cor	MENSI ROUN	TY AUDIT RACHI. ON PLA D FLOC	AN DR
No. Job Title Desi C	Date : UIT UNI : DI G G G G Cor NA Cor D LAE		ON PLA D FLOC	AN DR I
No. Job Title Desi	Date Date UIT UNI UIT UNI Control Contro	MENSI ROUN nsultan <b>JIN</b> e-Bukhai Commerc 242642,3585787, 3	TY AUDIT ACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I
No. Job Title Desi	Date	NERSI KAF MENSI ROUN nsultan <b>JIM</b> GEF BORAT	TY AUDIT ACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I
No. Job Title Desi	Date Date UIT UNI UIT UNI Control Contro	NERSI KAF MENSI ROUN nsultan <b>JIM</b> GEF BORAT	TY AUDIT ACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I
No. Job Title Desi	Date	NERSI KAF MENSI ROUN nsultan <b>JIM</b> GEF BORAT	TY AUDIT ACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I
No. Job Title Desi	Date	NERSI KAF MENSI ROUN nsultan <b>JIM</b> GEF BORAT	TY AUDIT ACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I
No. Job Title Desi	Date	NERSI KAF MENSI ROUN nsultan <b>JIM</b> GEF BORAT	TY AUDIT RACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I
No. Job Title Desi	Date	NERSI KAF MENSI ROUN nsultan <b>JIM</b> GEF BORAT	TY AUDIT RACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I
No. Job Title Desi	Date	NERSI KAF MENSI ROUN nsultan <b>JIM</b> GEF BORAT	TY AUDIT RACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I
No. Job Title Desi	Date	MENSI ROUN nsultan <b>DINI</b> <b>GGF</b> Borat e-Bukhai Commerc 242642,35857957, 3 com	TY AUDIT ACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I Karachi, Pakistan.
No. Job Title Desi	Date	MENSI ROUN nsultan <b>DINI</b> <b>GGF</b> Borat e-Bukhai Commerc 242642,35857957, 3 com	TY AUDIT RACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I Karachi, Pakistan.
No. Job Title Desi C MEF	Date	MENSI ROUN nsultan <b>DINI</b> <b>GGF</b> Borat e-Bukhai Commerc 242642,35857957, 3 com	TY AUDIT ACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I LTD Karachi, Pakistan.
No. Job Title Desi	Date	MENSI ROUN nsultan <b>DINI</b> <b>GGF</b> Borat e-Bukhai Commerc 242642,35857957, 3 com	TY AUDIT ACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I Karachi, Pakistan.
No. Job Title Desi C C MEF	Date Date UIT UNI UIT UNI Const DI G G Const DI Const	IVERSI KAF MENSI ROUN nsultan JIVI GGF JItant :	TY AUDIT ACHI. ON PLA D FLOC t : E E E E E E E E E E E E E E E E E E E	AN DR I LTD Karachi, Pakistan.




	MAIN	С	
27'-11"	L 8'-0"	L 8'-3" L	
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	RAMP UP.		
01 CH-01 CH-01 CH-01 CH-01 -	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		
01 CH-01 CH-01 CH-01 CH-01 CH-01 -			
01) CH-01) CH-01) CH-01) CH-01) CH-01)	AUDITORIUM $66^{-6^{*}x28^{*}-2^{*}}$ 7 7 7 $\pm$ $0^{-0^{*}}$ $8^{-11}\frac{1}{2}^{*}$	STAGE 7'-4"x27'-4" • <u>FLOOR LEVEL</u> +1'-6" • * * * * * * * * * * * * * * * * * * *	
01 CH-01 CH-01 CH-01 CH-01 CH-01 -	5     8'-11 <sup>1</sup> / <sub>2</sub> "       5     -       5     -       6     -       7     8'-0"		
	1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-		
01 CH-01 CH-01 CH-01 CH-01 CH-01 -	107 117 117 117 117 117 117 117		
$\begin{array}{c c c c c c c c c c c c c c c c c c c $	STEP UP.		
	MAIN ENTRANCE		

FURNIT	URE SCHEDULE			FURNITURE LAYOUT NOTES
ITEM NO.	DESCRIPTION	SIZE	QUANTITY	NOTE 1: FURNITURE LAYOUT INDICATES DESIGN INT
				ALL DIMENSIONS TO BE VERIFIED ON SITE F
PD-01	PODIUM	1'-6" X 3'-0"	01 NO.	FURNITURE VENDOR PRIOR TO FABRICATIO
CH-01	AUDITORIUM CHAIR	1'-11" X 1'-9"	166 NO.S	DISCREPANCIES MUST BE REPORTED BEFOR
CH-02	CONTROL ROOM CHAIR	1'-7" X 1'-8"	01 NO.	
TD-01	TABLE DESK	1'-6" X 5'-8"	01 NO.	DO SO WILL BE THE RESPONSIBILITY OF TH

Y	NOTE 1: FURNITURE LAYOUT INDICATES DESIGN INTENT AND FII ALL DIMENSIONS TO BE VERIFIED ON SITE BY THE CONT FURNITURE VENDOR PRIOR TO FABRICATION. ANY SIZE DISCREPANCIES MUST BE REPORTED BEFORE EXECUTIO DO SO WILL BE THE RESPONSIBILITY OF THE CONTRACT
	NOTE 2: ALL CUSTOM AND LOOSE FURNITURE TO BE FABRICATE PER APPROVED SHOP DRAWINGS AND FINAL DESIGN IN MOCK-UPS, MATERIAL SAMPLES, AND FINISHES MUST E FOR REVIEW AND WRITTEN APPROVAL PRIOR TO PROD
	NOTE 3: ANY SIZE TOLERANCES, FITMENT ISSUES, OR LAYOUT M ARISING FROM INADEQUATE SITE VERIFICATION OR DR MISINTERPRETATION WILL BE THE FULL RESPONSIBILITY FURNITURE VENDOR AND/OR CONTRACTOR.
	NOTE 4: FURNITURE INSTALLATION MUST FOLLOW STRICT ALIGI LEVELING, AND SPACING AS PER APPROVED LAYOUTS. F POSITIONING TO BE MARKED, REVIEWED, AND VERIFIEI ARCHITECT/DESIGNER PRIOR TO PERMANENT FIXING.
	NOTE 5: ALL JOINERY TO BE FINISHED WITH NON-TOXIC, FIRE-RA ANTI-TERMITE TREATMENTS WHERE APPLICABLE. CERT COMPLIANCE MUST BE SUBMITTED PRIOR TO INSTALLA
	NOTE 6: FINAL QUALITY CONTROL (QC) OF FURNITURE INCLUDIN HARDWARE, JOINERY, AND FUNCTIONALITY SHALL BE T RESPONSIBILITY OF THE VENDOR. THE ARCHITECT SHALL

FURNITURE LAYOUT NOTES	TAG LEGEND
NOTE 1: FURNITURE LAYOUT INDICATES DESIGN INTENT AND FINAL POSITIONS. ALL DIMENSIONS TO BE VERIFIED ON SITE BY THE CONTRACTOR AND FURNITURE VENDOR PRIOR TO FABRICATION. ANY SIZE OR CLEARANCE DISCREPANCIES MUST BE REPORTED BEFORE EXECUTION. FAILURE TO DO SO WILL BE THE RESPONSIBILITY OF THE CONTRACTOR/VENDOR.	AA 000 Reference to Finishes Specification. Index Reference Finish Reference Finish Reference
NOTE 2: ALL CUSTOM AND LOOSE FURNITURE TO BE FABRICATED STRICTLY AS PER APPROVED SHOP DRAWINGS AND FINAL DESIGN INTENT. MOCK-UPS, MATERIAL SAMPLES, AND FINISHES MUST BE SUBMITTED FOR REVIEW AND WRITTEN APPROVAL PRIOR TO PRODUCTION.	Reference to Detail Drawing. Detail No. I-1.00 Reference.
NOTE 3: ANY SIZE TOLERANCES, FITMENT ISSUES, OR LAYOUT MISALIGNMENTS ARISING FROM INADEQUATE SITE VERIFICATION OR DRAWING MISINTERPRETATION WILL BE THE FULL RESPONSIBILITY OF THE FURNITURE VENDOR AND/OR CONTRACTOR.	
NOTE 4: FURNITURE INSTALLATION MUST FOLLOW STRICT ALIGNMENT, LEVELING, AND SPACING AS PER APPROVED LAYOUTS. FINAL POSITIONING TO BE MARKED, REVIEWED, AND VERIFIED ON SITE BY ARCHITECT/DESIGNER PRIOR TO PERMANENT FIXING.	WALL LEGEND  Existing Wall  Curtain Wall  Curtain Wall  Curtain Wall  Curtain Wall  Existing Wall  Curtain Wall  C
NOTE 5: ALL JOINERY TO BE FINISHED WITH NON-TOXIC, FIRE-RATED, AND ANTI-TERMITE TREATMENTS WHERE APPLICABLE. CERTIFICATES OF COMPLIANCE MUST BE SUBMITTED PRIOR TO INSTALLATION.	Fixed Glazing Proposed Wall
NOTE 6: FINAL QUALITY CONTROL (QC) OF FURNITURE INCLUDING MATERIAL, HARDWARE, JOINERY, AND FUNCTIONALITY SHALL BE THE RESPONSIBILITY OF THE VENDOR. THE ARCHITECT SHALL NOT BE LIABLE	GENERAL NOTES 1. COORDINATION & VERIFICATION
FOR MATERIAL OF PERFORMANCE ISSUES DUE TO VENDOR NON-COMPLIANCE.	ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ARCHITECTURAL, STRUCTURAL, MEP, FURNITURE, CEILING, ELECTRICAL, FIRE SAFETY, AND ALL SPECIALIST CONSULTANT DRAWINGS, SPECIFICATIONS, AND DETAIL DOCUMENTS. CONTRACTOR MUST VERIFY ALL DIMENSIONS, LEVELS, AND SITE CONDITIONS PRIOR TO COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES, OMISSIONS, OR CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT FOR CLARIFICATION AND DIRECTION BEFORE PROCEEDING.
	2. MISSING DETAILS & CLARIFICATIONS IN THE EVENT THAT A CONSTRUCTION DETAIL IS NOT SHOWN OR PROVIDED, IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REQUEST THE REQUIRED DETAIL FROM THE ARCHITECT. FAILURE TO REQUEST SUCH DETAILS PRIOR TO EXECUTION SHALL NOT BE USED AS A BASIS FOR ANY CLAIMS OR EXTENSIONS OF TIME. "NOT AWARE" OR "NOT SHOWN" WILL NOT BE CONSIDERED A VALID
	EXCUSE. 3. LEAKAGE PREVENTION & WATERPROOFING ALL WET AREAS, ROOF SLABS, DUCTS, AND SERVICE ZONES TO BE TREATED WITH SPECIFIED WATERPROOFING SYSTEMS. CONTRACTOR TO ENSURE NO LEAKAGE POINTS ARE LEFT UNSEALED. MOCK-UP AND TESTING (INCLUDING POND TESTS WHERE APPLICABLE) MUST BE CONDUCTED AND VERIFIED BY THE ARCHITECT/CONSULTANT PRIOR TO COVERING.
	ALE WOODEN SUFACES TO BE TREATED WITH ANTI-TERMITE SOLUTION AND     FIRE-RETARDANT COATING PRIOR TO SITE DELIVERY OR INSTALLATION.     DOCUMENTED PROOF OF TREATMENT APPLICATION (INCLUDING MSDS AND     PRODUCT DATA SHEETS) TO BE SUBMITTED FOR APPROVAL UNTREATED OR     IMPROPERLY TREATED WOOD WILL BE REJECTED AND REPLACEMENT SHALL BE     CONTRACTOR'S RESPONSEILITY     5. EXPOSED METAL ELEMENTS
	<ul> <li>ALL EXPOSED METAL ELEMENTS</li> <li>ALL EXPOSED METAL SURFACES (INCLUDING STRUCTURAL, JOINERY SUPPORTS, FITTINGS, AND FIXTURES) TO BE COATED WITH ANTI-RUST PRIMER AND FINISH COAT SUITABLE TO SPECIFIED ENVIRONMENTAL CONDITIONS. FINAL PAINT FINISH TO BE AS PER APPROVED SAMPLE AND FREE FROM DEFECTS SUCH AS PEELING, RUST, OR DISCOLORATION.</li> <li>HAZARDOUS MATERIALS &amp; SAFETY FINISHES NO HAZARDOUS, SHARP, TOXIC, OR INFLAMMABLE MATERIALS ARE TO BE LEFT</li> </ul>
	EXPOSED IN THE BUILT ENVIRONMENT. ALL MATERIALS TO BE NON-COMBUSTIBLE (UNLESS SPECIFIED OTHERWISE), CHILD-SAFE (WHERE APPLICABLE), AND COMPLIANT WITH LOCAL HEALTH, SAFETY, AND ENVIRONMENTAL STANDARDS. CERTIFICATES OF CONFORMANCE TO BE SUBMITTED AS PART OF HANDOVER. 7. CONSTRUCTION SAFETY & COMPLIANCE
	ALL CONSTRUCTION WORKS SHALL BE CARRIED OUT IN COMPLIANCE WITH LOCAL BUILDING CODES, OSHA STANDARDS, AND SITE SAFETY REQUIREMENTS. PERSONAL PROTECTIVE EQUIPMENT (PPE) IS MANDATORY FOR ALL WORKERS. CONTRACTOR TO ENSURE BARRICADING, SAFETY SIGNAGE, FIRE EXTINGUISHERS, AND PROPER STORAGE OF MATERIALS ON SITE. 8. APPROVALS & MOCK-UPS WHEREVER REQUIRED, MOCK-UPS MUST BE PREPARED AND APPROVED PRIOR TO
	MASS EXECUTION. ANY WORK CARRIED OUT WITHOUT PRIOR APPROVAL, INCLUDING MATERIALS, COLOURS, SAMPLES, AND JOINERY DETAILS, SHALL BE SUBJECT TO REJECTION AT THE CONTRACTOR'S END. 9. DRAWING UPDATES & RECORD KEEPING CONTRACTOR TO MAINTAIN A PRINTED SET OF LATEST GOOD-FOR-CONSTRUCTION DRAWINGS ON SITE. ANY MARK-UP OR REDLINE ADJUSTMENTS TO BE NOTED AND SHARED WITH ARCHITECT ON WEEKLY BASIS.
	FINAL AS-BUILT DRAWINGS TO BE PROVIDED AT PROJECT CLOSEOUT. FINAL AS-BUILT DRAWINGS TO BE PROVIDED AT PROJECT CLOSEOUT. 10. STANDARDS & DOCUMENTATION ALL MATERIALS AND EXECUTION METHODS SHALL ADHERE TO MANUFACTURER'S GUIDELINES AND CONSTRUCTION INDUSTRY BEST PRACTICES. CONTRACTOR TO REFER TO THE PROJECT SPECIFICATION MANUAL FOR ALL TECHNICAL STANDARDS. LATEST MANUFACTURER DATASHEETS, MSDS, FIRE RATINGS, AND INSTALLATION GUIDELINES TO BE KEPT ON SITE FOR REFERENCE.
	REVISIONS           No.         Date         Description
	Job : UIT UNIVERSITY AUDITORIUM, KARACHI.
	Title : FURNITURE PLAN GROUND FLOOR
	Design Consultant :
	NAJMI BILGRAMI COLLABORATIVE (PVT)LTD 14-C, Lane 7, Main Kitx-Bukhari Commercial, Phase - VI, D.O.H.A, Karachi, Pakistan. T +95-21-355274659.35242642,35857957, 35857990 F +95-21-35557966
	W www.najmibilgrami.com MEP Consultant :
	STAMP : TENDER DRAWINGS
	Job Arch : U.G Checked: A.N. Cad By : MINHAS
	Job No :         I-CO-2803           Date :         JUNE 20, 2025           Scale :         1/4" = 1'-0"
RAWINGS. ALL	



27'-11"	<u>8'-0"</u>	8'-3"	
	RAMP UP.		
$ \begin{array}{c} (+0) \\ ($	$\begin{array}{c} F_{12}^{(C)} \\ F_{12}^{(C)} \\$	$\begin{array}{c} 1'-11'' \\ \hline \\$	
$\begin{array}{c} 01 \\ 01 \\ \hline \\ CH-01 \\ \hline$	HIN ENTRANCE		


FURNIT	URE SCHEDULE			FURNITURE LAYOUT NOTES
ITEM NO.	DESCRIPTION	SIZE	QUANTITY	<b>NOTE 1:</b> FURNITURE LAYOUT INDICATES DESIGN IN
				ALL DIMENSIONS TO BE VERIFIED ON SITE I
CH-01	AUDITORIUM CHAIR	1'-11" X 1'-9"	166 NO.S	FURNITURE VENDOR PRIOR TO FABRICATIO
CH-02	CONTROL ROOM CHAIR	1'-7" X 1'-8"	01 NO.	DISCREPANCIES MUST BE REPORTED BEFOI
GC-03	GUEST CHAIR	2'-6" X 2'-6"	04 NO.S	
TD-01	TABLE DESK	1'-6" X 5'-8"	01 NO.	DO SO WILL BE THE RESPONSIBILITY OF TH
ET-01	END TABLE	16" DIA	02 NO.S	

(c)

D.S O.S D.S O.	NOTE 1: FURNITURE LAYOUT INDICATES DESIGN INTENT AND FIN. ALL DIMENSIONS TO BE VERIFIED ON SITE BY THE CONTR FURNITURE VENDOR PRIOR TO FABRICATION. ANY SIZE C DISCREPANCIES MUST BE REPORTED BEFORE EXECUTION DO SO WILL BE THE RESPONSIBILITY OF THE CONTRACTO
D.S	NOTE 2: ALL CUSTOM AND LOOSE FURNITURE TO BE FABRICATED PER APPROVED SHOP DRAWINGS AND FINAL DESIGN INT MOCK-UPS, MATERIAL SAMPLES, AND FINISHES MUST BE FOR REVIEW AND WRITTEN APPROVAL PRIOR TO PRODU
	NOTE 3: ANY SIZE TOLERANCES, FITMENT ISSUES, OR LAYOUT MIS ARISING FROM INADEQUATE SITE VERIFICATION OR DRA MISINTERPRETATION WILL BE THE FULL RESPONSIBILITY FURNITURE VENDOR AND/OR CONTRACTOR.
	NOTE 4: FURNITURE INSTALLATION MUST FOLLOW STRICT ALIGN LEVELING, AND SPACING AS PER APPROVED LAYOUTS. FII POSITIONING TO BE MARKED, REVIEWED, AND VERIFIED ARCHITECT/DESIGNER PRIOR TO PERMANENT FIXING.
	NOTE 5: ALL JOINERY TO BE FINISHED WITH NON-TOXIC, FIRE-RAT ANTI-TERMITE TREATMENTS WHERE APPLICABLE. CERTIF COMPLIANCE MUST BE SUBMITTED PRIOR TO INSTALLAT
	NOTE 6: FINAL QUALITY CONTROL (QC) OF FURNITURE INCLUDING HARDWARE, JOINERY, AND FUNCTIONALITY SHALL BE TH RESPONSIBILITY OF THE VENDOR. THE ARCHITECT SHALL FOR MATERIAL OR PERFORMANCE ISSUES DUE TO VENDO NON-COMPLIANCE.

ALL DE**SIGNE:** AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.

	TAG LEGEND
T AND FINAL POSITIONS. HE CONTRACTOR AND ANY SIZE OR CLEARANCE XECUTION. FAILURE TO INTRACTOR/VENDOR.	AA 000 Reference to Finishes Specification. Index Reference Finish Reference Finish Reference
ABRICATED STRICTLY AS ESIGN INTENT. S MUST BE SUBMITTED FO PRODUCTION.	Reference to Detail Drawing. Detail No. I-1.00 Reference.
AYOUT MISALIGNMENTS IN OR DRAWING NSIBILITY OF THE	WALL LEGEND
ICT ALIGNMENT, YOUTS. FINAL VERIFIED ON SITE BY FIXING.	Existing Wall Structural Column
C, FIRE-RATED, AND LE. CERTIFICATES OF INSTALLATION.	Fixed Glazing Proposed Wall FURNITURE LAYOUT NOTES
INCLUDING MATERIAL, IALL BE THE CT SHALL NOT BE LIABLE	GENERAL NOTES  1. COORDINATION & VERIFICATION ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ARCHITECTURAL,
TO VENDOR	ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ARCHITECTURAL, SPECIALIST CONSULTANT DRAWINGS, SPECIFICATIONS, AND DETAIL DOCUMENTS, CONTRACTOR MUST VERIFY ALL DIMENSIONS, LEVELS, AND STE CONDITIONS PROR TO COMMENCEMENT OF ANY WORK, ANY DISCREPANCES, OMISSIONS, OR CONFLICTS SHALL BE BROUGHT TO FI ATTINTION OF THE ARCHITECT FOR CLARRICATION AND DIRECTION BEFORE PROCEEDING. IM THE EVENT THAT A CONSTRUCTION DETAIL IS NOT SHOWN OR PROVIDED, IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REQUEST THE REQUERT SUB- DETAIL FROM THE ARCHITECT. FAILURE TO REQUEST SUCH DETAILS PROM THE EVENT THAT A CONSTRUCTION DETAIL IS NOT SHOWN OR PROVIDED, IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REQUEST THE REQUEST UNIT AND AWARE' OR "NOT SHOWN" WILL NOT BE CONSIDERED A VALID EXCLUTO SUCUSE.
	No.     Date     Description
	Job :
	UIT UNIVERSITY AUDITORIUM, KARACHI.
	Title : FURNITURE PLAN GROUND FLOOR
	Design Consultant : NAJINI BILGRANI COLLABORATIVE (PVT)LTD 14-C, Lane 7, Main Kit-e-Bukhari Commercial, Phase - VI, D.O.H.A, Karachi, Pakistan. 14-02-1-35247629, 35247642, 35857990 F 902-21-35857996 W www.aajmibilgrami.com MEP Consultant :
	STAMP : TENDER DRAWINGS Job Arch : U.G Checked: A.N. Cad By : MINHAS Job No : I-CO-2803
	Job No         I-CO-2803           Date         : JUNE 20, 2025           Scale         : 1/4" = 1'-0"




ALL DE**SIGNE:** AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.

#### FLOORING PLAN NOTES FIX FINISHES LEGEND: NOTE 1: FLOORING PLAN REPRESENTS FINISH INTENT AND PA CT-001 CARPET TILES ALIGNMENT. CONTRACTOR TO VERIFY SITE LEVELS, S CONDITIONS, AND ANY SERVICE LOCATIONS PRIOR TO NOTE 2: ALL FLOORING CUTS, GROUT LINES, AND MATERIAL COORDINATED AND APPROVED ON SITE BEFORE INST IMPROPER OR MISALIGNED INSTALLATION DUE TO NO VT-001 VINYL TILE LAYOUT WILL BE RECTIFIED BY CONTRACTOR. NOTE 3: FLOORING MATERIALS TO BE AS PER FINAL APPROVED MOCK-UP INSTALLATIONS TO BE PROVIDED FOR EACI INSTALLATION TO PROCEED ONLY AFTER MOCK-UP A TT-001 TERRAZO TILES **NOTE 4:** ANTI-SKID, FIRE-RATED, AND NON-HAZARDOUS FINISH PER AREA FUNCTIONALITY. EDGING, TRANSITIONS, AN BE SAFE, FLUSH, AND FREE OF SHARP ELEMENTS. NOTE 5: NOTE 5: EXPANSION JOINTS, GROUT FILLING, AND SEALANTS TO MANUFACTURER'S GUIDELINES AND INDUSTRY BEST P DAMAGE DUE TO IMPROPER SEALING OR SUBBASE WI BY CONTRACTOR. NOTE 6: ALL FLOORING INSTALLATION TO BE SUPERVISED, LEVE QA-APPROVED. MATERIAL WARRANTY CERTIFICATES T TO CLIENT PRIOR TO HANDOVER. LUMINAR LEGEND: SYMBOL DESCRIPTION LED Strip light (c) HO Wall Light NOTE: ALL LIGHT TEMPERATURE TO BE 3 27'-11" 8'-0" 8'-3" LED STRIP LIGHT LED STRIP LIGHT LED STRIP LED STRIP LIGHT LIGHT 1 0 C 0 C WALL -FLOOR LEVEL FLOOR LEVEL +1'-8" +0'-10" WALL LIGHT +2'-6" <u> YV</u> LED STRIP LED STRIP LED STR CT-001 + AUDITORIUM STAGE 66'-6"x28'-2" FLOOR LEVEL LED STRIP LED STRIP LED STRIP LIGHT VT-001 ठाठ् WALL LIGHT LED STRIP LIGHT LED STRIP LED STRIP LED STRIF FLOOR LEVEL FLOOR LEVEL .+1'-8" +0'-10" $\angle$

MAIN

ENTRANCE

	TAG LEGEND
TTERN UBSTRATE O EXECUTION.	AA 000 Reference to Finishes Specification. Index Reference Finish Reference Finish Reference
TRANSITIONS TO BE TALLATION. ION-VERIFIED	Reference to Detail Drawing. Detail No.
ED SAMPLE BOARDS. H TYPE. APPROVAL.	L-1.00 — Drawing No. Reference.
SHES TO BE USED AS ND SKIRTINGS TO	WALL LEGEND
TO BE USED AS PER PRACTICE. VILL BE RECTIFIED	Existing Wall     Structural Column       Curtain Wall     Cement Board Partition Wall       Fixed Glazing     Proposed Wall
VELED, AND S TO BE SUBMITTED	
	GENERAL NOTES 1. COORDINATION & VERIFICATION
	ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ARCHITECTURAL, STRUCTURAL, MEP, FURNITURE, CEILING, ELECTRICAL, FIRE SAFETY, AND ALL SPECIALIST CONSULTANT DRAWINGS, SPECIFICATIONS, AND DETAIL DOCUMENTS. CONTRACTOR MUST VERIFY ALL DIMENSIONS, LEVELS, AND SITE CONDITIONS PRIOR TO COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES, OMISSIONS, OR CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT FOR CLARIFICATION AND DIRECTION BEFORE PROCEEDING. 2. MISSING DETAILS & CLARIFICATIONS IN THE EVENT THAT A CONSTRUCTION DETAIL IS NOT SHOWN OR PROVIDED, IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REQUEST THE REQUIRED
	DETAIL FROM THE ARCHITECT. FAILURE TO REQUEST SUCH DETAILS PRIOR TO EXECUTION SHALL NOT BE USED AS A BASIS FOR ANY CLAIMS OR EXTENSIONS OF TIME. "NOT AWARE" OR "NOT SHOWN" WILL NOT BE CONSIDERED A VALID EXCUSE. 3. LEAKAGE PREVENTION & WATERPROOFING ALL WET AREAS, ROOF SLABS, DUCTS, AND SERVICE ZONES TO BE TREATED WITH SPECIFIED WATERPROOFING SYSTEMS. CONTRACTOR TO ENSURE NO LEAKAGE
	POINTS ARE LEFT UNSEALED. MOCK-UP AND TESTING (INCLUDING POND TESTS WHERE APPLICABLE) MUST BE CONDUCTED AND VERIFIED BY THE ARCHITECT/CONSULTANT PRIOR TO COVERING. 4. WOODEN ELEMENTS ALL WOODEN SURFACES TO BE TREATED WITH ANTI-TERMITE SOLUTION AND FIRE-RETARDANT COATING PRIOR TO SITE DELIVERY OR INSTALLATION.
	DOCUMENTED PROOF OF TREATMENT APPLICATION (INCLUDING MSDS AND PRODUCT DATA SHEETS) TO BE SUBMITTED FOR APPROVAL. UNTREATED OR IMPROPERLY TREATED WOOD WILL BE REJECTED AND REPLACEMENT SHALL BE CONTRACTOR'S RESPONSBILITY 5. EXPOSED METAL ELEMENTS ALL EXPOSED METAL SURFACES (INCLUDING STRUCTURAL, JOINERY SUPPORTS, CONTRACTOR DEVELOPMENT AND A DEVELOPMENT.
	FITTINGS, AND FIXTURES) TO BE COATED WITH ANTI-RUST PRIMER AND FINISH COAT SUITABLE TO SPECIFIED ENVIRONMENTAL CONDITIONS. FINAL PAINT FINISH TO BE AS PER APPROVED SAMPLE AND FREE FROM DEFECTS SUCH AS PEELING, RUST, OR DISCOLORATION. 6. HAZARDOUS MATERIALS & SAFETY FINISHES NO HAZARDOUS, SHARP, TOXIC, OR INFLAMMABLE MATERIALS ARE TO BE LEFT EXPOSED IN THE BUILT ENVIRONMENT. ALL MATERIALS TO BE
	NON-COMBUSTIBLE (UNLESS SPECIFIED OTHERWISE), CHILD-SAFE (WHERE APPLICABLE), AND COMPLIANT WITH LOCAL HEALTH, SAFETY, AND ENVIRONMENTAL STANDARDS. CERTIFICATES OF CONFORMANCE TO BE SUBMITTED AS PART OF HANDOVER. 7. CONSTRUCTION SAFETY & COMPLIANCE ALL CONSTRUCTION WORKS SHALL BE CARRIED OUT IN COMPLIANCE WITH LOCAL
	BUILDING CODES, OSHA STANDARDS, AND SITE SAFETY REQUIREMENTS. PERSONAL PROTECTIVE EQUIPMENT (PPE) IS MANDATORY FOR ALL WORKERS. CONTRACTOR TO ENSURE BARRICADING, SAFETY SIGNAGE, FIRE EXTINGUISHERS, AND PROPER STORAGE OF MATERIALS ON SITE. 8. APPROVALS & MOCK-UPS WHEREVER REQUIRED, MOCK-UPS MUST BE PREPARED AND APPROVED PRIOR TC MASS EXECUTION. ANY WORK CARRIED OUT WITHOUT PRIOR APPROVAL,
	INCLUDING MATERIALS, COLOURS, SAMPLES, AND JOINERY DETAILS, SHALL BE SUBJECT TO REJECTION AT THE CONTRACTOR'S END. 9. DRAWING UPDATES & RECORD KEEPING CONTRACTOR TO MAINTAIN A PRINTED SET OF LATEST GOOD-FOR-CONSTRUCTION DRAWINGS ON SITE. ANY MARK-UP OR REDLINE ADJUSTMENTS TO BE NOTED AND SHARED WITH ARCHITECT ON WEEKLY BASIS. FINAL AS-BUILT DRAWINGS TO BE PROVIDED AT PROJECT CLOSEOUT.
	10. STANDARDS & DOCUMENTATION ALL MATERIALS AND EXECUTION METHODS SHALL ADHERE TO MANUFACTURER'S GUIDELINES AND CONSTRUCTION INDUSTRY BEST PRACTICES. CONTRACTOR TO REFER TO THE PROJECT SPECIFICATION MANUAL FOR ALL TECHNICAL STANDARDS. LATEST MANUFACTURER DATASHEETS, MSDS, FIRE RATINGS, AND INSTALLATION GUIDELINES TO BE KEPT ON SITE FOR REFERENCE.
	REVISIONS No. Date Description
	Job : UIT UNIVERSITY AUDITORIUM, KARACHI.
	Title : FIX FINISHES PLAN
	GROUND FLOOR
	Design Consultant : NAJNI BILGRANI COLLABORATIVE (PVT)LTD 14-C, Lane 7, Main Kha-Bukhar Commercial, Phase - VI, D.O.H.A, Karachi, Pakistan. 1+92-21-35242629,35242644,35857957, 35857990 F+92-21-33657986 W www.anjmistigramicom
	MEP Consultant :
	STAMP : TENDER DRAWINGS
	Job Arch : U.G Checked: A.N. Cad By : MINHAS Job No : I-CO-2803
	Date         :         JUNE 20, 2025         Dwg. No.           Scale         :         1/4" = 1'-0"         I-1.4.01



ALL DE**SIGNE:** AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.


REFLECTED CEILING PLAN (R.C.P.) NO NOTE 1: RCP REPRESENTS DESIGN INTENT FOR HEIGHTS, FIXT AND ALIGNMENT. ALL CEILING ELEMENTS INCLUDING DIFFUSERS, ACCESS PANELS, AND SPEAKERS TO BE FL WITH ARCHITECTURAL, MEP, STRUCTURAL, AND ELEC NOTE 2: ALL ELECTRICAL FIXTURES, LIGHTS, DEVICES, AND CEII BE MARKED ON SITE FOR APPROVAL PRIOR TO INSTAL INSTALLATION SHALL PROCEED WITHOUT FINAL ONSI THE DESIGN TEAM.

NOTE 3: LACK OF MARKING, MEP COORDINATION, OR ON-SITE BE THE CONTRACTOR'S FULL RESPONSIBILITY. ARCHIT SHALL NOT BE HELD LIABLE FOR ERRORS ARISING FRO SERVICES OR LATE-STAGE REVISIONS DUE TO NON-CO EXECUTION.

NOTE 4: MEP CONTRACTOR TO ENSURE PROPER COORDINATIO DETECTION, EMERGENCY LIGHTING, AND SENSOR SYS DEFENSE NORMS. FINISH ALIGNMENT TO BE REVIEWE ARCHITECT PRIOR TO CUT-OUTS OR EXECUTION.


NOTE 5: ALL MATERIALS, FINISH COLORS, EDGE DETAILS, AND ACCESS PANELS TO BE EXECUTED AS PER SPECIFICATI CEILINGS TO BE PRESENTED FOR FINAL APPROVAL BE ROLL-OUT.

NOTE 6: AUTOMATION, DIMMING ZONES, AND ELECTRICAL CO INTERFACES TO BE TESTED AND VALIDATED FOR COM TO FINAL FIXING. ANY LATE-STAGE DISRUPTIONS OR I CONTRACTOR'S RESPONSIBILITY





OTES	TAG LEGEND		
TURE POSITIONS, NG LIGHTS, FULLY COORDINATED ECTRICAL DRAWINGS	AA 000 Specifica	e to Finishes tion. erence	Reference to Elevation Drawing. Elevation Reference Drawing No.
EILING SERVICES TO ALLATION. NO ISITE APPROVAL BY	Reference Detail Dro Detail No 1-1.00 Drawing 1	e to Iwing.	one Reference
TE ALIGNMENT WILL IITECT/DESIGNER ROM MISALIGNED	Reference		
COORDINATED	WALL LEGEND		
TION OF HVAC, FIRE YSTEMS AS PER CIVIL WED WITH		ing Wall	Structural Column Cement Board Partition Wall
D CONCEALED TIONS. MOCK-UP BEFORE FULL	Fixed	Glazing	Proposed Wall
CONTROL MPATIBILITY PRIOR	GENERAL NOTES 1. COORDINATION & VERIFI		
R REWORK WILL BE	STRUCTURAL, MEP, FURN SPECIALIST CONSULTANT CONTRACTOR MUST VERI PRIOR TO COMMENCEME CONFLICTS SHALL BE BRO CLARIFICATION AND DIRE	AD IN CONJUNCTION WITH ARCHI ITURE, CEILING, ELECTRICAL, FIRE DRAWINGS, SPECIFICATIONS, AN FY ALL DIMENSIONS, LEVELS, ANIN NT OF ANY WORK. ANY DISCREPJ UGHT TO THE ATTENTION OF THI CTION BEFORE PROCEEDING.	SAFETY, AND ALL D DETAIL DOCUMENTS. D SITE CONDITIONS ANCIES, OMISSIONS, OR
TON aint Finish	THE SOLE RESPONSIBILITY DETAIL FROM THE ARCHI EXECUTION SHALL NOT BI	IFICATIONS VSTRUCTION DETAIL IS NOT SHOV OF THE CONTRACTOR TO REQUE FECT. FAILURE TO REQUEST SUCH E USED AS A BASIS FOR ANY CLAIR NOT SHOWN" WILL NOT BE CON	EST THE REQUIRED DETAILS PRIOR TO MS OR EXTENSIONS OF
aint Finish	3. LEAKAGE PREVENTION & ALL WET AREAS, ROOF SL SPECIFIED WATERPROOFI POINTS ARE LEFT UNSEAL WHERE APPLICABLE) MUS ARCHITECT/CONSULTANT 4. WOODEN ELEMENTS	ABS, DUCTS, AND SERVICE ZONES NG SYSTEMS. CONTRACTOR TO E ED. MOCK-UP AND TESTING (INCI T BE CONDUCTED AND VERIFIED PRIOR TO COVERING.	NSURE NO LEAKAGE LUDING POND TESTS BY THE
	FIRE-RETARDANT COATIN DOCUMENTED PROOF OF PRODUCT DATA SHEETS) IMPROPERLY TREATED W CONTRACTOR'S RESPONS 5. EXPOSED METAL ELEMEN		STALLATION. UDING MSDS AND L. UNTREATED OR LACEMENT SHALL BE
	FITTINGS, AND FIXTURES) COAT SUITABLE TO SPECI TO BE AS PER APPROVED RUST, OR DISCOLORATION 6. HAZARDOUS MATERIALS NO HAZARDOUS, SHARP,	TO BE COATED WITH ANTI-RUST FIED ENVIRONMENTAL CONDITIO SAMPLE AND FREE FROM DEFECT I.	PRIMER AND FINISH INS. FINAL PAINT FINISH IS SUCH AS PEELING, IALS ARE TO BE LEFT
	NON-COMBUSTIBLE (UNL APPLICABLE), AND COMP ENVIRONMENTAL STAND, SUBMITTED AS PART OF F 7. CONSTRUCTION SAFETY 8	ESS SPECIFIED OTHERWISE), CHIL LIANT WITH LOCAL HEALTH, SAFE ARDS. CERTIFICATES OF CONFORM IANDOVER. & COMPLIANCE	D-SAFE (WHERE TY, AND MANCE TO BE
	BUILDING CODES, OSHA S PERSONAL PROTECTIVE E CONTRACTOR TO ENSURE AND PROPER STORAGE O 8. APPROVALS & MOCK-UP:	5	QUIREMENTS. FOR ALL WORKERS. , FIRE EXTINGUISHERS,
	MASS EXECUTION. ANY W INCLUDING MATERIALS, C SUBJECT TO REJECTION A 9. DRAWING UPDATES & RE CONTRACTOR TO MAINT/	AIN A PRINTED SET OF LATEST	OR APPROVAL, Y DETAILS, SHALL BE
	ADJUSTMENTS TO BE NO FINAL AS-BUILT DRAWING 10. STANDARDS & DOCUM ALL MATERIALS AND EXEC	CUTION METHODS SHALL ADHERE	CT ON WEEKLY BASIS. CLOSEOUT. E TO MANUFACTURER'S
	REFER TO THE PROJECT SI STANDARDS. LATEST MAN	UCTION INDUSTRY BEST PRACTIC PECIFICATION MANUAL FOR ALL T JUFACTURER DATASHEETS, MSDS S TO BE KEPT ON SITE FOR REFER	ECHNICAL 5, FIRE RATINGS, AND
	REVISIONS		
	No. Date	Description	
	Job : VINU TIU	ERSITY AUDITC KARACHI.	PRIUM,
	-	TED CEILING F	
	GR Design Cons	OUND FLOOF ultant :	<u> </u>
		GRAND RATIVE (PVT) LT that Commercial, Phase - VI, D.O.H.A, Kara	
	MEP Consult	ant :	
	STAMP :		
		ER DRAWIN	GS
	Job Arch : U.G Checked: A.N.		North :
	Cad By : MINHAS Job No : I-CO-2803 Date : JUNE 20, 202	5 Dwg. No.	j V.
	Date : JUNE 20, 202 Scale : 1/4" = 1'-0"	, Dwg. No.	1.5.01




ALL DE**NOME**: AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.

AG LEC	GEND				Reference to
					Kelelelice IO
	000 S	eference to pecification. Idex Referen		Â	Elevation Drawing. Elevation Reference
Ľ		nish Referenc		1-1.00	Drawing No. —Zone Reference
		eference to etail Drawing	7		
(1)	$\rightarrow$	etail No.	J.		
	~ /	rawing No. eference.			
VALL LE	EGEND				
335.5		Existing W	/all		Structural Column
	<u>antean</u> ta a	Curtain W	_		Cement Board
	r	<ul> <li>Fixed Gla;</li> </ul>			Partition vvali
			zing 💥		Proposed Wall
	RAL NOT				
ALL DF	RAWINGS		CONJUNCTIO		CHITECTURAL, FIRE SAFETY, AND ALL
SPECIA	ALIST CON	SULTANT DRAV	WINGS, SPEC	IFICATIONS,	AND DETAIL DOCUMEN AND SITE CONDITIONS
CONFL	ICTS SHAL	L BE BROUGH	Τ ΤΟ ΤΗΕ ΑΤΤ	ENTION OF	REPANCIES, OMISSIONS, THE ARCHITECT FOR
2. MISSI	NG DETAIL	AND DIRECTIO	TIONS		
THE SC	OLE RESPC	ONSIBILITY OF T	THE CONTRAC	CTOR TO RE	HOWN OR PROVIDED, IT QUEST THE REQUIRED JCH DETAILS PRIOR TO
EXECU	ITION SHA	LL NOT BE USE	D AS A BASIS	FOR ANY C	LAIMS OR EXTENSIONS C
EXCUS 3. LEAKA		NTION & WAT	ERPROOFING	6	
SPECIF	IED WATE	RPROOFING S	YSTEMS. COM	ITRACTOR T	NES TO BE TREATED WIT O ENSURE NO LEAKAGE
WHER	E APPLICA	BLE) MUST BE	CONDUCTED	AND VERIF	INCLUDING POND TESTS IED BY THE
4. WOOD	DEN ELEM				
FIRE-R	ETARDAN	T COATING PRI	IOR TO SITE D	DELIVERY OF	RMITE SOLUTION AND RINSTALLATION. NCLUDING MSDS AND
PRODU IMPRC	JCT DATA DPERLY TR	SHEETS) TO BE EATED WOOD	SUBMITTED WILL BE REJE	FOR APPRO	VELODING M3D3 AND OVAL. UNTREATED OR REPLACEMENT SHALL BE
CONTE 5. EXPOS	RACTOR'S SED METAI	RESPONSBILITY L ELEMENTS	(		
ALL EX FITTIN	(POSED M GS, AND F	ETAL SURFACE IXTURES) TO B	E COATED W	ITH ANTI-RU	RAL, JOINERY SUPPORTS, JST PRIMER AND FINISH
TO BE	AS PER AF				ITIONS. FINAL PAINT FINI ECTS SUCH AS PEELING,
6. HAZAF	RDOUS MA	ATERIALS & SA			TERIALS ARE TO BE LEFT
EXPOS	ED IN THE	BUILT ENVIRC	NMENT. ALL	MATERIALS	
ENVIR	ONMENTA		. CERTIFICAT		AFETY, AND ORMANCE TO BE
7. CONST	TRUCTION	PART OF HAND	MPLIANCE		
BUILDI	ING CODE	S, OSHA STANI	DARDS, AND	SITE SAFETY	COMPLIANCE WITH LOC REQUIREMENTS. DRY FOR ALL WORKERS.
	RACTOR TO		RICADING, S	AFETY SIGN	AGE, FIRE EXTINGUISHER
AND P 8. Appro		<b>/IOCK-UPS</b> UIRED, MOCK-	UPS MUST B	E PREPAREC	AND APPROVED PRIOR
AND P 8. APPRO WHER MASS INCLUI	EVER REQ EXECUTIO DING MAT	UIRED, MOCK- N. ANY WORK TERIALS, COLOI	CARRIED OU URS, SAMPLE	T WITHOUT S, AND JOIN	AND APPROVED PRIOR PRIOR APPROVAL, IERY DETAILS, SHALL BE
AND P 8. APPRO WHER MASS INCLUI SUBJER	EVER REQ EXECUTIO DING MAT CT TO REJI <b>/ING UPD</b> #	UIRED, MOCK- N. ANY WORK FERIALS, COLOU ECTION AT THE ATES & RECORI	CARRIED OU <sup>-</sup> URS, SAMPLE CONTRACTO D KEEPING	T WITHOUT S, AND JOIN DR'S END.	PRIOR APPROVAL,
AND P 8. APPRO WHER MASS INCLUI SUBJEI 9. DRAW CONTE GOOD	EVER REQ EXECUTIO DING MAT CT TO REJI <b>/ING UPD</b> RACTOR TO I-FOR-CON	UIRED, MOCK- N. ANY WORK TERIALS, COLOU ECTION AT THE ATES & RECORI D MAINTAIN A ISTRUCTION DF	CARRIED OU <sup>T</sup> URS, SAMPLE E CONTRACTO D KEEPING PRINTED SET RAWINGS ON	T WITHOUT S, AND JOIN DR'S END. OF LATEST I SITE. ANY I	PRIOR APPROVAL,
AND P 8. APPRC WHER MASS INCLUI SUBJE 9. DRAW CONTE GOOD ADJUS FINAL	EVER REQ EXECUTIO DING MAT CT TO REJI <b>/ING UPDA</b> RACTOR TO I-FOR-CON STMENTS T AS-BUILT	UIRED, MOCK- N. ANY WORK TERIALS, COLOU ECTION AT THE ATES & RECORI D MAINTAIN A ISTRUCTION DF	CARRIED OU URS, SAMPLE CONTRACTO D KEEPING PRINTED SET RAWINGS ON AND SHARED BE PROVIDE	T WITHOUT S, AND JOIN DR'S END. OF LATEST I SITE. ANY I WITH ARCH	PRIOR APPROVAL, IERY DETAILS, SHALL BE MARK-UP OR REDLINE ITECT ON WEEKLY BASIS
AND P 8. APPRC WHER MASS INCLUI SUBJEI 9. DRAW CONTF GOOD ADJUS FINAL 10. STAM ALL M GUIDE	EVER REQ EXECUTIO DING MAT CT TO REJI VING UPDA RACTOR TO -FOR-CON STMENTS 1 AS-BUILT NDARDS & ATERIALS ELINES AND	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE CATES & RECORI D MAINTAIN A ISTRUCTION DE TO BE NOTED A DRAWINGS TO & DOCUMENTA AND EXECUTIC D CONSTRUCTI	CARRIED OU URS, SAMPLE E CONTRACTO D KEEPING PRINTED SET RAWINGS ON ND SHARED BE PROVIDE E PROVIDE TION ON METHODS ON INDUSTR	r Without s, and Join pr's End. cof Latest i site. Any r With Arch d At Projec s Shall Adh y Best Prae	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC
AND P 8. APPRC WHER MASS INCLUI SUBJEI 9. DRAW CONTT GOOD ADJUS FINAL 10. STAN ALL M. GUIDE REFER STANE	EVER REQ EXECUTIO DING MAT CT TO REJI <b>VING UPDA</b> RACTOR TO -FOR-CON STMENTS T AS-BUILT I <b>NDARDS &amp;</b> ATERIALS LUNES ANI TO THE PI DARDS. LA	UIRED, MOCK- N. ANY WORK TERIALS, COLOU ECTION AT THE ATES & RECORI D MAINTAIN A ISTRUCTION DI TO BE NOTED A DRAWINGS TO ADD EXECUTIO D CONSTRUCTI TOJECT SPECIF TEST MANUFA	CARRIED OU URS, SAMPLE E CONTRACTO D KEEPING PRINTED SET RAWINGS ON AND SHARED BE PROVIDE TION DN METHODS ON INDUSTR ICATION MAI CTURER DAT.	r without s, and join pr's end. of latest i site. any f with arch d at projec s shall add- y best prac NUAL FOR A asheets, m	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI SUBJEI 9. DRAW CONTT GOOD ADJUS FINAL 10. STAN ALL M. GUIDE REFER STANE	EVER REQ EXECUTIO DING MAT CT TO REJI <b>VING UPDA</b> RACTOR TO -FOR-CON STMENTS T AS-BUILT I <b>NDARDS &amp;</b> ATERIALS LUNES ANI TO THE PI DARDS. LA	UIRED, MOCK- N. ANY WORK FERIALS, COLOI ECTION AT THE <b>ATES &amp; RECORI</b> D MAINTAIN A ISTRUCTION DI TO BE NOTED A DRAWINGS TO <b>B DOCUMENTA</b> AND EXECUTION DOCUMENTA ROJECT SPECIF	CARRIED OU URS, SAMPLE E CONTRACTO D KEEPING PRINTED SET RAWINGS ON AND SHARED BE PROVIDE TION DN METHODS ON INDUSTR ICATION MAI CTURER DAT.	r without s, and join pr's end. of latest i site. any f with arch d at projec s shall add- y best prac NUAL FOR A asheets, m	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI SUBJEI 9. DRAW CONTT GOOD ADJUS FINAL 10. STAN ALL M. GUIDE REFER STANE	EVER REQ EXECUTIO DING MAT CT TO REJI <b>VING UPDA</b> RACTOR TO -FOR-CON STMENTS T AS-BUILT I <b>NDARDS &amp;</b> ATERIALS LUNES ANI TO THE PI DARDS. LA	UIRED, MOCK- N. ANY WORK TERIALS, COLOU ECTION AT THE ATES & RECORI D MAINTAIN A ISTRUCTION DI TO BE NOTED A DRAWINGS TO ADD EXECUTIO D CONSTRUCTI TOJECT SPECIF TEST MANUFA	CARRIED OU URS, SAMPLE E CONTRACTO D KEEPING PRINTED SET RAWINGS ON AND SHARED BE PROVIDE TION DN METHODS ON INDUSTR ICATION MAI CTURER DAT.	r without s, and join pr's end. of latest i site. any f with arch d at projec s shall add- y best prac NUAL FOR A asheets, m	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI SUBJEI 9. DRAW CONTT GOOD ADJUS FINAL 10. STAN ALL M. GUIDE REFER STANE	EVER REQ EXECUTIO DING MAT CT TO REJI <b>VING UPDA</b> RACTOR TO -FOR-CON STMENTS T AS-BUILT I <b>NDARDS &amp;</b> ATERIALS LUNES ANI TO THE PI DARDS. LA	UIRED, MOCK- N. ANY WORK TERIALS, COLOU ECTION AT THE ATES & RECORI D MAINTAIN A ISTRUCTION DI TO BE NOTED A DRAWINGS TO ADD EXECUTIO D CONSTRUCTI TOJECT SPECIF TEST MANUFA	CARRIED OU URS, SAMPLE E CONTRACTO D KEEPING PRINTED SET RAWINGS ON AND SHARED BE PROVIDE TION DN METHODS ON INDUSTR ICATION MAI CTURER DAT.	r without s, and join pr's end. of latest i site. any f with arch d at projec s shall add- y best prac NUAL FOR A asheets, m	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI SUBJEI 9. DRAW CONTT GOOD ADJUS FINAL 10. STAN ALL M. GUIDE REFER STANE	EVER REQ EXECUTIO DING MAT CT TO REJI <b>VING UPDA</b> RACTOR TO -FOR-CON STMENTS T AS-BUILT I <b>NDARDS &amp;</b> ATERIALS LUNES ANI TO THE PI DARDS. LA	UIRED, MOCK- N. ANY WORK TERIALS, COLOU ECTION AT THE ATES & RECORI D MAINTAIN A ISTRUCTION DI TO BE NOTED A DRAWINGS TO ADD EXECUTIO D CONSTRUCTI TOJECT SPECIF TEST MANUFA	CARRIED OU URS, SAMPLE E CONTRACTO D KEEPING PRINTED SET RAWINGS ON AND SHARED BE PROVIDE TION DN METHODS ON INDUSTR ICATION MAI CTURER DAT.	r without s, and join pr's end. of latest i site. any f with arch d at projec s shall add- y best prac NUAL FOR A asheets, m	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI SUBJEI 9. DRAW CONTF GOOD ADJUS FINAL 10. STAN ALL M GUIDE REFER STANE INSTAI	EVER REQ EXECUTIO DING MAT CT TO REJI ING UPDA RACTOR TG -FOR-CON STMENTS 1 AS-BUILT 1 MOARDS & ATERIALS LUNES AND TO THE PI DARDS. LA' LLATION G	UIRED, MOCK- N. ANY WORK TERIALS, COLOU ECTION AT THE ATES & RECORI D MAINTAIN A ISTRUCTION DI TO BE NOTED A DRAWINGS TO ADD EXECUTIO D CONSTRUCTI TOJECT SPECIF TEST MANUFA	CARRIED OU URS, SAMPLE E CONTRACTO D KEEPING PRINTED SET RAWINGS ON AND SHARED BE PROVIDE TION DN METHODS ON INDUSTR ICATION MAI CTURER DAT.	r without s, and join pr's end. of latest i site. any f with arch d at projec s shall add- y best prac NUAL FOR A asheets, m	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI SUBJEI 9. DRAW CONTT GOOD ADJUS FINAL 10. STAN ALL M GUIDE REFER STANE INSTAI	EVER REQ EXECUTIO DING MAT CT TO REJI ING UPDA RACTOR TG -FOR-CON STMENTS 1 AS-BUILT 1 MOARDS & ATERIALS LUNES AND TO THE PI DARDS. LA' LLATION G	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORT D MAINTAIN A DRAWINGS TO DRAWINGS TO DOCUMENTA AND EXECUTIC D CONSTRUCTI ROJECT SPECIF TEST MANUFA GUIDELINES TO	CARRIED OU URS, SAMPLE E CONTRACTO D KEEPING PRINTED SET RAWINGS ON AND SHARED BE PROVIDE TION DN METHODS ON INDUSTR ICATION MAI CTURER DAT.	r without s, and join pr's end. of latest i site. any f with arch d at projec s shall add- y best prac NUAL FOR A asheets, m	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M. GUIDE REFER STANE INSTAI	EVER REQ EXECUTIO DING MAT CT TO REJI ING UPDA RACTOR TO FOR-CON TIMENTS T AS-BUILT I VDARDS & ATERIALS ELINES AND TO THE PI DARDS. LA LLATION G	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORT D MAINTAIN A DRAWINGS TO DRAWINGS TO DOCUMENTA AND EXECUTIC D CONSTRUCTI ROJECT SPECIF TEST MANUFA GUIDELINES TO	CARRIED OU' URS, SAMPLE CONTRACT D KEEPING PRINTED SET RAWINGS ON NIND SHARED BE PROVIDE TION DI MOETHODS ON INDUSTR ICATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CONTRECTOR DI MAI DI MAI	r without s, and join pr's end. of latest i site. any f with arch d at projec s shall add- y best prac NUAL FOR A asheets, m	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI SUBJEI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANE INSTAI	EVER REQ EXECUTIO DING MAT CT TO REJI ING UPDA RACTOR TO FOR-CON TIMENTS T AS-BUILT I VDARDS & ATERIALS ELINES AND TO THE PI DARDS. LA LLATION G	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORT D MAINTAIN A DRAWINGS TO DRAWINGS TO DOCUMENTA AND EXECUTIC D CONSTRUCTI ROJECT SPECIF TEST MANUFA GUIDELINES TO	CARRIED OU' URS, SAMPLE CONTRACT D KEEPING PRINTED SET RAWINGS ON NIND SHARED BE PROVIDE TION DI MOETHODS ON INDUSTR ICATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CONTRECTOR DI MAI DI MAI	r without s, and join pr's end. of latest i site. any f with arch d at projec s shall add- y best prac NUAL FOR A asheets, m	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI SUBJEI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANE INSTAI	EVER REQ EXECUTIO DING MAT CT TO REJI ING UPDA RACTOR TO FOR-CON STMENTS 1 AS-BUILT 1 VOLARDS & ATERIALS LINES AND TO THE PI DARDS. LA' LLATION G	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORT D MAINTAIN A DRAWINGS TO DRAWINGS TO DOCUMENTA AND EXECUTIC D CONSTRUCTI ROJECT SPECIF TEST MANUFA GUIDELINES TO	CARRIED OU' URS, SAMPLE CONTRACT D KEEPING PRINTED SET RAWINGS ON NIND SHARED BE PROVIDE TION DI MOETHODS ON INDUSTR ICATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CCATION MAI CONTRECTOR DI MAI DI MAI	r without s, and join pr's end. of latest i site. any f with arch d at projec s shall add- y best prac NUAL FOR A asheets, m	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI EVISIO No.	EVER REQ EXECUTIO DING MAT CT TO REJI ING UPDA RACTOR TO -FOR-CON STMENTS I AS-BUILT I MOARDS & ATERIALS LUNES AND TO THE PI DARDS LA LLATION G	UIRED, MOCK- N. ANY WORK FERIALS, COLOI ECTION AT THE TTES & RECORE D MAINTAIN A STRUCTION DI TO BE NOTED A DRAWINGS TO AND EXECUTIO D CONSTRUCTI TEST MANUFA UIDELINES TO	CARRIED OU' URS, SAMPLE CONTRACT D KEEPING PRINTED SET RAWINGS ON NUD SHARED BE PROVIDE BE PROVIDE TION N METHODS ON INDUSTR ICATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI SECONTRE DAT	T WITHOUT S, AND JOIN R'S END. OF LATEST ISITE. ANY WITH ARCH J AT PROJEC S SHALL ADD Y BEST PRAV UUAL FOR A SSHEETS, M SITE FOR RE	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTUREI CTICES. CONTRACTOR TC LLI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI EVISIO No.	EVER REQ EXECUTIO DING MAT CT TO REJI ING UPDA RACTOR TO -FOR-CON STMENTS I AS-BUILT I MOARDS & ATERIALS LUNES AND TO THE PI DARDS LA LLATION G	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORE D MAINTAIN A STRUCTION DI TO BE NOTED A DRAWINGS TO BOCUMENTA AND EXECUTIC D CONSTRUCTI EST MANUFA UIDELINES TO	CARRIED OU' URS, SAMPLE E CONTRACT D KEEPING PRINTED SET AWINGS ON NND SHARED BE PROVIDE TION BE PROVIDE TION DN METHODS ON INDUSTR ICATION MAI TCTURER DAT BE KEPT ON BE KEPT ON BE KEPT ON	T WITHOUT S, AND JOIN R'S END. OF LATEST ISITE. ANY WITH ARCH D AT PROJECT S SHALL ADH Y BEST PRAC SHALL ADH Y	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LL TECHNICAL SDS, FIRE RATINGS, AND
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI EVISIO No.	EVER REQ EXECUTIO DING MAT CT TO REJI ING UPDA RACTOR TO -FOR-CON STMENTS I AS-BUILT I MOARDS & ATERIALS LUNES AND TO THE PI DARDS LA LLATION G	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORE D MAINTAIN A STRUCTION DI TO BE NOTED A DRAWINGS TO BOCUMENTA AND EXECUTIC D CONSTRUCTI EST MANUFA UIDELINES TO	CARRIED OU' URS, SAMPLE CONTRACT D KEEPING PRINTED SET RAWINGS ON NUD SHARED BE PROVIDE BE PROVIDE TION N METHODS ON INDUSTR ICATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI CLATION MAI SECONTRE CONTRACTOR BE KEPT ON	T WITHOUT S, AND JOIN R'S END. OF LATEST ISITE. ANY WITH ARCH D AT PROJECT S SHALL ADH Y BEST PRAC SHALL ADH Y	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTUREI CTICES. CONTRACTOR TC LLI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI EVISIO No.	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO FOR-CON STMENTS 1 AS-BUILT I VOLARDS & ATERIALS LILATION G NS DARDS LA' LLATION G	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORE D MAINTAIN A STRUCTION DI TO BE NOTED A DRAWINGS TO BOCUMENTA AND EXECUTIC D CONSTRUCTI EST MANUFA UIDELINES TO	CARRIED OU' URS, SAMPLE E CONTRACT D KEEPING PRINTED SET AWINGS ON NND SHARED BE PROVIDE TION BE PROVIDE TION DN METHODS ON INDUSTR ICATION MAI TCTURER DAT BE KEPT ON BE KEPT ON BE KEPT ON	T WITHOUT S, AND JOIN R'S END. OF LATEST ISITE. ANY WITH ARCH D AT PROJECT S SHALL ADH Y BEST PRAC SHALL ADH Y	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTUREI CTICES. CONTRACTOR TC LLI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI SUBJET 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANE INSTAT DOD Title	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO ING POPA RACTOR TO INGENERATION STMENTS 1 AS-BUILT I VADARDS & ATERIALS LILATION G ILATION G DATE DATE DATE LILATION G	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORD TO BE NOTED A DRAWINGS TO AND EXECUTIO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO DOSTRUCTI EST MANUFA GUIDELINES TO	CARRIED OU'URS, SAMPLE CONTRACTE D KEEPING PRINTED SET AWINGS ON AND SHARED BE PROVIDE TION NM METHODS ON INDUSTR ICTURER DAT. BE KEPT ON BE KEPT ON BE SECTIPTION BE KEPT ON	T WITHOUT S, AND JOIN R'S END. OF LATEST SOF LATEST ISTE: ANY WITH ARCH D AT PROJECT SHALL ADP Y BEST PRA- NUAL FOR A SAHEETS, M SITE FOR RE	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LL TECHNICAL SDS, FIRE RATINGS, AND FERENCE. TORIUM,
AND P 8. APPRC WHER MASS INCLUI SUBJET 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANE INSTAT DOD Title	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO ING POPA RACTOR TO INGENERATION STMENTS 1 AS-BUILT I VADARDS & ATERIALS LILATION G ILATION G DATE DATE DATE LILATION G	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN A STRUCTION DI TO BE NOTED A DRAWINGS TO CODUMENTA AND EXECUTIC D CONSTRUCTI EST MANUFA UIDELINES TO DI DOCUMENTA AND EXECUTIC D CONSTRUCTI TEST MANUFA UIDELINES TO DE DE DE DE DE DE DE DE DE DE DE DE DE	CARRIED OU'URS, SAMPLE CONTRACTE OSCIMATION DEEPING PRINTED SET AWVINGS ON IND SHARED BE PROVIDE TION DI METHODS ON INDUSTR ICATION MAI TON DI METHODS ON INDUSTR ICATION MAI TON DI METHODS ON INDUSTR ICATION MAI CATRON BE KEPT ON DESCRIPTION ESSITY / CARAC	TWITHOUT S, AND JOIN JR'S END. OF LATEST ISITE. ANY WITH ARCH D AT PROJEC S SHALL ADD Y BEST PRAI UDAL FOR A SSHEETS, M SITE FOR RE AUDIT SHI.	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LIL TECHNICAL ISSS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI SUBJET 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANE INSTAT DOD Title	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO ING POPA RACTOR TO INGENERATION STMENTS 1 AS-BUILT I VADARDS & ATERIALS LILATION G ILATION G DATE DATE DATE LILATION G	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORD TO BE NOTED A DRAWINGS TO AND EXECUTIO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO DOSTRUCTI EST MANUFA GUIDELINES TO	CARRIED OU'URS, SAMPLE CONTRACTE OSCIMATION DEEPING PRINTED SET AWVINGS ON IND SHARED BE PROVIDE TION DI METHODS ON INDUSTR ICATION MAI TON DI METHODS ON INDUSTR ICATION MAI TON DI METHODS ON INDUSTR ICATION MAI CATRON BE KEPT ON DESCRIPTION ESSITY / CARAC	TWITHOUT S, AND JOIN JR'S END. OF LATEST ISITE. ANY WITH ARCH D AT PROJEC S SHALL ADD Y BEST PRAI UDAL FOR A SSHEETS, M SITE FOR RE AUDIT SHI.	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LIL TECHNICAL ISSS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANE INSTAI DO NO. JOD Title GE	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO ING UPDA RACTOR TO INGENERATION STMENTS T AS-BUILT I VADARDS & ATERIALS LILATION G DARDS, LA' LILATION G DARDS, LA' LILATION G UIT U INS Date	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN A STRUCTION DI TO BE NOTED A DRAWINGS TO CODUMENTA AND EXECUTIC D CONSTRUCTI EST MANUFA UIDELINES TO DI DOCUMENTA AND EXECUTIC D CONSTRUCTI TEST MANUFA UIDELINES TO DE DE DE DE DE DE DE DE DE DE DE DE	CARRIED OU' URS, SAMPLE E CONTRACT D KEEPING PRINTED SET AWINGS ON ND SHARED BE PROVIDE TION DN METHODS ON INDUSTR ICTURER DAT. BE KEPT ON BE KEPT ON BE KEPT ON CARAC	TWITHOUT S, AND JOIN JR'S END. OF LATEST ISITE. ANY WITH ARCH D AT PROJEC S SHALL ADD Y BEST PRAI UDAL FOR A SSHEETS, M SITE FOR RE AUDIT SHI.	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LIL TECHNICAL ISSS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI DOD	ever req execution Ding MAT ct to rejuting upp/ ractor to rejuting ing upp/ ractor to rejuting ing upp/ ractor to rejuting ither in the regular of the regul	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN AN ISTRUCTION DF TO BE NOTED A DRAWINGS TO DRAWINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO DOCUMENTA SUIDELINES TO DOCUMENTA BACCK DOCUMENTA MANUFAS UDDELINES TO DE DE DE DE DE DE DE DE DE DE DE DE DE	CARRIED OU'URS, SAMPLE CONTRACTE ON CONTRACT DECONTRACTO DECONTRACTO DECONTRACTO DISCONTRACTOR DISCONTACTOR DISCON	TWITHOUT S, AND JOIN JR'S END. OF LATEST ISITE. ANY WITH ARCH D AT PROJEC S SHALL ADD Y BEST PRAI UDAL FOR A SSHEETS, M SITE FOR RE AUDIT SHI.	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LIL TECHNICAL ISSS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI JOD Title GE Desi	ever req execution bins matrice to rejuins matrice ina upport actor to rejuins ina upport actor to rejuins ithered at a attentals attent	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN AN STRUCTION DF TO BE NOTED A DRAWINGS TO DRAWINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO DOCUM	CARRIED OU'URS, SAMPLE CONTRACTE ON CONTRACT DECONTRACTO PRINTED SET AWINGS ON IND SHARED BE PROVIDE TION DIM METHODO BE PROVIDE TION DIM METHODO DI INDUSTR ICATION MAI CATURED DAT BE KEPT ON RESERVING CARLANCE CARLANCE CALLANCE	SAND JOIN S, AND JOIN JOF LATEST SOF LA	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LIL TECHNICAL ISSS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI JOD Title GE Desi	ever req execution bins matrice to rejuins matrice ina upport actor to rejuins ina upport actor to rejuins ithered at a attentals attent	UIRED, MOCK- N. ANY WORK TERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN AN ISTRUCTION DF TO BE NOTED A DRAWINGS TO DRAWINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO DOCUMENTA SUIDELINES TO DOCUMENTA BACCK DOCUMENTA MANUFAS UDDELINES TO DE DE DE DE DE DE DE DE DE DE DE DE DE	CARRIED OU'URS, SAMPLE CONTRACTE ON CONTRACT DECONTRACTO PRINTED SET AWINGS ON IND SHARED BE PROVIDE TION DIM METHODO BE PROVIDE TION DIM METHODO DI INDUSTR ICATION MAI CATURED DAT BE KEPT ON RESERVING CARLANCE CARLANCE CALLANCE	SAND JOIN S, AND JOIN JOF LATEST SOF LA	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDLINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TC LIL TECHNICAL ISSS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANE INSTAI DESI DESI C	EVER REQ EXECUTION DING MAT CT TO REJU ING UPDA RACTOR TO INGACTOR TO INGACTOR TO INGACTOR TO INTERNATION OF INTERNATION OF INTERNATIONO OF INTERNATIONO OF INTERNATIONO OF		CARRIED OUTURS, SAMPLE ECONTRACT ECONTRACT ECONTRACT ENTRO IND SHARED BE PROVIDE TION IND SHARED BE PROVIDE TION IND SHARED BE PROVIDE TION IND SHARED BE REPTON BE KEPT ON EXECTION CONTRACT EXECTION CONTRACT EXECTION CONTRACT EXECTION CONTRACT EXECTION CONTRACT EXECTION CONTRACT EXECUTION CONTRACT	TWITHOUT S, AND JOIN JR'S END. OF LATEST ISTE. ANY WITH ARCH D AT PROJEC SHALL ADDY Y BEST PRAV NUAL FOR A SAHEETS, M SITE FOR RE AUDIT CHI CHI CHI CHI CHI CHI CHI CHI CHI CHI	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STAND INSTAI DOD I JOD I C C 14 F	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO INGACTOR TO INGACTOR TO INGACTOR TO INTERNALS ATERIALS LUNES AND TO THE PI DARDS AS ATERIALS LUNES AND TO THE PI DARDS AS ATERIALS LUNES DARDS AND TO THE PI DARDS AND TO	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD STRUCTION DI TO BE NOTED A DRAWINGS TO DRAWINGS TO DOCUMENTA AND EXECUTIC D CONSTRUCTI CODECTSPECIF TEST MANUFA UIDELINES TO DECEMBER ADDECT STRUCTOR DECEMBER ADDECT DECEMBER CONSULT CON	CARRIED OU'URS, SAMPLE ECONTRACT ECONTRACT ECONTRACT DEEPING PRINTED SET AWINGS ON IND SHARED BE PROVIDE TION IND SHARED BE PROVIDE TION IND SHARED BE REPTON BE KEPT ON SECTIPTION BE KEPT ON SECTIPTION CARACT CAR	AUDIT SHALLADF AUDIT SHALLADF	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI JOD TITLE GE DESI C C 14 FW	ever Req executio Ding MAT ct to Reju ing upp/ ractor to FOR-CON STMENTS 1 as-BUILT VOARDS & ATERIALS ELINES AND TO THE PI DARDS LA' LLATION G UIT U ENER On C SOL C, Lane 7, WWW.najmbi	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN A ISTRUCTION DF TO BE NOTED A DISTRUCTION OF DED WINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO D	CARRIED OU'URS, SAMPLE CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT NUM SON NUM STARED SE PROVIDE TION SON METHODS ON INDUSTR ICATION MAI CATION MAI TION SON METHODS ON INDUSTR ICATION MAI CATION BE KEPT ON SON CARRANCE CA	AUDIT SHALLADF AUDIT SHALLADF	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI JOD TITLE GE DESI C C 14 FW	ever Req executio Ding MAT ct to Reju ing upp/ ractor to FOR-CON STMENTS 1 as-BUILT VOARDS & ATERIALS ELINES AND TO THE PI DARDS LA' LLATION G UIT U ENER On C SOL C, Lane 7, WWW.najmbi	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD STRUCTION DI TO BE NOTED A DRAWINGS TO DRAWINGS TO DOCUMENTA AND EXECUTIC D CONSTRUCTI CODECTSPECIF TEST MANUFA UIDELINES TO DECEMBER ADDECT STRUCTOR DECEMBER ADDECT DECEMBER CONSULT CON	CARRIED OU'URS, SAMPLE CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT NUM SON NUM STARED SE PROVIDE TION SON METHODS ON INDUSTR ICATION MAI CATION MAI TION SON METHODS ON INDUSTR ICATION MAI CATION BE KEPT ON SON CARRANCE CA	AUDIT SHALLADF AUDIT SHALLADF	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI JOD TITLE GE DESI C C 14 FW	ever Req executio Ding MAT ct to Reju ing upp/ ractor to FOR-CON STMENTS 1 as-BUILT VOARDS & ATERIALS ELINES AND TO THE PI DARDS LA' LLATION G UIT U ENER On C SOL C, Lane 7, WWW.najmbi	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN A ISTRUCTION DF TO BE NOTED A DISTRUCTION OF DED WINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO D	CARRIED OU'URS, SAMPLE CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT NUM SON NUM STARED SE PROVIDE TION SON METHODS ON INDUSTR ICATION MAI CATION MAI TION SON METHODS ON INDUSTR ICATION MAI CATION BE KEPT ON SON CARRANCE CA	AUDIT SHALLADF AUDIT SHALLADF	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI JOD TITLE GE DESI C C 14 FW	ever Req executio Ding MAT ct to Reju ing upp/ ractor to FOR-CON STMENTS 1 as-BUILT VOARDS & ATERIALS ELINES AND TO THE PI DARDS LA' LLATION G UIT U ENER On C SOL C, Lane 7, WWW.najmbi	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN A ISTRUCTION DF TO BE NOTED A DISTRUCTION OF DED WINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO D	CARRIED OU'URS, SAMPLE CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT NUM SON NUM STARED SE PROVIDE TION SON METHODS ON INDUSTR ICATION MAI CATION MAI TION SON METHODS ON INDUSTR ICATION MAI CATION BE KEPT ON SON CARRANCE CA	AUDIT SHALLADF AUDIT SHALLADF	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI JOD TITLE GE DESI C C 14 FW	ever Req executio Ding MAT ct to Reju ing upp/ ractor to FOR-CON STMENTS 1 as-BUILT VOARDS & ATERIALS ELINES AND TO THE PI DARDS LA' LLATION G UIT U ENER On C SOL C, Lane 7, WWW.najmbi	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN A ISTRUCTION DF TO BE NOTED A DISTRUCTION OF DED WINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO D	CARRIED OU'URS, SAMPLE CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT NUM SON NUM STARED SE PROVIDE TION SON METHODS ON INDUSTR ICATION MAI CATION MAI TION SON METHODS ON INDUSTR ICATION MAI SE KEPT ON BE KEPT ON SECTIPTION SECTIPTION CARLON	AUDIT SHALLADF AUDIT SHALLADF	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI JOD TITLE GE CC 14 FW	ever Req executio Ding MAT ct to Reju ing upp/ ractor to FOR-CON STMENTS 1 as-BUILT VOARDS & ATERIALS ELINES AND TO THE PI DARDS LA' LLATION G UIT U ENER On C SOL C, Lane 7, WWW.najmbi	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN A ISTRUCTION DF TO BE NOTED A DISTRUCTION OF DED WINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO D	CARRIED OU'URS, SAMPLE CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT NUM SON NUM STARED SE PROVIDE TION SON METHODS ON INDUSTR ICATION MAI CATION MAI TION SON METHODS ON INDUSTR ICATION MAI SE KEPT ON BE KEPT ON SECTIPTION SECTIPTION CARLON	AUDIT SHALLADF AUDIT SHALLADF	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRC WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GUIDE REFER STANC INSTAI DESI DESI C C 14 FW	ever Req executio Ding MAT ct to Reju ing upp/ ractor to FOR-CON STMENTS 1 as-BUILT VOARDS & ATERIALS ELINES AND TO THE PI DARDS LA' LLATION G UIT U ENER On C SOL C, Lane 7, WWW.najmbi	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN A ISTRUCTION DF TO BE NOTED A DISTRUCTION OF DED WINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO D	CARRIED OU'URS, SAMPLE CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT NUM SON NUM STARED SE PROVIDE TION SON METHODS ON INDUSTR ICATION MAI CATION MAI TION SON METHODS ON INDUSTR ICATION MAI SE KEPT ON BE KEPT ON SECTIPTION SECTIPTION CARLON	AUDIT SHALLADF AUDIT SHALLADF	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRO WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAN ALL M GOOD REFER STANE INSTAI DESI DESI C C 14 FW	ever Req execution Ding MAT cr to Reju ing upp/ ractor to Reju ing upp/ school to result ing upp	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN A ISTRUCTION DF TO BE NOTED A DISTRUCTION OF DED WINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO D	CARRIED OU'URS, SAMPLE CONTRACT CONTRACT CONTRACT CONTRACT CONTRACT NUM SON NUM STARED SE PROVIDE TION SON METHODS ON INDUSTR ICATION MAI CATION MAI TION SON METHODS ON INDUSTR ICATION MAI SE KEPT ON BE KEPT ON SECTIPTION SECTIPTION CARLON	AUDIT SHALLADF AUDIT SHALLADF	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SOS, FIRE RATINGS, AND FERENCE.
AND P 8. APPRO WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAM GUIDE REFER STANDAI INSTAI Desi C C C C C MEF	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO FOR-CON STMENTS T AS-BUILT VADARDS & ATERIALS LUINES AND TO THE PI DARDS LA' LLATION G DATE DARDS LA' LLATION G COLL C. Lane 7. M 192:21-35242 WW-najmbi CO	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD STRUCTION DI TO BE NOTED A DISTRUCTION DI TO BE NOTED A DISTRUCTION DI CODUMENTA AND EXECUTIC DISTRUCTION	CARRIED OUTURS, SAMPLE CONTRACT CONTRACT CONTRACT DECONTRACT DESCRIPTION DIAL SECONTRACT DIAL SECONTRACT DIAL SECONTRACT SECONT SECONTRACT SECONT SE	AUDIT SHALL ADP VEST PRAVISE SHALL ADP VEST PRAVISE STATE	PRIOR APPROVAL, IERY DETAILS, SHALL BE MARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! TICES. CONTRACTOR TO LIL TECHNICAL SSD, FIRE RATINGS, AND FERENCE. TORIUM, CORIUM, CORIUM, Karachi, Pakistan.
AND P 8. APPRO WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAM GUIDE REFER STANDAI INSTAI DESI C C C C C C MEF	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO FOR-CON STMENTS T AS-BUILT VADARDS & ATERIALS LUINES AND TO THE PI DARDS LA' LLATION G DATE DARDS LA' LLATION G COLL C. Lane 7. M 192:21-35242 WW-najmbi CO	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD DMAINTAIN A ISTRUCTION DF TO BE NOTED A DISTRUCTION OF DED WINGS TO DOCUMENTA AND EXECUTIO DOCUMENTA AND EXECUTIO D	CARRIED OUTURS, SAMPLE CONTRACT CONTRACT CONTRACT DECONTRACT DESCRIPTION DIAL SECONTRACT DIAL SECONTRACT DIAL SECONTRACT SECONT SECONTRACT SECONT SE	AUDIT SHALL ADP VEST PRAVISE SHALL ADP VEST PRAVISE STATE	PRIOR APPROVAL, IERY DETAILS, SHALL BE MARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! TICES. CONTRACTOR TO LIL TECHNICAL SSD, FIRE RATINGS, AND FERENCE. TORIUM, CORIUM, CORIUM, Karachi, Pakistan.
AND P 8. APPRO WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUSS FINAL 10. STAM GUIDE REFER STANDAI INSTAI DESI C C C C C C MEF	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO FOR-CON STMENTS T AS-BUILT VADARDS & ATERIALS LUINES AND TO THE PI DARDS LA' LLATION G DATE DARDS LA' LLATION G COLL C. Lane 7. M 192:21-35242 WW-najmbi CO	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD STRUCTION DI TO BE NOTED A DISTRUCTION DI TO BE NOTED A DISTRUCTION DI CODUMENTA AND EXECUTIC DISTRUCTION	CARRIED OUTURS, SAMPLE CONTRACT CONTRACT CONTRACT DECONTRACT DESCRIPTION DIAL SECONTRACT DIAL SECONTRACT DIAL SECONTRACT SECONT SECONTRACT SECONT SE	AUDIT SHALL ADP VEST PRAVISE SHALL ADP VEST PRAVISE STATE	PRIOR APPROVAL, IERY DETAILS, SHALL BE MARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! TICES. CONTRACTOR TO LIL TECHNICAL SSD, FIRE RATINGS, AND FERENCE. TORIUM, CORIUM, CORIUM, Karachi, Pakistan.
AND P 8. APPRO WHER MASS INCLUI 9. DRAW CONTF GOOD ADJUS FINAL 10. STAM GUIDE REFER STAM Desi C C 14. T FINAL STAM MEF	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO FOR-CON STMENTS T AS-BUILT VADARDS & ATERIALS LUINES AND TO THE PI DARDS LA' LLATION G DATE DARDS LA' LLATION G COLL C. Lane 7. M 192:21-35242 WW-najmbi CO	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TTES & RECORD STRUCTION DI TO BE NOTED A DISTRUCTION DI TO BE NOTED A DISTRUCTION DI CODUMENTA AND EXECUTIC DISTRUCTION	CARRIED OUTURS, SAMPLE CONTRACT CONTRACT CONTRACT DECONTRACT DESCRIPTION DIAL SECONTRACT DIAL SECONTRACT DIAL SECONTRACT SECONT SECONTRACT SECONT SE	AUDIT SHALL ADP VEST PRAVISE SHALL ADP VEST PRAVISE STATE	PRIOR APPROVAL, IERY DETAILS, SHALL BE MARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! TICES. CONTRACTOR TO LIL TECHNICAL SSD, FIRE RATINGS, AND FERENCE. TORIUM, CORIUM, CORIUM, Karachi, Pakistan.
AND P 8. APPRO WHER MASS INCLUI 9. DRAW CONTE GOOD ADJUSE FINAL 10. STAP ADJUSE REFER STAP Desi C C 14. T F W MEP	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO INGACTOR TO INGACTOR TO INGACTOR TO INGACTOR TO INGACTOR TO INGACTOR IN DARDS AND TO THE PI DARDS AND TO THE	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TES & RECORD STRUCTION DF TO BE NOTED A DISTRUCTION OF TO BE NOTED A DOCUMENTA AND EXECUTIO DOSTRUCTI DOCUMENTA AND EXECUTIO DOSTRUCTI EST MANUFA IUDELINES TO INTVER K CAL AR BACK CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT	CARRIED OUTURS, SAMPLE CONTRACT CONTRACT CONTRACT DECONTRACT DESCRIPTION DIAL SECONTRACT DIAL SECONTRACT DIAL SECONTRACT SECONT SECONTRACT SECONT SE	AUDIT SHALL ADP VEST PRAVISE SHALL ADP VEST PRAVISE STATE	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SSD, FIRE RATINGS, AND FERENCE. CORIUM, CORIUM, CORIUM, NGSS
AND P 8. APPRO WHER MASS INCLUI 9. DRAW CONTE GOOD ADJUSS FINAL 10. STAP ADJUSE FINAL 10. STAP ADJUSE FINAL 10. STAP ADJUSE FINAL 10. STAP ADJUSE FINAL 10. STAP ADJUSE FINAL 10. STAP STAP	EVER REQ EXECUTIO DING MAT CT TO REJU ING UPDA RACTOR TO FOR-CON STMENTS T AS-BUILT VADARDS & ATERIALS LILATION G INTO THE PI DARDS LA LILATION G INTO THE PI DARDS LA LILATION G INTO THE PI DARDS LA LILATION G INTO THE PI DARDS AND TO THE PI DARD	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TES & RECORD STRUCTION DF TO BE NOTED A DISTRUCTION OF TO BE NOTED A DOCUMENTA AND EXECUTIO DOSTRUCTI DOCUMENTA AND EXECUTIO DOSTRUCTI EST MANUFA IUDELINES TO INTVER K CAL AR BACK CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT INTVER K CONSULT	CARRIED OUTURS, SAMPLE CONTRACT CONTRACT CONTRACT DECONTRACT DESCRIPTION DIAL SECONTRACT DIAL SECONTRACT DIAL SECONTRACT SECONT SECONTRACT SECONT SE	AUDIT SHALLADF SHALLA	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SSD, FIRE RATINGS, AND FERENCE. CORIUM, CORIUM, CORIUM, NGSS
AND P 8. APPRO WHER MASS INCLUI 9. DRAW CONTE GOOD ADJUSS FINAL 10. STAP ALL M GUIDE REFER STAP Desi JOD Title GE Desi C C 14 T F MEF	ever Req execution DING MAT ct to REJU ING UPDA RACTOR TO STMENTS TA SA-BUILT VARDS AND TO THE PI DARDS AS ATERIALS LLATION G CO DATE C. LANE T UIT U C. LANE T UIT U C. LANE T CO CO CO CO CO CO CO CO CO CO CO CO CO	UIRED, MOCK- N. ANY WORK PERIALS, COLOI ECTION AT THE TES & RECORD STRUCTION DF TO BE NOTED A DISTRUCTION OF TO BE NOTED A DOCUMENTA AND EXECUTIO DOCUMENTA AND	CARRIED OUTURS, SAMPLE ECONTRACT DEEPING PRINTED SET AWINGS ON ND SHARED BE PROVIDE TION DI METHODS ON INDUSTR ICTURER DAT STOT ARACC CAC	AUDIT SHALL ADP Y BEST PRAMULA SHALL ADP Y BEST PRAMULA FOR A SHALL ADP Y BEST PRAMULA SHALL ADP	PRIOR APPROVAL, IERY DETAILS, SHALL BE WARK-UP OR REDUINE ITECT ON WEEKLY BASIS CT CLOSEOUT. IERE TO MANUFACTURE! CTICES. CONTRACTOR TO LIL TECHNICAL SSD, FIRE RATINGS, AND FERENCE. CORIUM, CORIUM, CORIUM, NGSS




ALL DE**NORE:** AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.

TAG LE	EGEND			Reference to
	000 Spe	erence to Finishe cification. ex Reference		Elevation Drawing. Elevation Reference
L	————Finis	h Reference	I-1.00	Drawing No. Zone Reference
$\left( \right)$	Det	erence to ail Drawing. ail No.		
		wing No. erence.		
WALL L	EGEND			
		Existing Wall		Structural Column
		Curtain Wall		Cement Board Partition Wall
		Fixed Glazing		Proposed Wall
GENE	RAL NOTE	s		
1. COO	RDINATION &	VERIFICATION BE READ IN CONJU	INCTION WITH A	RCHITECTURAL,
SPEC CON	TRACTOR MUS	LTANT DRAWINGS, ST VERIFY ALL DIME	SPECIFICATIONS NSIONS, LEVELS,	FIRE SAFETY, AND ALL , AND DETAIL DOCUMENT AND SITE CONDITIONS
CON	FLICTS SHALL		IE ATTENTION OF	REPANCIES, OMISSIONS, C THE ARCHITECT FOR
IN TH	HE EVENT THAT SOLE RESPON	SIBILITY OF THE CO	NTRACTOR TO RE	HOWN OR PROVIDED, IT I QUEST THE REQUIRED
EXEC TIME	CUTION SHALL E. "NOT AWAR	NOT BE USED AS A	BASIS FOR ANY C	UCH DETAILS PRIOR TO CLAIMS OR EXTENSIONS OF CONSIDERED A VALID
ALL V	<b>KAGE PREVENT</b> WET AREAS, R		AND SERVICE ZC	INES TO BE TREATED WITH
POIN WHE	ITS ARE LEFT U RE APPLICABL	INSEALED. MOCK-U E) MUST BE CONDU	IP AND TESTING ( JCTED AND VERIF	TO ENSURE NO LEAKAGE INCLUDING POND TESTS TIED BY THE
4. WOO ALL V	DDEN ELEMEN WOODEN SUR	FACES TO BE TREAT	ED WITH ANTI-TI	ERMITE SOLUTION AND
DOC PROI	UMENTED PRO DUCT DATA SH	IEETS) TO BE SUBM	T APPLICATION (I ITTED FOR APPRO	NCLUDING MSDS AND DVAL. UNTREATED OR
CON 5. EXPC	TRACTOR'S RE DSED METAL E	SPONSBILITY LEMENTS		
FITTI COA	INGS, AND FIX T SUITABLE TC	TURES) TO BE COAT SPECIFIED ENVIRO	ED WITH ANTI-R	RAL, JOINERY SUPPORTS, UST PRIMER AND FINISH ITIONS. FINAL PAINT FINIS FECTS SUCH AS PEELING,
RUST 6. HAZ/	r, or discolo <b>Ardous Mat</b>	RATION. E <b>RIALS &amp; SAFETY FI</b>	NISHES	
EXPC NON	DSED IN THE B	JILT ENVIRONMEN	T. ALL MATERIALS D OTHERWISE), (	CHILD-SAFE (WHERE
ENVI SUBI	IRONMENTAL MITTED AS PA	STANDARDS. CERTII RT OF HANDOVER.	FICATES OF CONF	
ALL ( BUIL	CONSTRUCTIO DING CODES,	OSHA STANDARDS,	CARRIED OUT IN AND SITE SAFETY	I COMPLIANCE WITH LOC/ Y REQUIREMENTS. ORY FOR ALL WORKERS.
CON AND	TRACTOR TO E	NSURE BARRICADI	NG, SAFETY SIGN	DRY FOR ALL WORKERS. AGE, FIRE EXTINGUISHERS
WHE MAS	ROVALS & MO	RED, MOCK-UPS MI		O AND APPROVED PRIOR T PRIOR APPROVAL,
INC	S EXECUTION.			NERY DETAILS SHALL BE
SUBJ <b>9. DRA</b> Y	S EXECUTION. UDING MATEF IECT TO REJEC WING UPDATI	IALS, COLOURS, SA TION AT THE CONTF ES & RECORD KEEPI	MPLES, AND JOIN RACTOR'S END. NG	NERY DETAILS, SHALL BE
SUBJ <b>9. DRA</b> CON GOO ADJU	S EXECUTION. UDING MATEF JECT TO REJEC WING UPDATI TRACTOR TO N DD-FOR-CONST JSTMENTS TO	IALS, COLOURS, SA TION AT THE CONTE S & RECORD KEEPI MAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH	MPLES, AND JOIR RACTOR'S END. NG ID SET OF LATEST GS ON SITE. ANY ARED WITH ARCH	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS.
SUBJ 9. DRA CON GOO ADJU FINA 10. ST/ ALL I	S EXECUTION. UDING MATER JECT TO REJECT WING UPDATI TRACTOR TO IN TRACTOR TO IN JSTMENTS TO LL AS-BUILT DR ANDARDS & D MATERIALS AN	IIALS, COLOURS, SA FION AT THE CONTE SS & RECORD KEEPI AAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRC OCUMENTATION ID EXECUTION MET	MPLES, AND JOIN RACTOR'S END. <b>NG</b> ED SET OF LATEST GS ON SITE. ANY ARED WITH ARCH OVIDED AT PROJE	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER
SUBJ 9. DRA CON GOO ADJU FINA 10. ST/ ALL I GUID REFE STAM	S EXECUTION. UDING MATEFI JECT TO REJEC WING UPDATI TRACTOR TO I D-FOR-CONST JSTMENTS TO JSTMENTS TO LAS-BUILT DR MATERIALS AN DELINES AND C IR TO THE PRO NDARDS. LATE:	IIALS, COLOURS, SA TION AT THE CONTE S& RECORD KEEPI MAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH/ AWINGS TO BE PRO OCUMENTATION ID EXECUTION MET CONSTRUCTION IND JECT SPECIFICATIOI	MPLES, AND JOIR RACTOR'S END. NG D SET OF LATEST SS ON SITE. ANY ARED WITH ARCH DVIDED AT PROJE 'HODS SHALL ADH USTRY BEST PRA N MANUAL FOR A R DATASHEETS, M	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISOS, FIRE RATINGS, AND
SUBJ 9. DRA CON GOO ADJU FINA 10. ST/ ALL I GUID REFE STAM	S EXECUTION, UDING MATER JECT TO REJEC WING UPDATI TRACTOR TO I DD-FOR-CONST JSTMENTS TO IL AS-BUILT DR ANDARDS & D MATERIALS AN DELINES AND C IR TO THE PRO NDARDS, LATE: ALLATION GUI	IIALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AMINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH- AWINGS TO BE PRC OCUMENTATION ID EXECUTION NET CONSTRUCTION IND JECT SPECIFICATION ST MANUFACTUREF	MPLES, AND JOIN NACTOR'S END. NG D SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH VIDED AT PROJE VIDED AT PROJE VIDED SHALL ADH N MANUAL FOR A D DATASHEETS, M T ON SITE FOR RE	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISOS, FIRE RATINGS, AND
SUBJ 9. DRA GOO ADJU FINA 10. ST/ ALL GUIC REFE STAM INST.	S EXECUTION, UDING MATER JECT TO REJEC WING UPDATI TRACTOR TO N DD-FOR-CONST JSTMENTS TO L AS-BUILT DR ANDARDS & D DELINES AND C IR TO THE PRO VDARDS. LATE: ALLATION GUI	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRC OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEP	MPLES, AND JOIN NACTOR'S END. NG D SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH VIDED AT PROJE VIDED AT PROJE VIDED SHALL ADH N MANUAL FOR A D DATASHEETS, M T ON SITE FOR RE	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISOS, FIRE RATINGS, AND
SUBJ 9. DRA' CON GOO ADJU FINA 10. STA ALL I GUIC REFE STAN INST.	S EXECUTION, UDING MATER JECT TO REJEC WING UPDATI TRACTOR TO I DO-FOR-CONST ANDARDS & D NATERIALS AND DELINES AND C IR TO THE PRO VDARDS. LATE: ALLATION GUI	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRC OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEP	MPLES, AND JOIN NACTOR'S END. NG D SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH VIDED AT PROJE VIDED AT PROJE VIDED SHALL ADH N MANUAL FOR A D DATASHEETS, M T ON SITE FOR RE	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISOS, FIRE RATINGS, AND
SUBJ 9. DRA GOO ADJU FINA 10. ST/ ALL GUIC REFE STAM INST.	SEXECUTION. UDING MATERI IECT TO REJEC WING UPDATI TRACTOR TO P DO-FOR-CONST JSTMENTS TO L AS-BUILT DR ANDARDS & D MATERIALS AND DELINES AND C IR TO THE PRO WATERIALS AND DARDS. LATE ALLATION GUI ONS Date	IALS, COLOURS, SA TION AT THE CONT IS & RECORD KEEPI AAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH. AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION DELINES TO BE KEPI DELINES TO BE KEPI DELINES TO BE KEPI	MPLES, AND JOIN NACTOR'S END. NG DO SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH VIDED AT PROJE USTRY BEST PRA N MANUAL FOR A R DATASHEETS, M T ON SITE FOR RE	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISDS, FIRE RATINGS, AND FERENCE.
SUBJ 9. DRA' CON GOO ADJU FINA 10. STA ALL I GUIC REFE STAN INST.	SEXECUTION. UDING MATERI IECT TO REJEC WING UPDATI TRACTOR TO P DO-FOR-CONST JSTMENTS TO L AS-BUILT DR ANDARDS & D MATERIALS AND DELINES AND C IR TO THE PRO WATERIALS AND DARDS. LATE ALLATION GUI ONS Date	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AMINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRC OCUMENTATION ID EXECUTION MED ID EXECU	MPLES, AND JOIN NACTOR'S END. NG DO SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH VIDED AT PROJE USTRY BEST PRA N MANUAL FOR A R DATASHEETS, M T ON SITE FOR RE	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISDS, FIRE RATINGS, AND FERENCE.
SUBJ 9. DRA' CON GOO ADJU FINA 10. STA ALL I GUIC REFE STAN INST.	S EXECUTION. UDING MATERI JECT TO REJEC WING UPDATI TRACTOR TO N DD-FOR-CONST ANDARDS & D MATERIALS AN DELINES AND C IR TO THE PRO VOARDS. LATE ALLATION GUI Date UIT UI	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AMINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRC OCUMENTATION ID EXECUTION MED ID EXECU	MPLES, AND JOIR ACTOR'S END. NG ID SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH HODS SHALL ADD HODS SHALL ADD USTRY BEST PRA N MANUAL FOR A DATASHEETS, M T ON SITE FOR RE	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISDS, FIRE RATINGS, AND FERENCE.
SUBJ 9. DRA CON GOO ADJU FINA 10. STA INST.	SEXECUTION. UDING MATERI IECT TO REJEC WING UPDATI TRACTOR TO P DO-FOR-CONST JSTMENTS TO L AS-BUILT DR ANDARDS & D MATERIALS AN DELINES AND C CONS Date UIT UI CONS Date CONS C	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AMINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRC OCUMENTATION ID EXECUTION MED ID EXECU	MPLES, AND JOIR ACTOR'S END. NG ID SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH HODS SHALL ADD HODS SHALL ADD USTRY BEST PRA N MANUAL FOR A D DATASHEETS, M T ON SITE FOR RE	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISDS, FIRE RATINGS, AND IFERENCE.
SUBJ 9. DRA CON GOO ADJU FINA 10. STA INST.	SEXECUTION. UDING MATERI IECT TO REJEC WING UPDATI TRACTOR TO P DO-FOR-CONST JSTMENTS TO L AS-BUILT DR ANDARDS & D MATERIALS AN DELINES AND C CONS Date UIT UI CONS Date CONS C	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AMINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRC OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEP DELINES TO BE KEP	MPLES, AND JOIR ACTOR'S END. NG ID SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH HODS SHALL ADD HODS SHALL ADD USTRY BEST PRA N MANUAL FOR A D DATASHEETS, M T ON SITE FOR RE	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISDS, FIRE RATINGS, AND IFERENCE.
SUBJ 9. DRA GOO ADJU FINA 10. STA ALL 1 GUIC REFE STAN INST.	SEXECUTION. UDING MATERI LECT TO REJEC WING UPDATI TRACTOR TO N DOFOR-CONST ANDARDS & D MATERIALS AN DELINES AND C IR TO THE PRO NOARDS. LATE ALLATION GUI ONS Date UIT UI CONS UIT UI	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AMINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRC OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEP DELINES TO BE KEP	MPLES, AND JOIN NACTOR'S END. NG ID SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH HODS SHALL ADD HODS SHALL ADD NANUAL FOR A DATASHEETS, M T ON SITE FOR RE OTASHEETS, M T ON SITE FOR RE CONSTRUCTION ACHI.	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISDS, FIRE RATINGS, AND IFERENCE.
SUBJ 9. DRA GOO ADU FINA 10. STA INST.	SERECUTION. UDING MATERI IECT TO REJEC WING UPDATI TRACTOR TO N DO-FOR-CONST JSTMENTS TO L AS-BUILT DR ANDARDS & D MATERIALS AN DELINES AND C IR TO THE PRO MATERIALS ALLATION GUI ONS Date UIT UI Sign Co	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEP DELINES TO BE KEP DELINES TO BE KEP NIVERSIT KAR	MPLES, AND JOIN NACTOR'S END. NG ID SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH VIDED AT PROJECT WIDDS SHALL ADD HODS SHALL ADD NANUAL FOR A DATASHEETS, M T ON SITE FOR RE CONSTRUCTION OF AUDIT ACHI.	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISDS, FIRE RATINGS, AND IFERENCE.
SUBJ 9. DRA GOO ADJU GOO ADJU ALL 1 GUIC REFE STAN INST.	SERECUTION. UDING MATERIALS AN DEFOR-CONST JSTMENTS TO LAS-BUILT DR ANDARDS & D MATERIALS AN DELINES AND C IR TO THE PRO DATES ALLATION GUI DATES UIT UI SIGN CO SIGN CO	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION INTO ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND ID EXECUTION IND I	MPLES, AND JOIN NACTOR'S END. NG ID SET OF LATEST 35 ON SITE. ANY ARED WITH ARCH WIDDS SHALL ADD HODS SHALL ADD NANUAL FOR A DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO UL TECHNICAL ISDS, FIRE RATINGS, AND FFRENCE.
SUBJ 9. DRA GOO ADJU GOO ADJU 10. ST ALL 1 GUIC REFE STAN INST.	SERECUTION. UDING MATERI LECT TO REJEC WING UPDATI TRACTOR TO N DO-FOR-CONST JSTMENTS TO L AS-BUILT DR ANDARDS & D MATERIALS AN DELINES AND C IR TO THE PRO ONS Date UIT UI DELINE Sign Co INTA SIGN CO INTA INT	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION INTO ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND ID EXECUTION I	MPLES, AND JOIN NACTOR'S END. NG DO SET OF LATEST 35 ON SITE. ANY WIDDD AT PROJE UNDTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI	
SUBJ 9. DRA GOO ADJU GOO ADJU IO. ST ALL I GUIC REFE STAN INST.	SEXECUTION. UDING MATERI LECT TO REJEC WING UPDATI TRACTOR TO P DO-FOR-CONST JSTMENTS TO LAS-BUILT DR ANDERINES AND C INTERIALS AN DELINES AND C INTERIALS AND CONS DATERIALS AND CONS DATERIALS AND CONS DATE UIT UI CONS DATE UIT UI CONS CONS DATE UIT UI CONS CON	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SHA AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND ST MANUFACTUREF ID EXECUTION INTO ST MANUFACTUREF ID EXECUTION I	MPLES, AND JOIN NACTOR'S END. NG DO SET OF LATEST 35 ON SITE. ANY WIDDD AT PROJE UNDTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI	
SUBJ 9. DRA GOO ADJU GOO ADJU IO. ST ALL I GUIC REFE STAN INST.	SEXECUTION. UDING MATERI LECT TO REJEC WING UPDATI TRACTOR TO P DO-FOR-CONST JSTMENTS TO LAS-BUILT DR ANDERINES AND C INTERIALS AN DELINES AND C INTERIALS AND CONS DATERIALS AND CONS DATERIALS AND CONS DATE UIT UI CONS DATE UIT UI CONS CONS DATE UIT UI CONS CON	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH, AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION INT ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND ID	MPLES, AND JOIN NACTOR'S END. NG DO SET OF LATEST 35 ON SITE. ANY WIDDD AT PROJE UNDTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI	
SUBJ 9. DRA GOO ADJU GOO ADJU IO. ST ALL I GUIC REFE STAN INST.	SEXECUTION. UDING MATERI LECT TO REJEC WING UPDATI TRACTOR TO P DO-FOR-CONST JSTMENTS TO LAS-BUILT DR ANDERINES AND C INTERIALS AN DELINES AND C INTERIALS AND CONS DATERIALS AND CONS DATERIALS AND CONS DATE UIT UI CONS DATE UIT UI CONS CONS DATE UIT UI CONS CON	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SHA AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND ST MANUFACTUREF ID EXECUTION INTO ST MANUFACTUREF ID EXECUTION I	MPLES, AND JOIN NACTOR'S END. NG DO SET OF LATEST 35 ON SITE. ANY WIDDD AT PROJE UNDTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI	
SUBJ 9. DRA GOO ADJU GOO ADJU IO. ST ALL I GUIC REFE STAN INST.	SEXECUTION. UDING MATERI LECT TO REJEC WING UPDATI TRACTOR TO P DO-FOR-CONST JSTMENTS TO LAS-BUILT DR ANDERINES AND C INTERIALS AN DELINES AND C INTERIALS AND CONS DATERIALS AND CONS DATERIALS AND CONS DATE UIT UI CONS DATE UIT UI CONS CONS DATE UIT UI CONS CON	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SHA AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND ST MANUFACTUREF ID EXECUTION INTO ST MANUFACTUREF ID EXECUTION I	MPLES, AND JOIN NACTOR'S END. NG DO SET OF LATEST 35 ON SITE. ANY WIDDD AT PROJE UNDTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI	
SUBJ 9. DRA GOO ADJU GOO ADJU IO. ST ALL I GUIC REFE STAN INST.	SEXECUTION. UDING MATERI LECT TO REJEC WING UPDATI TRACTOR TO P DO-FOR-CONST JSTMENTS TO LAS-BUILT DR ANDERINES AND C INTERIALS AN DELINES AND C INTERIALS AND CONS DATERIALS AND CONS DATERIALS AND CONS DATE UIT UI CONS DATE UIT UI CONS CONS DATE UIT UI CONS CON	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SHA AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND ST MANUFACTUREF ID EXECUTION INTO ST MANUFACTUREF ID EXECUTION I	MPLES, AND JOIN NACTOR'S END. NG DO SET OF LATEST 35 ON SITE. ANY WIDDD AT PROJE UNDTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI	
SUBJ 9. DRA GOO ADJU GOO ADJU 10. ST/ ALL I GUID REFE STAN INST.	ONS ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS ONS Date ONS ONS Date ONS ONS Date ONS ONS Date ONS ONS ONS ONS ONS ONS Date ONS ONS ONS ONS ONS ONS ONS ONS	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SHA AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND ST MANUFACTUREF ID EXECUTION INTO ST MANUFACTUREF ID EXECUTION I	MPLES, AND JOIN NACTOR'S END. NG DO SET OF LATEST 35 ON SITE. ANY WIDDD AT PROJE UNDTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI	
SUBJ 9. DRA GOO ADJU GOO ADJU 10. ST/ ALL I GUID REFE STAN INST.	ONS Date ONS Date Dign CC Date Dign CC ONS Date Dign CC Date Dign CC NAMP:	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AMINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH AWINGS TO BE PRO COLUMENTATION ID EXECUTION IND DESCRIPTION IND DESCRIPTION DELINES TO BE KEPI DELINES TO BE KEPI DELINES TO BE KEPI CONSULTANT KAR ERIOR E CONSULTANT KHARA SULTANT :	MPLES, AND JOIN ACTOR'S END. NG DO SET OF LATEST SS ON SITE. ANY HODS SHALL ADI- USTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI I. Phase - VI, D.O.HA 857990	MARK-UP OR REDLINE INTECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICLS. CONTRACTOR TO ULTECHNICAL ISDS, FIRE RATINGS, AND FERENCE.
SUBJ 9. DRA GOO ADJU GOO ADJU 10. ST/ ALL I GUID REFE STAN INST.	ONS Date ONS Date Dign CC Date Dign CC ONS Date Dign CC Date Dign CC NAMP:	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SHA AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELINES TO BE KEPI ID EXECUTION IND ST MANUFACTUREF ID EXECUTION INTO ST MANUFACTUREF ID EXECUTION I	MPLES, AND JOIN ACTOR'S END. NG DO SET OF LATEST SS ON SITE. ANY HODS SHALL ADI- USTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI I. Phase - VI, D.O.HA 857990	MARK-UP OR REDLINE INTECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ULTECHNICAL ISDS, FIRE RATINGS, AND FERENCE.
SUBJ 9. DRA GOO ADJU GOO ADJU 10. ST/ ALL I GUID REFE STAN INST.	ONS ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date ONS Date COLLA Sign Co NA PCON COLLA Sign Co COLLA COLL	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEPI AMINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SH AWINGS TO BE PRO COLUMENTATION ID EXECUTION IND DESCRIPTION IND DESCRIPTION DELINES TO BE KEPI DELINES TO BE KEPI DELINES TO BE KEPI CONSULTANT KAR ERIOR E CONSULTANT KHARA SULTANT :	MPLES, AND JOIN ACTOR'S END. NG DO SET OF LATEST SS ON SITE. ANY HODS SHALL ADI- USTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI I. Phase - VI, D.O.HA 857990	MARK-UP OR REDLINE INTECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ULTECHNICAL ISDS, FIRE RATINGS, AND FERENCE.
SUBJ 9. DRA GOO ADJU GOO ADJU FINA IO. STA INST. NO. JOC Title Des C	ONS Date Dig Coll Coll Coll Coll Coll Coll Coll Coll	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEP AVAINTAIN A PRINTE RUCTION DAAWING ENOTED AND SH, AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELIVES TO BE KEP ONSTRUCTION IND JECT SPECIFICATION ST MANUFACTUREF DELIVES TO BE KEP ONSULTATION ID EXECUTION IND JECT SPECIFICATION ST MANUFACTUREF DELIVES TO BE KEP ONSULTATION ID EXECUTION IND SULTATION SULTATION ID EXECUTION IND ID EXECUTION IND	MPLES, AND JOIN ACTOR'S END. NG DO SET OF LATEST SS ON SITE. ANY HODS SHALL ADI- USTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI I. Phase - VI, D.O.HA 857990	MARK-UP OR REDLINE INTECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ULTECHNICAL ISDS, FIRE RATINGS, AND FERENCE. CORIUM, CONS ONS MGS
SUBJ 9. DRA GOO ADJU FINA 10. ST ALL I GUI GUI REFE STAN NO. JOb AT Check	ONS Date Date Date Date Date Date Date Date	IALS, COLOURS, SA TION AT THE CONT SS & RECORD KEEP AVAINTAIN A PRINTE RUCTION DRAWING BE NOTED AND SHA AWINGS TO BE PRO OCUMENTATION ID EXECUTION IND JECT SPECIFICATION ID EXECUTION IND ID EXECUTION IND	MPLES, AND JOIN ACTOR'S END. NG DO SET OF LATEST SS ON SITE. ANY HODS SHALL ADI- USTRY BEST PRA N MANUAL FOR A N MANUAL FOR A N MANUAL FOR A N MANUAL FOR A N DATASHEETS, M T ON SITE FOR RE CALLEVATI ELEVATI I. Phase - VI, D.O.HA 857990	MARK-UP OR REDLINE INTECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ULTECHNICAL ISDS, FIRE RATINGS, AND FERENCE. CORIUM, CONS ONS MGS




## SECTION D-D



SECTION C-C

ALL DE**SIGNE:** AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.


		ference to Finishe	ac A	Reference to
AA	000 Sp	ecification. Jex Reference		Elevation Drawing. —Elevation Reference
		ish Reference ference to	I-1.00	Drawing No. —Zone Reference
		e <b>tail Drawing.</b> etail No. awing No.		
	Re	ference.		
	EGEND			
		Existing Wall		Structural Column
		Curtain Wall		Cement Board Partition Wall
		Fixed Glazing		Proposed Wall
GENE	RAL NOT	ES		
ALL D	RAWINGS T	& VERIFICATION O BE READ IN CONJU P. FURNITURE, CEILI		RCHITECTURAL, FIRE SAFETY, AND ALL
SPECI CONT PRIOI	IALIST CONS TRACTOR MU	ULTANT DRAWINGS JST VERIFY ALL DIMI ENCEMENT OF ANY	, SPECIFICATIONS, ENSIONS, LEVELS, WORK. ANY DISCF	AND DETAIL DOCUMENTS AND SITE CONDITIONS REPANCIES, OMISSIONS, O
CLAR 2. MISS	IFICATION A	ND DIRECTION BEFO	RE PROCEEDING.	THE ARCHITECT FOR
THE S DETA	SOLE RESPON	SIBILITY OF THE CO ARCHITECT. FAILU	NTRACTOR TO RE RE TO REQUEST SU	QUEST THE REQUIRED JCH DETAILS PRIOR TO LAIMS OR EXTENSIONS OF
TIME EXCU 3. LEAK	. "NOT AWA SE. <b>AGE PREVEN</b>	RE" OR "NOT SHOW	N" WILL NOT BE C	CONSIDERED A VALID
SPEC POIN	IFIED WATEF TS ARE LEFT	PROOFING SYSTEM	S. CONTRACTOR T JP AND TESTING (	NES TO BE TREATED WITH O ENSURE NO LEAKAGE INCLUDING POND TESTS IED BY THE
ARCH 4. WOO	ITECT/CONS	ULTANT PRIOR TO C	OVERING.	
FIRE-I DOCU PROD	RETARDANT JMENTED PF DUCT DATA S	COATING PRIOR TO COOF OF TREATMEN HEETS) TO BE SUBM	SITE DELIVERY OF T APPLICATION (II IITTED FOR APPRO	RINSTALLATION. NCLUDING MSDS AND DVAL. UNTREATED OR
CONT 5. EXPO	RACTOR'S R	ESPONSBILITY ELEMENTS		REPLACEMENT SHALL BE
FITTI COAT	NGS, AND FIX SUITABLE T	TURES) TO BE COA O SPECIFIED ENVIRO	FED WITH ANTI-RU	RAL, JOINERY SUPPORTS, JST PRIMER AND FINISH ITIONS. FINAL PAINT FINIS ECTS SUCH AS PEELING,
RUST	, OR DISCOLO RDOUS MA	ORATION. TERIALS & SAFETY F	INISHES	TERIALS ARE TO BE LEFT
EXPO NON- APPL	SED IN THE I COMBUSTIB	BUILT ENVIRONMEN LE (UNLESS SPECIFIE D COMPLIANT WITH	T. ALL MATERIALS ED OTHERWISE), C LOCAL HEALTH, S	5 TO BE CHILD-SAFE (WHERE AFETY, AND
SUBN 7. CONS	AITTED AS PA	. STANDARDS. CERTI ART OF HANDOVER. SAFETY & COMPLIAN	NCE	
BUILE	DING CODES, ONAL PROTE	OSHA STANDARDS, CTIVE EQUIPMENT	AND SITE SAFETY (PPE) IS MANDATO	I COMPLIANCE WITH LOCA REQUIREMENTS. DRY FOR ALL WORKERS. AGE, FIRE EXTINGUISHERS
AND 8. Appr	PROPER STO	RAGE OF MATERIAL OCK-UPS	S ON SITE.	AGE, FIRE EXTINGUISHERS
MASS	EXECUTION	. ANY WORK CARRIE	D OUT WITHOUT	
CONT GOOI	VING UPDAT TRACTOR TO D-FOR-CONS		ED SET OF LATEST GS ON SITE. ANY I	MARK-UP OR REDLINE
CONT GOOI ADJU FINAL <b>10. STA</b>	NING UPDAT TRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D NDARDS & I	MAINTAIN A PRINTI TRUCTION DRAWIN D BE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH OVIDED AT PROJEC	ITECT ON WEEKLY BASIS. CT CLOSEOUT.
CONT GOOI ADJU FINAL <b>10. STA</b> ALL N GUID REFEI	VING UPDAT TRACTOR TO D-FOR-CONS STMENTS TO - AS-BUILT D INDARDS & I MATERIALS A ELINES AND R TO THE PRI	MAINTAIN A PRINTI TRUCTION DRAWIN ) BE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MET CONSTRUCTION INE DJECT SPECIFICATIO	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJEC THODS SHALL ADH DUSTRY BEST PRAC N MANUAL FOR A	IITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER' CTICES. CONTRACTOR TO
CONT GOOI ADJU FINAL <b>10. STA</b> ALL N GUID REFEI STAN	VING UPDAT (RACTOR TO D-FOR-CONS STMENTS TO AS-BUILT D NDARDS & I MATERIALS A ELINES AND R TO THE PRI (DARDS, LATI	MAINTAIN A PRINTI TRUCTION DRAWIN ) BE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MET CONSTRUCTION INE DJECT SPECIFICATIO	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJE THODS SHALL ADH DUSTRY BEST PRAM N MANUAL FOR A R DATASHEETS, M	ITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER' CTICES. CONTRACTOR TO LLL TECHNICAL ISDS, FIRE RATINGS, AND
CONT GOOI ADJU FINAL <b>10. STA</b> ALL N GUID REFEI STAN	VING UPDAT (RACTOR TO D-FOR-CONS STMENTS TO AS-BUILT D NDARDS & I MATERIALS A ELINES AND R TO THE PRI (DARDS, LATI	MAINTAIN A PRINTI TRUCTION DRAWIN ) BE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MET CONSTRUCTION INE DIECT SPECIFICATIO EST MANUFACTUREI	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJE THODS SHALL ADH DUSTRY BEST PRAM N MANUAL FOR A R DATASHEETS, M	ITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER' CTICES. CONTRACTOR TO LLL TECHNICAL ISDS, FIRE RATINGS, AND
CONT GOOI ADJU FINAL <b>10. STA</b> ALL N GUID REFEI STAN	VING UPDAT (RACTOR TO D-FOR-CONS STMENTS TO AS-BUILT D NDARDS & I MATERIALS A ELINES AND R TO THE PRI (DARDS, LATI	MAINTAIN A PRINTI TRUCTION DRAWIN ) BE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MET CONSTRUCTION INE DIECT SPECIFICATIO EST MANUFACTUREI	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJE THODS SHALL ADH DUSTRY BEST PRAM N MANUAL FOR A R DATASHEETS, M	ITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER' CTICES. CONTRACTOR TO LLL TECHNICAL ISDS, FIRE RATINGS, AND
CONT GOOI ADJU FINAL <b>10. STA</b> ALL N GUID REFEI STAN INSTA	VING UPDAT IRACTOR TO D-FOR-CONS STIMENTS TC AS-BUILT D INDARDS & I MATERIALS A ELINES AND TO THE PRI DARDS. LATI LLATION GL	MAINTAIN A PRINTI TRUCTION DRAWIN D EN NOTED AND SH RAWINGS TO BE PRI DOCUMENTATION ND EXECUTION MET CONSTRUCTION INIC CONSTRUCTION INIC CONSTRUCTION INIC DIECT SPECIFICATIO DIECT SPECIFICATIO DIELINES TO BE KEP	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJEC THODS SHALL ADH- JUSTRY BEST PRAIN N MANUAL FOR A R DATASHEETS, M T ON SITE FOR RE	ITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER' CTICES. CONTRACTOR TO LLL TECHNICAL ISDS, FIRE RATINGS, AND
CONT GOOI ADJU FINAL <b>10. STA</b> ALL N GUID REFEI STAN INSTA	VING UPDAT (RACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & MATERIALS A ELINES AND R TO THE PR IDARDS. LATI LLATION GL	MAINTAIN A PRINTI TRUCTION DRAWIN ) BE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MET CONSTRUCTION INE DIECT SPECIFICATIO EST MANUFACTUREI	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJEC THODS SHALL ADH- JUSTRY BEST PRAIN N MANUAL FOR A R DATASHEETS, M T ON SITE FOR RE	ITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER' CTICES. CONTRACTOR TO LLL TECHNICAL ISDS, FIRE RATINGS, AND
CONT GOOI ADJU FINAL <b>10. STA</b> ALL N GUID REFEI STAN INSTA	VING UPDAT IRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I MATERIALS A ELINES AND ATERIALS A ELINES AND DARDS. LATI LLATION GU	MAINTAIN A PRINTI TRUCTION DRAWIN D EN NOTED AND SH RAWINGS TO BE PRI DOCUMENTATION ND EXECUTION MET CONSTRUCTION INIC CONSTRUCTION INIC CONSTRUCTION INIC DIECT SPECIFICATIO DIECT SPECIFICATIO DIELINES TO BE KEP	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJEC THODS SHALL ADH- JUSTRY BEST PRAIN N MANUAL FOR A R DATASHEETS, M T ON SITE FOR RE	ITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER' CTICES. CONTRACTOR TO LLL TECHNICAL ISDS, FIRE RATINGS, AND
CONT GOOI ADJU FINAL <b>10. STA</b> ALL N GUID REFEI STAN INSTA	VING UPDAT (RACTOR TO D-FOR-CONS STIMENTS TC AS-BUILT D INDARDS & I ANTERIALS AND R TO THE PR DATERIALS AND CONS Date Date	MAINTAIN A PRINTI TRUCTION DRAWIN D ER NOTED AND SH RAWINGS TO BE PRI DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE CONSTRUCTION INE DIECT SPECIFICATIO IDELINES TO BE KEF	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJEC (HODS SHALL AD- JUSTRY BEST PRAIN N MANUAL FOR A TO N SITE FOR RE TO N SITE FOR RE	ITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOI ADJU FINAL <b>10. STA</b> ALL N GUID REFEI STAN INSTA	VING UPDAT (RACTOR TO D-FOR-CONS STIMENTS TC AS-BUILT D INDARDS & I ANTERIALS AND R TO THE PR DATERIALS AND CONS Date Date	MAINTAIN A PRINTI TRUCTION DRAWIN BE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MEI CONSTRUCTION IND CONSTRUCTION IND DIECT SPECIFICATIO ST MANUFACTURE IDELINES TO BE KEP	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJEC (HODS SHALL AD- JUSTRY BEST PRAIN N MANUAL FOR A TO N SITE FOR RE TO N SITE FOR RE	ITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOI ADJU FINAL <b>10. STA</b> ALL N GUID REFEI STAN INSTA	VING UPDAT IRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I MATERIALS A ELINES AND DARDS LATI LLATION GL DARDS DATE DATE UIT U	MAINTAIN A PRINTI TRUCTION DRAWIN BE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MEI CONSTRUCTION IND CONSTRUCTION IND DIECT SPECIFICATIO ST MANUFACTURE IDELINES TO BE KEP	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJEC THODS SHALL ADD- DUSTRY BEST PRAIN N MANUAL FOR A DUSTRY BEST PRAIN TO N SITE FOR RE TO N SITE FOR RE TO N SITE FOR RE	ITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOI ADJU FINAL 10. STA ALL N GUID REFEI STAN INSTA	VING UPDAT (RACTOR TO D-FOR-CONS STIMENTS TC AS-BUILT D INDARDS & I ATERIALS A ELINES AND R TO THE PR DATERIALS DATERIALS DATERIALS DATE UIT U	MAINTAIN A PRINTI TRUCTION DRAWIN BE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MEI CONSTRUCTION IND CONSTRUCTION IND DIECT SPECIFICATIO ST MANUFACTURE IDELINES TO BE KEP	tion	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOO ADJU FINAL 10. STA ALL N GUID REFEI STAN INST7	VING UPDAT IRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I MATERIALS A ELINES AND DARDS. LAT DARDS. LAT DARDS. LAT DARDS Date UIT U T INT	MAINTAIN A PRINTI TRUCTION DRAWIN D ER NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE CONSTRUCTION INE DIECT SPECIFICATIO DIECT SPECIFICATIO DIECT SPECIFICATIO DECLINES TO BE KEP DESCRIP IDELINES TO BE KEP DESCRIP IDELINES TO BE KEP	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJEC THODS SHALL ADI- JUSTRY BEST PRAVA N MANUAL FOR A R DATASHEETS, M TO N SITE FOR RE TO N SITE FOR RE TO AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFEI STAN INSTA	VING UPDAT (RACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I ATTERIALS A LILINES AND NO ATTERIALS A DATERIALS A DATERIALS A DATERIALS A UIT U UIT U CONS Date IN IN IN IN IN IN IN IN IN IN	MAINTAIN A PRINTI TRUCTION DRAWIN D ER NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE DIDELINES TO BE KEP DIDELINES TO BE KEP NIVERSIT KAR TERIOR E	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJEC THODS SHALL ADI- JUSTRY BEST PRAI- N MANUAL FOR A R DATASHEETS, M TO NSITE FOR RE TO NO SITE FOR RE TO AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFE STAN INSTA	VING UPDAT IRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I ATTERIALS AND R TO THE PR DATERIALS AND DATES. DATE DATE UIT U INT U INT U	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE DIDELINES TO BE KEF DIDELINES TO BE KEF NIVERSIT KAR TERIOR E CONSULTANT	ED SET OF LATEST GS ON SITE. ANY I ARED WITH ARCH DVIDED AT PROJEC THODS SHALL ADI- JUSTRY BEST PRAV N MANUAL FOR A R DATASHEETS, M TO NSITE FOR RE TO SITE FOR RE TO AUDIT ACHI. ELEVATI : [	TORIUM,
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFER STAN INSTA	DNS Date IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII	MAINTAIN A PRINTI TRUCTION DRAWIN D ER NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE DIDELINES TO BE KEP DIDELINES TO BE KEP NIVERSIT KAR TERIOR E	tion TY AUDITACHI.	ITECT ON WEEKLY BASIS. CT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO LIL TECHNICAL ISDS, FIRE RATINGS, AND FERENCE.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFEI STAN INSTA	VING UPDAT (RACTOR TO D-FOR-CORS STMENTS TO AS-BUILT D INDARDS & I ATERIALS A ELINES AND R TO THE PR DATE: DATE: DATE: DATE: DATE: DATE: UIT U COLLANCE OLLAN	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MEI CONSTRUCTION IND CONSTRUCTION IND DIECT SPECIFICATIO DIECT SPECIFICATIO DIECT SPECIFICATIO DIECT SPECIFICATIO DIECT SPECIFICATIO IDELINES TO BE KEF IDELINES TO BE KEF	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFER STAN INSTA	VING UPDAT IRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I ATERIALS AND R TO THE PR DATERIALS AND R TO THE PR DATE: LALATION GL DATE: UIT U COLL C COLL C COLL C V WWW.najmibilig	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MEI CONSTRUCTION IND CONSTRUCTION IND DIECT SPECIFICATIO DIECT SPECIFICATIO DIECT SPECIFICATIO DIECT SPECIFICATIO DIECT SPECIFICATIO IDELINES TO BE KEF IDELINES TO BE KEF	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFER STAN INSTA	VING UPDAT IRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I ATERIALS AND R TO THE PR DATERIALS AND R TO THE PR DATE: LALATION GL DATE: UIT U COLL C COLL C COLL C V WWW.najmibilig	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE CONSTRUCTION INE DISCUSSION MET CONSTRUCTION INE DISCUSSION INFO DISCUSSION INFO DISCUSSIO	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFER STAN INSTA	VING UPDAT IRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I ATERIALS AND R TO THE PR DATERIALS AND R TO THE PR DATE: LALATION GL DATE: UIT U COLL C COLL C COLL C V WWW.najmibilig	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE CONSTRUCTION INE DISCUSSION MET CONSTRUCTION INE DISCUSSION INFO DISCUSSION INFO DISCUSSIO	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFER STAN INSTA	VING UPDAT IRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I ATERIALS AND R TO THE PR DARDS. LAT LALLATION GL DARDS. LAT UIT U COLL C COLL C COLL C V WWW.najmibilij	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE CONSTRUCTION INE DISCUSSION MET CONSTRUCTION INE DISCUSSION INFO DISCUSSION INFO DISCUSSIO	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFER STAN INSTA	VING UPDAT IRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I ATERIALS AND R TO THE PR DARDS. LAT LALLATION GL DARDS. LAT UIT U COLL C COLL C COLL C V WWW.najmibilij	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE CONSTRUCTION INE DISCUSSION MET CONSTRUCTION INE DISCUSSION INFO DISCUSSION INFO DISCUSSIO	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFER STAN INSTA	VING UPDAT IRACTOR TO D-FOR-CONS STMENTS TC AS-BUILT D INDARDS & I ATERIALS AND R TO THE PR DARDS. LAT LALLATION GL DARDS. LAT UIT U COLL C COLL C COLL C V WWW.najmibilij	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE CONSTRUCTION INE DISCUSSION MET CONSTRUCTION INE DISCUSSION IN DISCUSSION IN DISCUSSION IN DISCUSSION INTERSIONALINA INTERSIONALINA INTERSIONA INTERSIONA INTERS	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFER STAN INSTA	VING UPDAT IRACTOR TO IPORCONS STMENTS TO AS-BUILT D INDARDS & I ATERIALS ALLATION GL DATES. DATE: UIT U IN IN IN IN IN IN IN IN IN IN	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION INE CONSTRUCTION INE CONSTRUCTION INE DISCUSSION MET CONSTRUCTION INE DISCUSSION IN DISCUSSION IN DISCUSSION IN DISCUSSION INTERSIONALINA INTERSIONALINA INTERSIONA INTERSIONA INTERS	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. CT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE. CONS CONS ILI LTD Karachi, Pakistan.
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFER STAN INSTA	DNS Date UIT U Control of the provided and the provided a	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MEN CONSTRUCTION IND CONSTRUCTION IND DIECTORY OF THE ST DIECTORY OF THE ST DIECT	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. TC CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE. TORIUM, ONS ILI LTD Karachi, Pakistan.
CONT GOOD ADJU FINAL 10. STA ALUN GUID REFEI STAN Des C C C C C C C C C C C C C C C C C C C	DNS DATE: INDATE: DATE:	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MEI CONSTRUCTION IND CONSTRUCTION IND CONSTRUCTION IND DIECTORY OF THE IDELINES TO BE KEP IDELINES TO BE KEP	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. TCT CLOSEOUT. IERE TO MANUFACTURER CTICES. CONTRACTOR TO ILL TECHNICAL ISOS, FIRE RATINOS, AND FERENCE. TORIUM, ONS ILL Karachi, Pakistan. NGSS
CONT GOOD ADJU FINAL 10. STA ALL N GUID REFEI STAN No. JOD Title Dess C 1. T T F V MEI	DNS DNS DATERIALS AS-BUILT D INDARDS & I ATTERIALS ALLATION GL DATES. DATE IDARDS. LATION GL DATES. DATE IDARDS. DATE IDAR	MAINTAIN A PRINTI TRUCTION DRAWIN DE NOTED AND SH RAWINGS TO BE PRO DOCUMENTATION ND EXECUTION MEN CONSTRUCTION INC OULCT SPECIFICATIO IDELINES TO BE KEP IDELINES TO BE KEP IDE	tion TY AUDIT ACHI. ELEVATI	ITECT ON WEEKLY BASIS. TCT CLOSEOUT. HERE TO MANUFACTURER CTICES. CONTRACTOR TO ILI TECHNICAL ISOS, FIRE RATINGS, AND FERENCE. TORIUM, ONS ILI LTD LTD LTD NGSS



ALL DE**SIGNE:** AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.


R	eference to Finishe		Reference to Elevation Drawing,	
	oecification. dex Reference		Elevation Reference	
	nish Reference	I-1.00	Drawing No. –Zone Reference	
D	eference to etail Drawing. etail No.			
	rawing No.			
	eference.			
WALL LEGEND				J
	Existing Wall		Structural Column	
	Curtain Wall		Cement Board	
	∃ Fixed Glazing		Partition Wall	
			<u> </u>	J
GENERAL NOT	ŦS			1
1. COORDINATION	& VERIFICATION			
STRUCTURAL, M	TO BE READ IN CONJU EP, FURNITURE, CEILII SULTANT DRAWINGS,	NG, ELECTRICAL, F		
PRIOR TO COMM	UST VERIFY ALL DIME 1ENCEMENT OF ANY V L BE BROUGHT TO TH	VORK. ANY DISCR	EPANCIES, OMISSIONS, OR	
CLARIFICATION A	AND DIRECTION BEFOR			
THE SOLE RESPO	NSIBILITY OF THE COM	ITRACTOR TO REC		
EXECUTION SHAI	IE ARCHITECT. FAILUR LL NOT BE USED AS A ARE" OR "NOT SHOWN	BASIS FOR ANY CL	AIMS OR EXTENSIONS OF	
SPECIFIED WATE POINTS ARE LEFT	RPROOFING SYSTEMS UNSEALED. MOCK-U	. CONTRACTOR TO P AND TESTING (II	IES TO BE TREATED WITH DENSURE NO LEAKAGE NCLUDING POND TESTS	
WHERE APPLICA ARCHITECT/CON	BLE) MUST BE CONDU SULTANT PRIOR TO CO	CTED AND VERIFI		
	E <b>NTS</b> JRFACES TO BE TREAT F COATING PRIOR TO S			
DOCUMENTED P PRODUCT DATA	ROOF OF TREATMENT SHEETS) TO BE SUBM	APPLICATION (IN TTED FOR APPRO	CLUDING MSDS AND /AL. UNTREATED OR	
CONTRACTOR'S	RESPONSBILITY	REJECTED AND R	EPLACEMENT SHALL BE	
FITTINGS, AND F	ETAL SURFACES (INCLU IXTURES) TO BE COAT	ED WITH ANTI-RU	AL, JOINERY SUPPORTS, ST PRIMER AND FINISH	
COAT SUITABLE	TO SPECIFIED ENVIRO	NMENTAL CONDI	TONS. FINAL PAINT FINISH	
6. HAZARDOUS MA	ATERIALS & SAFETY FI		ERIALS ARE TO BE LEFT	
EXPOSED IN THE NON-COMBUSTI	BUILT ENVIRONMENT BLE (UNLESS SPECIFIE	. ALL MATERIALS D OTHERWISE), CH	TO BE HILD-SAFE (WHERE	
ENVIRONMENTA	ID COMPLIANT WITH I L STANDARDS. CERTIF PART OF HANDOVER.			
7. CONSTRUCTION ALL CONSTRUCT	SAFETY & COMPLIAN	CARRIED OUT IN		
BUILDING CODES PERSONAL PROT	5, OSHA STANDARDS, ECTIVE EQUIPMENT (I	AND SITE SAFETY I PPE) IS MANDATO		
AND PROPER STO 8. APPROVALS & N	ORAGE OF MATERIALS 10CK-UPS	ON SITE.		
WHEREVER REQ MASS EXECUTIO	UIRED, MOCK-UPS MU N. ANY WORK CARRIEI	OUT WITHOUT F	AND APPROVED PRIOR TO PRIOR APPROVAL, ERY DETAILS, SHALL BE	
SUBJECT TO REJE	ERIALS, COLOURS, SA ECTION AT THE CONTR TES & RECORD KEEPI	ACTOR'S END.	JEIMLE, JIMLE DE	1
CONTRACTOR TO GOOD-FOR-CON	D MAINTAIN A PRINTE STRUCTION DRAWING	D SET OF LATEST IS ON SITE. ANY M	IARK-UP OR REDLINE	
	U BE NOTED AND SHA	DED MANY	TECT ON MESSION	
	DRAWINGS TO BE PRC		TECT ON WEEKLY BASIS. T CLOSEOUT.	
10. STANDARDS & ALL MATERIALS	<b>DOCUMENTATION</b>	VIDED AT PROJEC		
10. STANDARDS & ALL MATERIALS & GUIDELINES AND REFER TO THE PF STANDARDS. LAT	DOCUMENTATION AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION	VIDED AT PROJEC HODS SHALL ADHI USTRY BEST PRAC I MANUAL FOR AL DATASHEETS, MS	T CLOSEOUT. ERE TO MANUFACTURER'S TICES. CONTRACTOR TO L TECHNICAL iDS, FIRE RATINGS, AND	
10. STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PF STANDARDS, LAT INSTALLATION G	DOCUMENTATION AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION FEST MANUFACTURER	VIDED AT PROJEC HODS SHALL ADHII USTRY BEST PRAC I MANUAL FOR AL DATASHEETS, MS ON SITE FOR REF	T CLOSEOUT. ERE TO MANUFACTURER'S TICES. CONTRACTOR TO L TECHNICAL iDS, FIRE RATINGS, AND	
10. STANDARDS & ALL MATERIALS. GUIDELINES AND REFER TO THE PF STANDARDS. LAT INSTALLATION G	DOCUMENTATION AND EXECUTION MET O CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP	VIDED AT PROJEC HODS SHALL ADHII USTRY BEST PRAC I MANUAL FOR AL DATASHEETS, MS ON SITE FOR REF	T CLOSEOUT. ERE TO MANUFACTURER'S TICES. CONTRACTOR TO L TECHNICAL iDS, FIRE RATINGS, AND	
10. STANDARDS & ALL MATERIALS. GUIDELINES AND REFER TO THE PF STANDARDS. LAT INSTALLATION G	DOCUMENTATION AND EXECUTION MET O CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP	VIDED AT PROJEC HODS SHALL ADHII USTRY BEST PRAC I MANUAL FOR AL DATASHEETS, MS ON SITE FOR REF	T CLOSEOUT. ERE TO MANUFACTURER'S TICES. CONTRACTOR TO L TECHNICAL iDS, FIRE RATINGS, AND	
10. STANDARDS & ALL MATERIALS. GUIDELINES AND REFER TO THE PF STANDARDS. LAT INSTALLATION G EVISIONS No. Date JOD :	DOCUMENTATION AND EXECUTION MET O CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP Descript	VIDED AT PROJEC	T CLOSEOUT.	
10. STANDARDS & ALL MATERIALS. GUIDELINES AND REFER TO THE PF STANDARDS. LAT INSTALLATION G EVISIONS No. Date JOD :	DOCUMENTATION AND EXECUTION MET CONSTRUCTION IND OIGET SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP Descript	VIDED AT PROJEC	T CLOSEOUT.	
10. STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PF STANDARDS, LAT INSTALLATION G NO. Date JOD: UIT L	DOCUMENTATION AND EXECUTION MET CONSTRUCTION IND OIGET SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP Descript	VIDED AT PROJECTOR SHALL ADHII USTRY BEST PRACI I MANUAL FOR AL DATASHEETS, MS ON SITE FOR REF	T CLOSEOUT.	
10. STANDARDS & ALL MATERIALS. GUIDELINES AND REFER TO THE PF STANDARDS. LAT INSTALLATION G REVISIONS No. Date JOD :	DOCUMENTATION AND EXECUTION MET CONSTRUCTION IND OIGET SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP Descript	VIDED AT PROJECTOR SHALL ADHII USTRY BEST PRACI I MANUAL FOR AL DATASHEETS, MS ON SITE FOR REF	T CLOSEOUT.	
IO. STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PF STANDARDS. LAT INSTALLATION G NO. Date JOD : UIT L Title :	DOCUMENTATION AND EXECUTION MET DO CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP Descript	vided at project Hodd Shall adhii USTRY BEST PRAC I MANUAL FOR AL DATASHEETS, MR FON SITE FOR REF	T CLOSEOUT.	
IO. STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PF STANDARDS. LAT INSTALLATION G NO. Date JOD : UIT L Title :	DOCUMENTATION AND EXECUTION MET CONSTRUCTION IND OIGET SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP Descript	vided at project Hodd Shall adhii USTRY BEST PRAC I MANUAL FOR AL DATASHEETS, MR FON SITE FOR REF	T CLOSEOUT.	
10. STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PF STANDARDS, LAT INSTALLATION G No. Date Job : UIT L Title : MIS	DOCUMENTATION AND EXECUTION MET DO CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP Descript	VIDED AT PROJECT HODS SHALL ADHII USTRY BEST PRACI I MANUAL FOR AL DATASHEETS, ME ON SITE FOR REF ON SITE FOR REF ACHI.	T CLOSEOUT.	
ID. STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G No. Date Job : UIT L Title : MIS Design C	Decumentation AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP DESCRIPT JNIVERSIT KARA CELLANE	VIDED AT PROJECT HODS SHALL ADHII USTRY BEST PRACI I MANUAL FOR AL DATASHEETS, MS I ON SITE FOR REF	T CLOSEOUT.	
ID. STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G No. Date Job : UIT L Title : MIS Design C	Decumentation AND EXECUTION MET AND EXECUTION MET SO CONSTRUCTION IND ROLECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP Descript Descript Descript Descript CELLANE CELLANE Consultant	VIDED AT PROJECTOR SHALL ADHII USTRY BEST PRACI I MANUAL FOR AL DATASHEETS, MS I ON SITE FOR REF	T CLOSEOUT.	
ID. STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G No. Date Job : UIT L Title : MIS Design C	Decumentation AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP DESCRIPT JNIVERSIT KARA CELLANE	VIDED AT PROJECTOR SHALL ADHII USTRY BEST PRACI I MANUAL FOR AL DATASHEETS, MS I ON SITE FOR REF	T CLOSEOUT.	
ALL MATERIALS, GUIDELINES AND REFER TO THE PF STANDARDS. LAT INSTALLATION G REVISIONS No. Date JOD : UIT L Title : MIS Design C NA BIG COLL 14-C, Lane 7, MI	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP Descript Descript Descript Descript CELLANE CELLANE CONSULTANT LICERSIT ABORATI AND FACTOR	INDER AT PROJECTION OF ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR ALL ADHATASHETS, MANUAL FOR ALL		
ID. STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PF STANDARDS, LAT INSTALLATION G No. Date Job : UIT U Title : MIS Design C NA BIG COLL 14-C, Lane 7, MI	DOCUMENTATION AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP DESCRIPT JNIVERSIT KAR.	INDER AT PROJECTION OF ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR ALL ADHATASHETS, MANUAL FOR ALL		
ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G No. Date JOD : UIT L Title : MIS Design C Design C UIT L L Lac, Lane 7, M T 49221-3542 F 49221-3542 F 49221-3542 F 49221-3542	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP Descript De	INDER AT PROJECTION OF ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR ALL ADHATASHETS, MANUAL FOR ALL		
ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS. LAT INSTALLATION G NO. Date JOD : UIT L Title : MIS Design C INCA BIG COLL 14-C, Lane 7, M 1-9221-35242 F 92221-35257	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP Descript De	INDER AT PROJECTION OF ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR ALL ADHATASHETS, MANUAL FOR ALL		
ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G NO. Date JOD : UIT L Title : MIS Design C ICCLL 14-C, Lane 7, M 1-9221-35242 F-9221-35547 W www.najmbi	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP Descript De	INDER AT PROJECTION OF ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR ALL ADHATASHETS, MANUAL FOR ALL		
ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G NO. Date JOD : UIT L Title : MIS Design C INSTALLATION G INSTALLATION G	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP Descript De	INDER AT PROJECTION OF ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR ALL ADHATASHETS, MANUAL FOR ALL		
ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G No. Date JOD : UIT L Title : MIS Design C IAC, Lane 7, M T +9221-3542 F +9221-354 F +9221-354 F +9221-3542 F +9221-354 F +9221-354	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP Descript De	INDER AT PROJECTION OF ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR ALL ADHATASHETS, MANUAL FOR ALL		
ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G No. Date JOD : UIT L Title : MIS Design C IAC, Lane 7, M T +9221-3542 F +9221-354 F +9221-354 F +9221-3542 F +9221-354 F +9221-354	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP Descript De	INDER AT PROJECTION OF ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR ALL ADHATASHETS, MANUAL FOR ALL		
ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS. LAT INSTALLATION G NO. Date JOD : UIT U Title : MIS Design C IAC, Lane 7. M T+92/21-35242 F+92/21-35547 W WWW.najmbi	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP Descript De	INDER AT PROJECTION OF ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHITUSTRY BEST PRACTUREST, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR REFORMED ATASHEETS, MANUAL FOR ALL ADHATASHEETS, MANUAL FOR ALL ADHATASHETS, MANUAL FOR ALL		
ID. STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G No. Date JOD : UIT L Title : MIS Design C IL-C, Lane 7, M T-9221-3542 F-9221-3542 F-9221-3542 F-9221-3542	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP Descript De	INDER AT PROJECTION OF ALL ADHII USTRY BEST PRACI I MANUAL FOR ALL DATASHEETS, MS ION SITE FOR REF INDER ALL ADHII ION SITE FOR ALL ADHIII ION SITE FOR ALL ADHIII ION SITE FOR ALL ADHII ION SITE FO		
ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS. LAT INSTALLATION G NO. Date JOD : UIT L Title : MIS Design C INCA BEL COLL 14-C, Lang 7. M BIS MEP COI	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP DESCRIPT DE	ion Y AUDIT ACHI. COUS DI COUS	T CLOSEOUT. ERE TO MANUFACTURER'S TICES. CONTRACTOR TO L TECHNICAL DOS, FIRE RATINGS, AND ERENCE. ORIUM, ETAILS I. Grachi, Pakistan.	
ID STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G No. Date Job : UIT L Title : MIS Design C ILC, Lang 7, M HEP COI	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROLECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP JNIVERSIT KAR. CELLANE CONSULTANT CELLANE CONSULTANT AJJNI AJJNI ABORATI ABORATI ABORATI ABORATI AND AND AND AND AND AND AND AND AND AND	ion Y AUDIT ACHI. COUS DI COUS	T CLOSEOUT. ERE TO MANUFACTURER'S TICES. CONTRACTOR TO L TECHNICAL DOS, FIRE RATINGS, AND ERENCE. ORIUM, ETAILS I. Grachi, Pakistan.	
ID STANDARDS & ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS. LAT INSTALLATION G NO. Date JOD : UIT L Title : MIS Design C Id-C, Lang 7, M HEP COI MEP COI STAMP : II JOD Arch : U.G	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROLECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEP JNIVERSIT KAR. CELLANE CONSULTANT CELLANE CONSULTANT AJJNI AJJNI ABORATI ABORATI ABORATI ABORATI AND AND AND AND AND AND AND AND AND AND	ion Y AUDIT ACHI. COUS DI COUS	T CLOSEOUT. ERE TO MANUFACTURER'S TICES. CONTRACTOR TO L TECHNICAL DOS, FIRE RATINGS, AND ERENCE. ORIUM, ETAILS I. Grachi, Pakistan.	
EVISIONS NO. Date JOD : UIT U Title : MIS Design C COLL 14-C,Lan H2-21-3542 F +92-21-35457 W WWW.najmbi MEP COI STAMP : TI LOD Arch : U.G Checked: A.N.	Decumentation AND EXECUTION MET AND EXECUTION MET CONSTRUCTION IND ROJECT SPECIFICATION TEST MANUFACTURER UIDELINES TO BE KEPP JNIVERSIT KAR CELLANE CONSULTANT CELLANE CONSULTANT A JONN A B O RATI A JONN A B O RATI A SOULTANT CONSULTANT CONSULTANT CONSULTANT CONSULTANT	ion Y AUDIT ACHI. COUS DI COUS	T CLOSEOUT. TE TO MANUFACTURER'S TICES. CONTRACTOR TO L TECHNICAL DORIUM, ORIUM, ETAILS ICACCHI, Pakistan. IGSS	
ALL MATERIALS, GUIDELINES AND REFER TO THE PI STANDARDS, LAT INSTALLATION G NO. Date JOD I JOD I TITLE : MIS Design C I ALL MATERIALS UIT L I MEP CON MEP CON STAMP : TI JOD Arch : U.G Checkey : M.NE	Descript	ion Y AUDIT ACHI. COUS DI COUS	T CLOSEOUT. TE TO MANUFACTURER'S TICES. CONTRACTOR TO L TECHNICAL DORIUM, ORIUM, ETAILS ICACCHI, Pakistan. IGSS	

	Γ			
Φ				
0				
7 V				
V				
14 J.				
V				
Ϋ́Υ ·				
4				
¥				
77				
1				
₹ <b>7</b>				
с.				
₽				
- - - -				
, v				
∨ ∇ ∇				
₽.				
4				
Φ.				
4				
•				
• • •				
₽ 7				
V				
۲				
I. . ⊽				
•.	L			
Π			1	
· =	=	1	-	D




ALL DE**SIGNE:** AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.

	TAG LEGEND
	Reference to Finishes Specification. Index Reference Finish Reference Reference to Detail Drawing. Cone Reference
	WALL LEGEND
	Existing Wall       Structural Column         Curtain Wall       Cement Board         Partition Wall       Fixed Glazing
	<ul> <li>GENERAL NOTES</li> <li>1. COORDINATION &amp; VERIFICATION</li> <li>ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ARCHITECTURAL, STRUCTURAL, MEY, FURNITURE, CLINIC, JULICA, PIRE SAFETY, AND ALL SPECIALIST CONSULTANT DRAWINGS, SPECIFICATIONS, AND DETAIL DOCUMENTS, CONTRACTOR MUSY VEIFY ALL DIMENSIONS, LUCKA, AND STRE CONDITIONS PROR TO COMMENCEMENT OF ANY WORK, ANY DISCREPANCIES, OMISSIONS, OR CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT FOR CLARIFICATION AND DIRECTION BEFORE PROCEEDING.</li> <li>2. MISING DETAILS CLARIFICATION</li> <li>2. MISING DETAILS CLARIFICATION DETAIL IS NOT SHOWN OR PROVIDED, IT IS THE SUBIL RESOLUCITS TO THE ATTENTION OF ULBEST THE REQUIRED DETAIL FROM THE ARCHITECT. FAILURE TO REQUEST SUCH DETAILS PRIOR TO EXECUTION SHALL NOT BE USED AS ABSS FOR ANY CLAIMS OR RETRIENSIONS OF TIME. "NOT AWARE" OR "NOT SHOWN" WILL NOT BE CONSIDERED A VALID EXCUSE.</li> <li>2. MISING DETAILS AS ABSS FOR ANY CLAIMS OR RETRIENSIONS OF TIME." NOT AWARE" OR "NOT SHOWN" WILL NOT BE CONSIDERED A VALID EXCUSE.</li> <li>3. MERCARDY CLAIMS AND STRUCTURE ZONGS TO BE TREATED WITH SPECIFIED WATERPROOFING SYSTEMS. CONTRACTOR TO ENSURE NO LEAKAGE POINTS ARE LETT UNSEALED. MOCK VAL PA ND TSTING (NICLUDING ROND TSTS WHERE APPLICABLE) MIST BE CONDUCTED AND VERIFIED BY THE ARCHITECT/CONSULTANT PRIOR TO COVERING.</li> <li>4. WOODEN SURFACTURAT FRIOR TO COVERING.</li> <li>4. LUK ZORDS MATERATED AND THE FOR APPLICABLE DE INFORMATIC CONTING FRIOR TO STEE DELIVERY OR INSTALLATION. DOCUMENTED FROOF OF DATA THEATE POINT INTERMITE SOLUTION AND FRIE-RETARDANT. CONTING PRIOR TO STEE DELIVERY OR INSTALLATION. DOCUMENTED FROMO-POINTE AND AND TESTS WHERE APPLICABLE DE NOTARY CONTING TO STRUCTURAL, JOINERY SUPPORTS, FITTINGS, AND FIXTURES) TO BE COATED WITH ANTI-TRIMITE SOLUTION AND FRIE-RETARDANT. COATING PRIOR TO STRUCTURAL, JOINERY SUPPORTS, RITTINGS, AND FIXTURES (INCLUDING STRUCTURAL, JOINERY SUPPORTS, RITTINGS, AND FIXTURES) TO BE COATED WITH ANTI-RUST PRIMER AND FINIS TO BE SOFTOR TO TREATED AND APPROVAL LUTRERS</li></ul>
	REVISIONS           No.         Date         Description
	Job : UIT UNIVERSITY AUDITORIUM, KARACHI.
	Title : MISCELLANEOUS DETAILS Design Consultant :
	NAJINA COMPARING CONTROLOGICAL CONTROL
	STAMP : TENDER DRAWINGS
= 1'-0"	Checked: A.N. Cad By : MINHAS Job No : I-CO-2803 Date : JUNE 20, 2025 Scale : AS SHOWN L-3.02




ALL DE**SIGNE**: AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.


	TAG LEGEND
	Reference to Finishes Reference to
	AA 000 Specification. Index Reference
	Finish Reference Finish Reference
	Reference to Detail Drawing.
	Reference.
	WALL LEGEND
	Existing Wall Structural Column
	Curtain Wall
	Fixed Glazing Proposed Wall
	GENERAL NOTES
	1. COORDINATION & VERIFICATION ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ARCHITECTURAL,
	STRUCTURAL, MEP, FURNITURE, CEILING, ELECTRICAL, FIRE SAFETY, AND ALL SPECIALIST CONSULTANT DRAWINGS, SPECIFICATIONS, AND DETAIL DOCUMENTS.
	CONTRACTOR MUST VERIFY ALL DIMENSIONS, LEVELS, AND SITE CONDITIONS PRIOR TO COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES, OMISSIONS, OR CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT FOR
	CLARIFICATION AND DIRECTION BEFORE PROCEEDING. 2. MISSING DETAILS & CLARIFICATIONS IN THE FUELT THAT A CONCENTRATION DETAIL IS NOT SHOWN OF PROVIDED THE
	IN THE EVENT THAT A CONSTRUCTION DETAIL IS NOT SHOWN OR PROVIDED, IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REQUEST THE REQUIRED DETAIL FROM THE ARCHITECT. FAILURE TO REQUEST SUCH DETAILS PRIOR TO
	EXECUTION SHALL NOT BE USED AS A BASIS FOR ANY CLAIMS OR EXTENSIONS OF TIME. "NOT AWARE" OR "NOT SHOWN" WILL NOT BE CONSIDERED A VALID EXCUSE.
	3. LEAKAGE PREVENTION & WATERPROOFING ALL WET AREAS, ROOF SLABS, DUCTS, AND SERVICE ZONES TO BE TREATED WITH
	SPECIFIED WATERPROOFING SYSTEMS. CONTRACTOR TO ENSURE NO LEAKAGE POINTS ARE LEFT UNSEALED. MOCK-UP AND TESTING (INCLUDING POND TESTS WHERE APPLICABLE) MUST BE CONDUCTED AND VERIFIED BY THE
	ARCHITECT/CONSULTANT PRIOR TO COVERING. 4. WOODEN ELEMENTS
	ALL WOODEN SURFACES TO BE TREATED WITH ANTI-TERMITE SOLUTION AND FIRE-RETARDANT COATING PRIOR TO SITE DELIVERY OR INSTALLATION.
	DOCUMENTED PROOF OF TREATMENT APPLICATION (INCLUDING MSDS AND PRODUCT DATA SHEETS) TO BE SUBMITTED FOR APPROVAL, UNTREATED OR IMPROPERLY TREATED WOOD WILL BE REJECTED AND REPLACEMENT SHALL BE
	CONTRACTOR'S RESPONSBILITY 5. EXPOSED METAL ELEMENTS
	ALL EXPOSED METAL SURFACES (INCLUDING STRUCTURAL, JOINERY SUPPORTS, FITTINGS, AND FIXTURES) TO BE COATED WITH ANTI-RUST PRIMER AND FINISH COAT SUITABLE TO SPECIFIED ENVIRONMENTAL CONDITIONS. FINAL PAINT FINISH
	TO BE AS PER APPROVED SAMPLE AND FREE FROM DEFECTS SUCH AS PEELING, RUST, OR DISCOLORATION.
	6. HAZARDOUS MATERIALS & SAFETY FINISHES NO HAZARDOUS, SHARP, TOXIC, OR INFLAMMABLE MATERIALS ARE TO BE LEFT EXPOSED IN THE BUILT ENVIRONMENT. ALL MATERIALS TO BE
	NON-COMBUSTIBLE (UNLESS SPECIFIED OTHERWISE), CHILD-SAFE (WHERE APPLICABLE), AND COMPLIANT WITH LOCAL HEALTH, SAFETY, AND
	ENVIRONMENTAL STANDARDS. CERTIFICATES OF CONFORMANCE TO BE SUBMITTED AS PART OF HANDOVER. 7. CONSTRUCTION SAFETY & COMPLIANCE
	ALL CONSTRUCTION WORKS SHALL BE CARRIED OUT IN COMPLIANCE WITH LOCAL BUILDING CODES, OSHA STANDARDS, AND SITE SAFETY REQUIREMENTS.
	PERSONAL PROTECTIVE EQUIPMENT (PPE) IS MANDATORY FOR ALL WORKERS. CONTRACTOR TO ENSURE BARRICADING, SAFETY SIGNAGE, FIRE EXTINGUISHERS, AND PROPER STORAGE OF MATERIALS ON SITE.
	8. APPROVALS & MOCK-UPS WHEREVER REQUIRED, MOCK-UPS MUST BE PREPARED AND APPROVED PRIOR TO
	MASS EXECUTION. ANY WORK CARRIED OUT WITHOUT PRIOR APPROVAL, INCLUDING MATERIALS, COLOURS, SAMPLES, AND JOINERY DETAILS, SHALL BE SUBJECT TO REJECTION AT THE CONTRACTOR'S END.
	9. DRAWING UPDATES & RECORD KEEPING CONTRACTOR TO MAINTAIN A PRINTED SET OF LATEST
1 0	GOOD-FOR-CONSTRUCTION DRAWINGS ON SITE. ANY MARK-UP OR REDLINE ADJUSTMENTS TO BE NOTED AND SHARED WITH ARCHITECT ON WEEKLY BASIS. FINAL AS-BUILT DRAWINGS TO BE PROVIDED AT PROJECT CLOSEOUT.
	10. STANDARDS & DOCUMENTATION ALL MATERIALS AND EXECUTION METHODS SHALL ADHERE TO MANUFACTURER'S
	GUIDELINES AND CONSTRUCTION INDUSTRY BEST PRACTICES. CONTRACTOR TO REFER TO THE PROJECT SPECIFICATION MANUAL FOR ALL TECHNICAL STANDARDS. LATEST MANUFACTURER DATASHEETS, MSDS, FIRE RATINGS, AND
	INSTALLATION GUIDELINES TO BE KEPT ON SITE FOR REFERENCE.
	INSTALLATION GUIDELINES TO BE KEPT ON SITE FOR REFERENCE.
	INSTALLATION GUIDELINES TO BE KEPT ON SITE FOR REFERENCE.
	INSTALLATION GUIDELINES TO BE KEPT ON SITE FOR REFERENCE.
	INSTALLATION GUIDELINES TO BE KEPT ON SITE FOR REFERENCE.
	INSTALLATION GUIDELINES TO BE KEPT ON SITE FOR REFERENCE.
	INSTALLATION GUIDELINES TO BE KEPT ON SITE FOR REFERENCE.
	REVISIONS
	REVISIONS       No.     Date     Description       Image: Second secon
	REVISIONS
	REVISIONS       No.     Date     Description       Job :     UIT UNIVERSITY AUDITORIUM,
	REVISIONS       No.     Date     Description       Image: Description     Image: Description
	REVISIONS       No.     Date     Description       Job :     UIT UNIVERSITY AUDITORIUM,
	REVISIONS          No.       Date       Description         Image: Image of the second sec
	REVISIONS           No.         Date         Description           Image: Image of the state of the stat
	REVISIONS          No.       Date       Description         Image: Image of the structure       Image of the structure       Image of the structure         Job :       Image of the structure       Image of the structure         Job :       Image of the structure       Image of the structure         Job :       Image of the structure       Image of the structure         Job :       Image of the structure       Image of the structure         Job :       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Ima
	REVISIONS          No.       Date       Description         Image: Im
	REVISIONS          No.       Date       Description         Image: Image of the structure       Image of the structure       Image of the structure         Job :       Image of the structure       Image of the structure         Job :       Image of the structure       Image of the structure         Job :       Image of the structure       Image of the structure         Job :       Image of the structure       Image of the structure         Job :       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Image of the structure       Image of the structure       Image of the structure         Ima
	REVISIONS          No.       Date       Description         Image: Im
	No.       Date       Description         Job :       UIT UNIVERSITY AUDITORIUM, KARACHI.         Title :       MISCELLANEOUS DETAILS         Design Consultant :       NAJNI         BILGRAMI       COLLABORATIVE (PYT)LTD
	No.       Date       Description         Image: Image
	No.       Date       Description         Image: Image
	No.       Date       Description         Image: Image
	No.       Date       Description         Image: Image
	No.       Date       Description         Image: Image
	No.       Date       Description         Image: Image
	No.       Date       Description         Image: Image
	No.       Date       Description         Image: Image
	No.       Date       Description         International       Description         Job:       UIT UNIVERSITY AUDITORIUM, KARACHI.         Jitle :       UIT UNIVERSITY AUDITORIUM, KARACHI.         Title :       MISCELLANEOUS DETAILS         Design Consultant :       NASINGERALUE (PVP)(DED)         MURALINATION (CONSULTANT)       Description         UP - Consultant :       NASINGERALUE (PVP)(DED)         MURALINATION       Description         MURALINATION       MURALINATION
	No.       Date       Description         International internationa internatintered internationa international internatinte
	No.       Date       Description         Image: Image
	No.       Date       Description         International internatinternational internatinternational internatio
	No.       Date       Description         Ide       Ide       Ide         Job :       UIT UNIVERSITY AUDITORIUM, KARACHI.         UIT UNIVERSITY AUDITORIUM, KARACHI.       Title :         MISCELLANEOUS DETAILS       Design Consultant :         NAJANNI BULGERALUE (VELVELTUR)       Design Consultant :         MEP Consultant :       MEP Consultant :         STAMP :       ENDER DRAWINGS         Job Arch:       U.G.         Job Arch:       U.G.         Job Arch:       U.G.         Job Arch:       U.G.         Yoth:       MOTH
	No.       Date       Description         Image: Image
	No.       Date       Description         Job :       UIT UNIVERSITY AUDITORIUM, KARACHI.         Title :       MISCELLANEOUS DETAILS         Design Consultant :       NAJINI SUBJECTIVE (PUP) LED         Vectors Australia       Description         Design Consultant :       NAJINI SUBJECTIVE (PUP) LED         Vectors Australia       Description         MISCELLANEOUS DETAILS       Description         Design Consultant :       NAJINI SUBJECTIVE (PUP) LED         Vectors Australia       Description         MEP Consultant :       NEP Consultant :         STAMP :       EENDER DRAWINGS         STAMP :       EENDER DRAWINGS         Job Arch: U.G       Nerth :         Checkee: A.M.       Cod By :         Cod By :       MINHAS         Job No: I. CO-2803       Description





ALL DE SNORE: AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.

	TAG LEGEND
	AA 000 Reference to Finishes Specification. Index Reference
	Finish Reference Reference to Drawing No. Zone Reference
	Detail Drawing. Detail No. 
	WALL LEGEND
	Curtain Wall Cement Board
	Fixed Glazing Proposed Wall
	GENERAL NOTES
	1. COORDINATION & VERIFICATION ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ARCHITECTURAL, STRUCTURAL, MEP, FURNITURE, CEILING, ELECTRICAL, FIRE SAFETY, AND ALL SPECIALIST CONSULTANT DRAWINGS, SPECIFICATIONS, AND DETAIL DOCUMENTS. CONTRACTOR MUST VENIFY ALL DIMENSIONS, LEVELS, AND SITE CONDITIONS PRIOR TO COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES, OMISSIONS, OR CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT FOR CLARIFICATION AND DIRECTION BEFORE PROCEEDING.
	2. MISSING DETAILS & CLARIFICATIONS IN THE EVENT THAT A CONSTRUCTION DETAIL IS NOT SHOWN OR PROVIDED, IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REQUEST THE REQUIRED DETAIL FROM THE ARCHITECT. FAILURE TO REQUEST SUCH DETAILS PRIOR TO EXECUTION SHALL NOT BE USED AS A BASIS FOR ANY CLAIMS OR EXTENSIONS OF TIME. "NOT AWARE" OR "NOT SHOWN" WILL NOT BE CONSIDERED A VALID EXCUSE.
	3. LEAKAGE PREVENTION & WATERPROOFING ALL WET AREAS, ROOF SLABS, DUCTS, AND SERVICE ZONES TO BE TREATED WITH SPECIFIED WATERPROOFING SYSTEMS. CONTRACTOR TO ENSURE NO LEAKAGE POINTS ARE LEFT UNSEALED. MOCK-UP AND TESTING (INCLUDING POND TESTS WHERE APPLICABLE), MUST BE CONDUCTED AND VERIFIED BY THE ARCHITECT/CONSULTANT PRIOR TO COVERING.
	4. WOODEN ELEMENTS ALL WOODEN SURFACES TO BE TREATED WITH ANTI-TERMITE SOLUTION AND FIRE-RETARDANT COATING PRIOR TO SITE DELIVERY OR INSTALLATION. DOCUMENTED PROOF OF TREATMENT APPLICATION (INCLUDING MSDS AND PRODUCT DATA SHEETS) TO BE SUBMITTED FOR APPROVAL. UNTREATED OR IMPROPERLY TREATED WOOD WILL BE REJECTED AND REPLACEMENT SHALL BE CONTRACTOR'S RESPONSBILITY
	5. EXPOSED METAL ELEMENTS     ALL EXPOSED METAL SURFACES (INCLUDING STRUCTURAL, JOINERY SUPPORTS, FITTINGS, AND FIXTURES) TO BE COATED WITH ANTI-RUST PRIMER AND FINISH COAT SUITABLE TO SPECIFIED ENVIRONMENTAL CONDITIONS. FINAL PAINT FINISH TO BE AS PER APPROVED SAMPLE AND FREE FROM DEFECTS SUCH AS PEELING, RUST, OR DISCOLORATION.     6. HAZARDOUS MATERIALS & SAFETY FINISHES     NO WATDOUS COMPACTOR DATE ON INSTANDAL CANTEDIALS ARE TO BE LEFT.
	NO HAZARDOUS, SHARP, TOXIC, OR INFLAMMABLE MATERIALS ARE TO BE LEFT EXPOSED IN THE BUILT ENVIRONMENT. ALL MATERIALS TO BE NON-COMBUSTIBLE (UNLESS SPECIFIED OTHERWISE), CHILD-SAFE (WHERE APPLICABLE), AND COMPLIANT WITH LOCAL HEALTH, SAFETY, AND ENVIRONMENTAL STANDARDS. CERTIFICATES OF CONFORMANCE TO BE
	SUBMITTED AS PART OF HANDOVER. 7. CONSTRUCTION SAFETY & COMPLIANCE ALL CONSTRUCTION WORKS SHALL BE CARRIED OUT IN COMPLIANCE WITH LOCAL BUILDING CODES, OSHA STANDARDS, AND SITE SAFETY REQUIREMENTS.
	PERSONAL PROTECTIVE EQUIPMENT (PPE) IS MANDATORY FOR ALL WORKERS. CONTRACTOR TO ENSURE BARRICADING, SAFETY SIGNAGE, FIRE EXTINGUISHERS, AND PROPER STORAGE OF MATERIALS ON SITE. 8. APPROVALS & MOCK-UPS
	WHEREVER REQUIRED, MOCK-UPS MUST BE PREPARED AND APPROVED PRIOR TO MASS EXECUTION. ANY WORK CARRIED OUT WITHOUT PRIOR APPROVAL, INCLUDING MATERIALS, COLOURS, SAMPLES, AND JOINERY DETAILS, SHALL BE SUBJECT TO REJECTION AT THE CONTRACTOR'S END.
	9. DRAWING UPDATES & RECORD KEEPING CONTRACTOR TO MAINTAIN A PRINTED SET OF LATEST GOOD-FOR-CONSTRUCTION DRAWINGS ON SITE. ANY MARK-UP OR REDLINE ADJUSTMENTS TO BE NOTED AND SHARED WITH ARCHITECT ON WEEKLY BASIS.
= 1 '-0"	FINAL AS-BUILT DRAWINGS TO BE PROVIDED AT PROJECT CLOSEOUT. 10. STANDARDS & DOCUMENTATION ALL MATERIALS AND EXECUTION METHODS SHALL ADHERE TO MANUFACTURER'S GUIDELINES AND CONSTRUCTION INDUSTRY BEST PRACTICES. CONTRACTOR TO
	REFER TO THE PROJECT SPECIFICATION MANUAL FOR ALL TECHNICAL STANDARDS. LATEST MANUFACTURER DATASHEETS, MSDS, FIRE RATINGS, AND INSTALLATION GUIDELINES TO BE KEPT ON SITE FOR REFERENCE.
	REVISIONS
	No.         Date         Description
	Job : UIT UNIVERSITY AUDITORIUM, KARACHI.
	Title :
	MISCELLANEOUS DETAILS
	Design Consultant :
	NAJMI BILGRAMI
	COLLABORATIVE (PVT)LTD 14-C, Lare 7, Main Khe-Bukhari Commercial, Phase - VI, D.O.H.A, Karachi, Pakistan. 1-9221-135242829, 35242842, 36857957, 35857950
	F +92-21-35857996 W www.najmibilgrami.com MEP Consultant :
	STAMP :
	TENDER DRAWINGS
	Job Arch : U.G North :
	Checked: A.N. Cad By : MINHAS Job No : I-CO-2803
= 1'-0"	Date         :         JUNE 20, 2025         Dwg. No.           Scale         :         AS SHOWN         I-3.04









ALL DESIGNE: AND DETAILS ARE THE PROPERTY OF NAJMI BILGRAMI COLLABORATIVE (Pvt.)Ltd. MAIN KH-E-BUKHARI COMMERCIAL, D.O.H.A, KARACHI AND CAN NOT BE USED WITHOUT WRITTEN PERMISSION. ALL DRAWINGS MUST BE RETURNED UPON COMPLETION OF WORK. PLEASE DO NOT SCALE DRAWINGS. ALL MEASUREMENTS MUST BE VERIFIED TO ENSURE COMPLIANCE, ACCURACY AND CONFORMITY TO BUILDING BYE-LAWS BY THE SUPERVISING ARCHITECT / ENGINEER / CONTRACTOR. APPROVED DRAWINGS SHOULD BE KEPT AT SITE ALL THE TIMES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL DRAWINGS I.E., ARCHITECTURE, STRUCTURE, MEP OR ANY OTHER RELATED DRAWING. ANY DISCREPANCY BETWEEN ANY KIND OF DRAWINGS SHOULD BE VERIFIED BY ARCHITECT BEFORE STARTING ANY WORK ON SITE.

		erence to Finish ecification.	es 🛆	Reference to
	Ind	ex Reference	A	Elevation Drawing. —Elevation Reference
<i>(</i>		sh Reference	I-1.00	Drawing No. Zone Reference
	Det	erence to tail Drawing. tail No.		
	i <sup>oo</sup> Z I	iwing No. erence.		
WALL L	EGEND			
	<u>92962757</u>	Existing Wall		Structural Column
		Curtain Wall Fixed Glazing		Partition Wall
GENE	RAL NOTE	S		
		VERIFICATION D BE READ IN CONJ	UNCTION WITH A	RCHITECTURAL,
SPEC	IALIST CONSU	ILTANT DRAWINGS	5, SPECIFICATIONS	FIRE SAFETY, AND ALL , AND DETAIL DOCUMENT AND SITE CONDITIONS
CONF	LICTS SHALL		HE ATTENTION OF	REPANCIES, OMISSIONS, C THE ARCHITECT FOR
IN TH	IE EVENT THA		N DETAIL IS NOT S	HOWN OR PROVIDED, IT
DETA EXEC	IL FROM THE	ARCHITECT. FAILU	IRE TO REQUEST SI A BASIS FOR ANY C	QUEST THE REQUIRED UCH DETAILS PRIOR TO LAIMS OR EXTENSIONS O
EXCU	SE.	E" OR "NOT SHOW		CONSIDERED A VALID
ALL V SPEC	VET AREAS, R IFIED WATERI	OOF SLABS, DUCT: PROOFING SYSTEM	5, AND SERVICE ZC 15. CONTRACTOR 1	NES TO BE TREATED WITH TO ENSURE NO LEAKAGE INCLUDING POND TESTS
WHE	RE APPLICABL	JNSEALED. MOCK- .E) MUST BE CONE JLTANT PRIOR TO	OUCTED AND VERIF	
ALL V				ERMITE SOLUTION AND
DOCU PROE	JMENTED PRO DUCT DATA SH	DOF OF TREATMEN HEETS) TO BE SUBM	NT APPLICATION (I MITTED FOR APPRO	NCLUDING MSDS AND DVAL. UNTREATED OR REPLACEMENT SHALL BE
CONT 5. EXPO	FRACTOR'S RE	SPONSBILITY LEMENTS		
FITTII COAT	NGS, AND FIX SUITABLE TO	TURES) TO BE COA D SPECIFIED ENVIR	TED WITH ANTI-RI	RAL, JOINERY SUPPORTS, UST PRIMER AND FINISH ITIONS. FINAL PAINT FINIS
TO BI RUST	E AS PER APPI , OR DISCOLO	ROVED SAMPLE AN	ID FREE FROM DEI	ECTS SUCH AS PEELING,
NO H EXPO	AZARDOUS, S SED IN THE B	HARP, TOXIC, OR I UILT ENVIRONMEI	NFLAMMABLE MA	
APPL ENVII	ICABLE), AND RONMENTAL	COMPLIANT WITH STANDARDS. CERT	HLOCAL HEALTH, S	
7. CONS	STRUCTION SA	RT OF HANDOVER. AFETY & COMPLIA	NCE	I COMPLIANCE WITH LOC
BUILE	DING CODES, ONAL PROTEC	OSHA STANDARDS CTIVE EQUIPMENT	, AND SITE SAFETY (PPE) IS MANDAT	
AND 8. APPF	PROPER STOP	RAGE OF MATERIA DCK-UPS	LS ON SITE.	
MASS	SEXECUTION.	ANY WORK CARRI	ED OUT WITHOUT	O AND APPROVED PRIOR T PRIOR APPROVAL, NERY DETAILS, SHALL BE
9. DRAV	WING UPDAT	TION AT THE CON <sup>®</sup> ES & RECORD KEEI MAINTAIN A PRINT	PING	
GOO ADJU	D-FOR-CONST ISTMENTS TO	RUCTION DRAWIN	IGS ON SITE. ANY HARED WITH ARCH	MARK-UP OR REDLINE IITECT ON WEEKLY BASIS.
<b>10. STA</b> All N	ANDARDS & D	OCUMENTATION	THODS SHALL AD	IERE TO MANUFACTURER
REFE	R TO THE PRC	JECT SPECIFICATIO	ON MANUAL FOR A	CTICES. CONTRACTOR TO ALL TECHNICAL ISDS, FIRE RATINGS, AND
		IDELINES TO BE KE		
REVISIO	DNS			
REVISIO No.	DNS Date	Descriț	otion	
	1	Descriț	otion	
No.	Date	Descriț	otion	
	Date	Descrip	otion	
No.	Date	NIVERSI	TY AUDIT	forium,
No.	Date	NIVERSI		FORIUM,
No.	Date	NIVERSI	TY AUDIT	Forium,
No.	Date	NIVERSI	TY AUDIT RACHI.	
No.	Date	NIVERSI	TY AUDIT	
No. Job	Date	NIVERSI KAF	TY AUDIT RACHI. R DETAIL	
No. Job Title	Date	NIVERSI KAF DOOF	TY AUDIT RACHI. R DETAIL	
No. Job Title	Date		TY AUDIT RACHI. R DETAIL	-
No.	Date		TY AUDIT RACHI. R DETAIL t : <b>E</b>	- I
No. Job Title	Date		TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- 
No. Job Title	Date	NIVERSI KAF DOOF onsultan JIN LGEF BORAT	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- 
No. Job Title	Date	NIVERSI KAF DOOF onsultan JIN LGEF BORAT	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- 
No. Job Title	Date	NIVERSI KAF DOOF onsultan JIN LGFF borat Kh-e-Bukhai Commerc 9,35242642,36857957, 3 6 ami.com	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- 
No. Job Title	Date	NIVERSI KAF DOOF onsultan JIN LGFF borat Kh-e-Bukhai Commerc 9,35242642,36857957, 3 6 ami.com	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- 
No. Job Title	Date	NIVERSI KAF DOOF onsultan JIN LGFF borat Kh-e-Bukhai Commerc 9,35242642,36857957, 3 6 ami.com	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- 
No. Job Title	Date	NIVERSI KAF DOOF onsultan JIN LGFF borat Kh-e-Bukhai Commerc 9,35242642,36857957, 3 6 ami.com	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- 
No. Job Title	Date	NIVERSI KAF DOOF onsultan JIN LGFF borat Kh-e-Bukhai Commerc 9,35242642,36857957, 3 6 ami.com	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- 
No. Job Title	Date	NIVERSI KAF	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- LTD Karachi, Pakistan.
No. Job Title	Date	NIVERSI KAF DOOF onsultan JIN LGFF borat Kh-e-Bukhai Commerc 9,35242642,36857957, 3 6 ami.com	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- LTD Karachi, Pakistan.
No. Job Title	Date	NIVERSI KAF	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- LTD Karachi, Pakistan.
No. Job Title Des G	Date Date Date Date Date Date Date Date	NIVERSI KAF DOOF onsultan JNO Gonsultan JNO Sultant :	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- LTD , Karachi, Pakistan. NGS
No. Job Title Des Des STA	Date Date Date Date Date Date Date Date	NIVERSI KAF DOOF onsultan JIVI Gere Southant Commerce Southant Com	TY AUDIT RACHI. R DETAIL t : <b>EXAVI</b> IVE (PVT) III. Phase-VI, D.O.HA S3857990 VI. D.O.HA	- LTD , Karachi, Pakistan. NGS
No. Job Title Des C MEI	Date Date Date Date Date Date Date Date	NIVERSI KAF	TY AUDIT RACHI. R DETAIL t : E E E E E E E E E E E E E E E E E E E	- LTD , Karachi, Pakistan. NGS

# **ELECTRICAL WORKS**

\* \* \* \*

# DESIGN DRAWINGS AND BILL OF QUANTITIES

\* \* \* \*

**AUDITORIUM AREA** 



# Electrical Consulting Engineers

## LIST OF MANUFACTURERS / SUPPLIERS

1.	LV Panel & Distribution Board	:	Unique Engineering, Engineer & Engineers
2.	LV Circuit Breaker	:	ABB
3.	Magnetic Contactors, Overload Relays / Energy analyzer	:	ABB / Lovato Lovato / Circutor
4.	LV Power Cables	:	Pakistan Cables
5.	Lighting Fixtures	:	Pierlite Pakistan, Uni Lux
6.	Switches , Sockets & Dimmers	:	Schneider, (Clipsal Pakistan),
7.	<b>PVC/UPVC Conduits &amp; Accessories</b>	:	Civic, Jeddah
8.	Cable Lugs	:	Corning (3M), Cembre
9.	Cable Trays / Ladder & Accessories	6:	Zain Lighting
10.	Linear Aluminum Channels	:	Zain Lighting
11.	MS Back Boxes / Ceiling Pull Boxes	;:	Master
12.	Floor Boxes (Imported)	:	Davis (Clipsal Pakistan)
13.	Imported Cable Connectors & Junction /Pull Boxes	:	Zain Lighting
14.	Industrial Sockets and Isolators	:	Schneider
15.	Network Cables / Voice and Data	:	Corning by 3M, Schneider (Clipsal Pakistan)
16.	Communication Racks (Imported Brand)	:	Toten
17.	Fire Alarm System	:	Gent by Honeywell
18.	Fire Resistance Cable	:	Prysmian, FP Plus
19.	Co-axial Cables	:	Corning by 3M, Schneider
20.	CCTV System	:	RG Technologies
21.	IP Public Address & Voice Evacuation System	:	ТОА
22.	Earthing / Grounding System	:	Famsons Technologies
23.	UPS	:	APC, Schneider, ABB

# BILL OF QUANTITIES

#### UIT UNIVERSITY (AUDITORIUM AREA)

#### **ELECTRICAL WORKS**

#### **BILL OF QUANTITIES**

S.No.	Description	Unit	Qty.	Rate	Amount
	SECTION - A				
	WIRING INSTALLATION				
1.	Providing and installing of <b>Downlight circuit wiring</b> from DB to lighting point with 3 x 2.5sq.mm in 1" dia. PVC conduit complete with all accessories.	Nos.	2		
1.1	Providing and installing <b>Downlight point wiring</b> with 3 x 1.5sq.mm single core PVC insulated 450/750V grade copper wires in 1" dia. PVC conduit surface/concealed mounted including all accessories, connectors switches with specified cover plates, sheet steel back boxes with brass earth terminal, 1.0 sq.mm 3-core PVC/PVC cable in flexible PVC conduit for final connection. Complete in all respect.				
a)	Downlight <b>point</b> controlled by one switch.	Nos.	10		
b)	Downlight point from <b>point</b> to <b>point</b> .	Nos.	24		
2.	Providing and installing of <b>Two Way Downlight circuit wiring</b> from DB to lighting point with 3 x 2.5sq.mm in 1" dia. PVC conduit complete with all accessories.	No.	1		
2.1	Providing and installing <b>Two Way Downlight point wiring</b> with 3 x 1.5sq.mm single core PVC insulated 450/750V grade copper wires in 1" dia. PVC conduit surface/concealed mounted including all accessories, connectors switches with specified cover plates, sheet steel back boxes with brass earth terminal, 1.0 sq.mm 3-core PVC/PVC cable in flexible PVC conduit for final connection. Complete in all respect.				
a)	Two Way Downlight <b>point</b> controlled by one switch.	Nos.	2		
b)	Two Way Downlight point from <b>point</b> to <b>point</b> .	Nos.	4		
3.	Providing and installing of <b>Magnetic Light circuit wiring</b> from DB to switch board with 3 x 2.5sq.mm in 1" dia. PVC conduit	N-	4		
24	complete with all accessories.	No.	1		
3.1	Magnetic Light <b>point</b> controlled by one switch.	Nos.	6		
3.2	Providing and installing of <b>Magnetic Light wiring</b> from Switch Board to <b>Magnetic Light Driver</b> with 3 x 2.5sq.mm in 1" dia. PVC conduit complete with all accessories.	Nos.	9		

S.No.	Description	Unit	Qty.	Rate	Amount
4.	Providing and installing of <b>LED Strip Light circuit wiring</b> from DB to lighting point with 3 x 2.5 sq.mm in 1" dia. PVC conduit complete with all accessories.	No.	1		
4.1	Providing and installing <b>LED Strip Light point wiring</b> with 3 x 1.5sq.mm single core PVC insulated 450/750V grade copper wires in 1" dia. PVC conduit surface/concealed mounted including all accessories, connectors switches with specified cover plates, sheet steel back boxes with brass earth terminal, 1.0 sq.mm 3-core PVC/PVC cable in flexible PVC conduit for final connection. Complete in all respect.				
a)	LED Strip Light <b>point</b> controlled by one switch.	Nos.	6		
b)	Downlight point from <b>point</b> to <b>point</b> .	Nos.	3		
5.	Providing and installing of <b>LED Profile Light / Wall Mounted</b> <b>recessed Light circuit wiring</b> from DB to lighting point with 3 x 2.5 sq.mm in 1" dia. PVC conduit complete with all accessories.	Nos.	3		
5.1	Providing and installing LED Profile Light / Wall Mounted recessed Light point wiring with 3 x 1.5sq.mm single core PVC insulated 450/750V grade copper wires in 1" dia. PVC conduit surface/concealed mounted including all accessories, connectors switches with specified cover plates, sheet steel back boxes with brass earth terminal, 1.0 sq.mm 3-core PVC/PVC cable in flexible PVC conduit for final connection. Complete in all respect.				
a)	LED Profile Light / Wall Mounted recessed Light <b>point</b> controlled by one switch.	Nos.	13		
b)	LED Profile Light / Wall Mounted recessed Light point from <b>point</b> to <b>point</b> .	Nos.	94		
6.	Providing and installing of <b>LED Emergency Light circuit</b> <b>wiring</b> from DB to lighting point with 3 x 2.5sq.mm in 1" dia. PVC conduit complete with all accessories.	No.	1		
6.1	Providing and installing <b>LED Emergency Light point wiring</b> with 3 x 1.5sq.mm single core PVC insulated 450/750V grade copper wires in 1" dia. PVC conduit surface/concealed mounted including all accessories, connectors switches with specified cover plates, sheet steel back boxes with brass earth terminal, 1.0 sq.mm 3-core PVC/PVC cable in flexible PVC conduit for final connection. Complete in all respect.				
a)	LED Emergency Light point from <b>point</b> to <b>point</b> .	Nos.	7		
	Providing and installing of LED Emergency Exit Light circuit wiring from DB to lighting point with 3 x 2.5sq.mm in 1" dia.				
	PVC conduit complete with all accessories.	No.	1		

S.No.	Description	Unit	Qty.	Rate	Amount
7.1	Providing and installing LED Emergency Exit Light point wiring with 3 x 1.5sq.mm single core PVC insulated 450/750V grade copper wires in 1" dia. PVC conduit surface/concealed mounted including all accessories, connectors switches with specified cover plates, sheet steel back boxes with brass earth terminal, 1.0 sq.mm 3-core PVC/PVC cable in flexible PVC conduit for final connection. Complete in all respect.				
a)	LED Emergency Exit Light point from <b>point</b> to <b>point</b> .	No.	1		
8.	Providing and installing of Raw circuit wiring from DB for <b>13A</b> , <b>Multi socket outlet</b> with 3 x 2.5 sq.mm single core PVC insulated copper wires in 1" dia. PVC conduit concealed/surface mounted with all accessories, sheet steel back boxes with brass earth terminals.	Nos.	1		
8.1	Same as Item No.8 but wiring from point to point.	Nos.	5		
9	Providing and installing of UPS circuit wiring from DB to <b>13A</b> <b>Duplex switch socket outlets</b> wired with 3 x 4 sq mm single core PVC insulated copper wires in 1" dia PVC conduit, surface/ concealed mounted with all accessories, sheet steel back boxes with brass earth terminal.	Nos.	4		
9.1	Same as Item No.9 but wiring from point to point.	Nos.	7		
	Providing and installing of circuit wiring from DB to <b>13A</b> , <b>Multi</b> <b>socket outlet</b> for <b>SMD Screen</b> wired with 3 x 4 sq mm single core PVC insulated copper wires in 1" dia PVC conduit, surface/ concealed mounted with all accessories, sheet steel back boxes with brass earth terminal.	Nos.	1		
10.1	Same as Item No.10 but wiring from point to point.	Nos.	4		
11.	Providing and installing of <b>Pop UP Box circuit wiring</b> from DB to Pop Up Box point with 3 x 4sq.mm in 1" dia. PVC conduit complete with all accessories.	Nos.	9		
11.1	Same as Item No.11 but wiring from point to point.	Nos.	157		
12.	Supply and installation of Imported Type Pop Up Box Stainless Steel (Eubic) Dimension: (Must be Suitable For 1 No.13A International Switch Socket With USB Charging Port 3A/5A,& Type C Charging Port With Chord. Face Plates Inlcuded Schneider Only of 18 SWG sheet. Complete in all respects as	Net	100		
	per details and drawings.	Nos.	166		

S.No.	Description	Unit	Qty.	Rate	Amount
13.	Supply & installation of <b>Technology box</b> of 16 SWG.G.I. Sheet having cover of 12 SWG. Suitable for for 1 No. 10 Amps Socket, 2 Nos. 13 Amps. Socket (Simplex), 1 No. Telephone outlet and 1No. data outlet.	Nos.	2		
	Supply & installation of <b>Floor box</b> of 16 SWG.G.I. Sheet having cover of 12 SWG. Suitable for for 1 No. 10 Amps Socket, 2 Nos. 13 Amps. Socket (Simplex), 1 No. Telephone outlet and 1No. data outlet.	No.	1		
	Supply & installation following sizes of M.S Powder Coated Perforated 14 SWG <b>Cable tray</b> with 16 SWG cover duly Painted after degreesing, derusting, phosphating and antirust primer including all installation accessories such as connecting plates with earth bonding, rawal bolts elbows,tees e.t.c. Complete in all respect.				
а	150 mm x 100 mm Cable Tray	Rft.	40		
	TOTAL OF SECTION - A RS.		1		

S.No.	Description	Unit	Qty.	Rate	Amount
	SECTION - B				
	SWITCHES & SOCKETS				
	Supply and Installation of following <b>10</b> Amps, Gang Switches or <b>10/ 13/ 15/ 20</b> Amps socket outlets make including 14 SWG sheet steel back boxes recessed / surface on wall or as per design drawings. Make : Clipsal Series Vivace for Sockets)				
1	10A, 220V One Gang Two Way Switch Unit	Nos.	2		
2	10A, 220V Three Gang Switch Unit	Nos.	9		
3	10A, 220V Four Gang Switch Unit	Nos.	2		
4	13A, Multi Socket Unit	Nos.	14		
5	13A, Flat-Pin Simplex Switch Socket Unit	Nos.	6		
6	20A DP Switch	No.	9		
7	32A 3-Pin Industrial Socket (Complete Set)	Nos.	2		
	TOTAL OF SECTION - B RS.				
	SECTION - C				
	TELEPHONE SYSTEM				
1.	Providing and installing of telephone point with 1" dia pvc conduit concealed mounted including sheet steel back box.	Nos.	2		
2.	Providing & installing of <b>cat-6 UTP cable</b> from telephone point. <b>Make : Corning by 3M, Clipsal</b>	Nos.	2		
3.	Providing & connecting of cat-6 RJ-45 Face Plate + I/O (Simplex) Make : Corning by 3M, Clipsal	Nos.	2		
	TOTAL OF SECTION - C RS.			1	

S.No.	Description	Unit	Qty.	Rate	Amount
	SECTION - D				
	COMPUTER DATA SYSTEM				
1.	Providing and installing of computer data outlet point in 1" dia. PVC conduit including sheet steel back box.	Nos.	14		
2.	Providing and installing of data Cat-6 UTP cable upto computer Point. Make : Corning by 3M, Clipsal	Nos.	8		
3.	Providing and installing of data Cat-6 UTP cable upto IP Based Wifi Point. Make : Corning by 3M, Clipsal	Nos.	4		
4.	Providing and installing of data Cat-6 UTP cable upto SMD Screen Point. Make : Corning by 3M, Clipsal	Nos.	2		
5.	Providing & connecting of Aux wire. Make : RG- Technology	Mtr.	35		
6.	Providing & connecting of HDMI Cable. Make : RG- Technology	Mtr.	35		
7.	Providing and Installing of 24 - port patch panel.	No.	1		
8.	Providing and Installing of <b>front cable management</b> .Complete with all fixing accessories.	No.	1		
9.	Supply, Installation and connectiong up <b>12U Rack</b> . Complete with all mounting accessories. <b>Make: Toten, Vertiv</b>	Job.	1		
10.	Supply, installation and connecting up of certified cat - 6, 4 pair (RJ45 TO RJ45 type plugs) <b>patch cord</b> .				
10.1	1.0 m Long (patch panel end)	Nos.	14		
10.2	3.0 m Long (patch panel end)	Nos.	12		
11.	Testing termination & commissioning of entire	Job.	1		
	TOTAL OF SECTION - D RS.				
	SECTION - E				
	CCTV SYSTEM.				
1.	Providing and installing of CCTV point in 1" dia. PVC conduit including sheet steel back box.	Nos.	11		
2.	Providing and installing of data Cat-6 UTP cable upto computer Point. Make : Corning by 3M, Clipsal	Nos.	11		
3.	Installation of <b>IP- Cemera</b> , 4 Megapixel.	Nos.	7		
4.	Installation of <b>IP Based HD - Cemera</b> 360 °C for Videography / Photography.	Nos.	4		
5.	Installation of <b>16 Chanel NVR</b> with all accessories.	No.	1		
6.	Installation of <b>21 inch</b> Screen LCD	No.	1		
7.	Testing & Commissioning of CCTV system.	Job.	1		
	TOTAL OF SECTION - E RS.				

S.No.	Description	Unit	Qty.	Rate	Amount
	SECTION - F				
	FIRE ALARM SYSTEM				
1.	Providing, laying of high impact 20 mm dia PVC conduit for Fire Alarm system concealed in Masonry wall & surface on slab (above F.C), complete as per drawing & instruction by consultant.	Nos.	9		
2.	Providing, laying & pulling of following size of PVC insulated cable in already laid PVC conduit as sown on the drawing, Complete with all wiring accessories. <b>Make: Prysmian FP 200</b> <b>Gold</b>				
2.1	2 x 1.5 mm <sup>2</sup> S.C PVC cable for Manual call point & M.D.	Nos.	8		
2.2	2 x 2.5 mm <sup>2</sup> S.C PVC cable for Bell.	No.	1		
3.	Installing testing & commissioning of <b>Manual call point</b> Conventional Type. Complete in all respects.	No.	1		
4.	Installing testing & commissioning of Fire Alarm <b>power bell</b> Conventional Type. Complete in all respects.	No.	1		
5.	Installing testing & commissioning of <b>Multi smoke detector.</b> Complete in all respects.	Nos.	7		
6.	Installing testing & commissioning of <b>2 Zone Fire Alarm panel</b> . Complete in all respects.	Job.	1		
	TOTAL OF SECTION - F RS.				
	SECTION - G				
	SOUND SYSTEM.				
1.	Providing and installing of sound point in 1" dia. PVC conduit	Nos.	10		
2.	Installation of 15/30 Watt Ceiling mounted speakers.	Nos.	10		
3.	Installation of 120 / 180w rms mixer line Amplifier 1 Zone.	No.	1		
4.	Installation of Table type Paging Microphone	Nos.	2		
5.	Supply, Installation of wiring for <b>speakers</b> wired with 40/0076, 2- core flexible pvc/pvc cable in 1" dia pvc pipe. <b>Make : Pakistan</b>				
	Cable, Fast Cables	Nos.	10		
6.	Supply and Installation of interconnection cables / connectors.	Lot	1		
7.	Testing & commissioning of the entire system.	Job	1		
	TOTAL OF SECTION - G RS.				

S.No.	Description	Unit	Qty.	Rate	Amount
	SECTION - H				
	LIGHT FIXTURES & FANS				
1.	Installation of following light fixtures including connecting accessories, flexible pipe, wire, termination, connectors testing & commissioning.				
a)	<b>Fixture Type - A</b> LED Down Light recessed ceiling mounted with 12 watt. As per architect approval	Nos.	32		
b)	<b>Fixture Type - B</b> LED Down Light recessed ceiling mounted with 7 watt. As per architect approval.	Nos.	8		
c)	Fixture Type - C LED Down Light recessed Wall mounted with 5 watt. As per architect approval.	Nos.	24		
d)	<u>Fixture Type - D</u> LED Strip Light. As per architect approval.	Mtr.	81		
e)	Fixture Type - E LED Aluminum Profile Light. As per architect approval.	Mtr.	165		
e-1)	Magnatic Track . As per architect approval.	Mtr.	50		
e-2)	200 Watt Magnatic Track Driver	Nos.	9		
f)	Fixture Type - F LED Magnetic recessed Razor Light with 18 watt. As per architect approval.	Nos.	16		
g)	Fixture Type - G LED Magnetic recessed Track Light with 12 watt. As per architect approval.	Nos.	46		
h)	Installation of Down light type Emergency light fixture with 1 hour battery backup time and comprising self contained battery charger reccessed in cieling. Including all accessories, complete in all respects. As per architect approval.	Nos.	8		
i)	Installation of Exit Emergency light fixture with 1 hour battery backup time and comprising self contained battery charger hanging with cieling. Including all accessories, complete in all respects. As per architect approval.	Nos.	2		
			_		
	TOTAL OF SECTION - H RS.				

S.No.	Description	Unit	Qty.	Rate	Amount
	SECTION - J				
	SWITCHGEAR				
	DISTRIBUTION BOARDS				
	Supply, installation, testing & commissioning of following Distribution Boards as shown on drawing made with 14 SWG sheet steel housing and powder coated as per approved color including all installation accessories such as Rawal bolt etc. Complete in all respects.				
1	LP DB (AUDITORIUM AREA)	No.	1		
	TOTAL OF SECTION - J RS.				
	SECTION - K				
	MAIN / SUB - MAIN CABLES				
1.	Supply, installation and connection of following main, submain 600 / 1000V grade PVC copper cables. <b>Make : Pakistan Cable, Fast Cables</b>				
a)	From Existing Panal to LP DB (Auditorium) 50 mm <sup>2</sup> 4 core pvc/ pvc cable + 2 x 25 mm <sup>2</sup> s/c pvc cable in suitable size pvc conduit .	Rft.	150 As per site		
b)	From Gen Set to LP DB (Auditorium)				
	Existing Supply	Rft.	-		
c)	From LP DB (Auditorium) to UPS 6 mm <sup>2</sup> 3 core pvc/ pvc cable in suitable size pvc conduit.	Rft.	20		
d)	From UPS to LP DB (Auditorium) 6 mm <sup>2</sup> 3 core pvc/ pvc cable in suitable size pvc conduit.	Rft.	20		
e)	From LP DB (Auditorium) to A/C Unit -1 16 mm <sup>2</sup> 4 core pvc/ pvc cable + 1 x 16 mm <sup>2</sup> s/c pvc cable in suitable size pvc conduit .	Rft.	150		
f)	From LP DB (Auditorium) to A/C Unit - 2 16 mm <sup>2</sup> 4 core pvc/ pvc cable + 1 x 16 mm <sup>2</sup> s/c pvc cable in suitable size pvc conduit .	Rft.	150		
	TOTAL OF SECTION - K RS.				

S.No.	Description	Unit	Qty.	Rate	Amount
	<u>SECTION - L</u>				
	EARTHING				
1.	Supply. Installation & Testing of EFE-T Chemical Grounding System with 19mm dia having Heavy-duty Copper Rod 10 Ft. long filled with Soil Conditioning Material with 6" x 25 Ft. Deep Boring with heavy duty PVC Put within Coaster Silver Cover for air breathing with Brass Nuts and Bolts ready to use. upto Test Terminal.For Neutral Earthing the result should be less than 1 Ohm, Complete in all respect.	Nos.	4		
2.	Supply, installation & connection of 2 x 25 sq.mm single core PVC cable in PVC pipe from earth pit to LP DB.	Rft.	95		
3.	Supply, installation & connection of 1 x 16 sq.mm single core PVC cable in PVC pipe from earth pit to Gen Set Neutral.	Rft.	30		
4.	Supply, installation & connection of 1 x 10 sq.mm single core PVC cable in PVC pipe from earth pit to Gen Set Body.	Rft.	30		
5.	Supply, installation & connection of 2 x 16 sq.mm single core PVC cable in PVC pipe from earth pit to HVAC Outer Body.	Rft.	80		
	TOTAL OF SECTION - L RS.				
	SECTION - M				
	AS BUILT DRAWINGS				
1.	Preparation, submission & approval of As-Built drawing of the entire installation. The contractor should submit Three sets of prints of As-Built drawing to the Client.	Job.	1		
	TOTAL OF SECTION - M RS.		1	1	

#### UIT UNIVERSITY (AUDITORIUM AREA)

S.No.	Description	Unit	Qty.	Rate	Amount
	SECTION - N				
	O.F.M ITEM				
1	CCTV SYSTEM.				
1.1	Owner Supplied of <b>IP- Cemera</b> , 4 Megapixel.	Nos.	7		
1.2	Owner Supplied of <b>IP Based HD - Cemera</b> 360 °C for Videography / Photography with all accessories	Nos.	4		
1.3	Owner Supplied of <b>16 Chanel NVR</b> with all accessories.	No.	1		
1.4	Owner Supplied of <b>21 inch</b> Screen LCD	No.	1		
2	FIRE ALARM SYSTEM				
2.1	Owner Supplied of Manual call point	Nos.	2		
2.2	Owner Supplied of Fire Alarm <b>power bell</b>	Nos.	2		
2.3	Owner Supplied of Multi smoke detector.	Nos.	7		
2.4	Owner Supplied of <b>2 Zone Fire Alarm panel</b> .	Job.	1		
3	SOUND SYSTEM.				
3.1	Owner Supplied of 15/30 Watt Ceiling mounted speakers.	Nos.	10		
3.2	Owner Supplied of 120 / 180w rms mixer line <b>Amplifier 1</b> Zone.				
		No.	1		
3.4	Owner Supplied of Table type Paging Microphone	Nos.	2		
5	LIGHT FIXTURES & FANS				
5.1	Owner Supplied of following light fixtures				
a)	<b><u>Fixture Type - A</u></b> LED Down Light recessed ceiling mounted with 12 watt. As per architect approval.	Nos.	32		
b)	<b>Fixture Type - B</b> LED Down Light recessed ceiling mounted with 7 watt. As per architect approval.	Nos.	8		
c)	Fixture Type - C LED Down Light recessed Wall mounted with 5 watt. As per architect approval.	Nos.	24		

#### UIT UNIVERSITY (AUDITORIUM AREA)

S.No.	Description	Unit	Qty.	Rate	Amount
d)	<b>Fixture Type - D</b> LED Strip Light. As per architect approval.	Mtr.	81		
e)	<u>Fixture Type - E</u> LED Aluminum Profile Light. As per architect approval.	Mtr.	165		
e-1)	Magnatic Track . As per architect approval.	Mtr.	50		
e-2)	200 Watt Magnatic Track Driver	Nos.	9		
f)	Fixture Type - F LED Magnetic recessed Razor Light with 18 watt. As per architect approval.	Nos.	16		
g)	Fixture Type - G LED Magnetic recessed Track Light with 12 watt. As per architect approval.	Nos.	46		
h)	Installation of Down light type Emergency light fixture with 1 hour battery backup time and comprising self contained battery charger reccessed in cieling. Including all accessories, complete in all respects. As per architect approval.	Nos.	8		
i)	Installation of Exit Emergency light fixture with 1 hour battery backup time and comprising self contained battery charger hanging with cieling. Including all accessories, complete in all respects. As per architect approval.	Nos.	2		
6	SMD SCREEN				
6.1 6.1	Owner Supplied of SMD Screen Owner Supplied of SMD Screen Control Wire	No. No.	1 1		
7	A/C UNIT				
7.1	Owner Supplied of A/C Unit (12 TR)	Nos.	2		
8	<u>UPS</u>				
8.1	Owner Supplied of <b>UPS</b> .	Job.	1		

## UIT UNIVERSITY (AUDITORIUM AREA) SUMMARY OF COST ELECTRICAL WORKS

S.NO	ALL SECTION		RS.	AMOUNT
1	SECTION-A	WIRING INSTALLATION	Rs.	
2	SECTION-B	SWITCHES & SOCKETS	Rs.	
3	SECTION-C	TELEPHONE SYSTEM	Rs.	
4	SECTION-D	COMPUTER DATA SYSTEM	Rs.	
5	SECTION-E	CCTV SYSTEM	Rs.	
6	SECTION-F	FIRE ALARM SYSTEM	Rs.	
7	SECTION-G	SOUND SYSTEM.	Rs.	
8	SECTION-H	LIGHT FIXTURES & FANS	Rs.	
9	SECTION-J	SWITCHGEAR	Rs.	
10	SECTION-K	MAIN/SUB-MAIN CABLES	Rs.	
11	SECTION-L	EARTHING	Rs.	
12	SECTION-M	AS BUILT DRAWINGS	Rs.	
		GRAND TOTAL	Rs.	

Rupees In Words:\_\_\_\_\_

# UIT UNIVERSITY, KARACHI

# ELECTRICAL & ALLIED WORKS (ISSUED FOR TENDER) July 2025

Design Consultant :



COLLABORATIVE (PVT)LTD 14-C, Lane 7, Main Kh-e-Bukhari Commercial, Phase - VI, D.O.H.A, Karachi, Pakistan. T +92-21-35242629,35242642,35857957, 35857990 F +92-21-35857986 W www.najmibilgrami.com MEP CONSULTANTS



**EXCELLENT ASSOCIATES** MEP CONSULTING ENGINEERS

SUIT # 201, 2nd FLOOR ANUM BLESSING Block. 7 & 8 K.C.H.S Shahra-E-Faisal Karachi Tel.No. 92-21- 34549508,34326269, <u>Fax.No. 92-21- 4396343</u> E-moil: excellent\_as@yahoo.com

UIT UNIVERSITY, KARACHI.			
	LIST OF DRAWING		
EL-01	DRAWINGS LIST & GENERAL NOTES		
EL-02	ELECTRICAL LEGEND & LIGHT FIXTURE SCHEDULE		
EL-03	STANDARD ELECTRICAL DETAILS - I		
EL-04	STANDARD ELECTRICAL DETAILS - II		
EL-05	EARTHING DETAIL		
EL-06	COMBINED CEILING ELECTRICAL LAYOUT		
EL-07	LIGHTING LAYOUT - 1		
EL-08	LIGHTING LAYOUT - 2		
EL-09	LIGHTING LAYOUT - 3		
EL-10	LIGHTING LAYOUT - 4		
EL-11	EMERGENCY LIGHTING LAYOUT		
EL-12	FIRE ALARM LAYOUT		
EL-13	CCTV & SOUND LAYOUT		
EL-14	WIFI LAYOUT		
EL-15	COMBINED FLOORING UTILITY LAYOUT		
EL-16	RAW & UPS POWER LAYOUT		
EL-17	DATA LAYOUT		
EL-18	SINGLE LINE DIAGRAM		

### **GENERAL NOTES**

01-	ALL WIRING OF LIGHTING AND POWER SHALL BE WITH SINGLE CORE PV SHALL BE 450/750V, WHEREAS FOR THREE PHASE CIRCUIT IT WILL BE
02-	CONDUIT UNDER FLOOR SHALL HAVE A MINIMUM DEPTH OF 50mm MEAS
03-	MINIMUM SIZE OF CONDUIT SHALL BE 25mmø, UNLESS OTHERWISE INDIC
04-	THE ELECTRICAL RESISTANCE OF ECC TOGETHER WITH EARTH LEAD AND
05-	BACK BOXES FOR SWITCHES, SOCKETS AND TELEPHONE ETC. SHALL BE
06-	WIRE AS ECC SHALL BE GREEN OR GREEN / YELLOW IN COLOR.
07-	RUNNING LENGTHS SHOWN IN B.O.Q ARE NOT EXACT CONTRACTOR SHALI
-80	CONDUIT AND CABLES TO BE LAID UNDER FLOOR SHALL BE IN COORDIN
09-	SHOP DRAWING TO BE SUBMITTED BY THE CONTRACTOR TO CONSULTANT
10-	CONTRACTOR TO BE COORDINATED TO ALL OTHER TRADE DRAWINGS.
11-	EXACT LOCATION OF LIGHT FIXTURES TO BE GIVEN BY THE ARCHITECT.
12-	CIRCUIT WIRING SHALL BE WITH THE FOLLOWING SIZE OF WIRES UNLESS
a)	DB TO SWITCH BOARD / 1ST LIGHT WITH 2x2.5 Sq.mm Cu/PVC + ECC
b)	SWITCH BOARD TO LIGHT POINT WITH 1x1.5 Sq.mm Cu/PVC FOR PHASE LIGHT FIXTURES ON SAME CIRCUIT.
c)	13A INTERNATIONAL SWITCH SOCKET UNIT WITH 2x4 Sq.mm Cu/PVC +
d)	13A 3-PIN SWITCH SOCKET UNIT WITH 2x4 Sq.mm Cu/PVC + ECC 1x4
e)	A/C WIRING WITH 2x4 Sq.mm Cu/PVC + ECC 1x4 Sq.mm Cu/PVC OR
13–	THE MAN HOLES/ HAND HOLES TO BE PROPERLY SEALED VIA A SEALE
14–	ADHESIVE SOLUTION TO BE USED FOR FIXING OF JUNCTION BOX.
15–	AVOID USING 4 WAY JUNCTION BOX AT EACH LOCATION. FOR TWO WAY
16-	USE PVC PLUGS/STOPPERS AT OPEN ENDS OF JUNCTION BOXES/PVC (
16-	FOR FIRE ALARM SYSTEM WIRING SHALL BE 2C, 1.5 Sq.mm Cu/PVC (FI ALARM CONTROL PANEL. FOR BASEMENT OR EXPOSE AREA USE SAME (



VC INSULATED WIRES FOR SINGLE PHASE CIRCUIT THE VOLTAGE GRADE OF WIRE E 600/1000 VOLTS.

ASURED FROM FINISH FLOOR LEVEL TO TOP OF CONDUIT.

DICATED.

ELECTRODE SHALL NOT EXCEED ONE OHM.

E MADE WITH 16SWG SHEET STEEL.

ALL HAVE TO TAKE MEASUREMENTS BEFORE PURCHASING THE MATERIAL.

NT FOR APPROVAL BEFORE COMMENCEMENT OF WORK.

S OTHERWISE INDICATED

ICC 1x2.5 Sq.mm Cu/PVC

SE, 1x2.5 Sq.mm Cu/PVC COMMON NEUTRAL AND 1x2.5 Sq.mm Cu/PVC COMMON ECC FOR ALL

- ECC 1x4 Sq.mm Cu/PVC

x4 Sq.mm Cu/PVC FOR COMPUTER POWER

OR AS MENTIONED IN DRAWINGS

LENT/WATER MASKING TAPE TO AVOID INGRESS OF SLURRY IN THE JUNCTION BOX.

Y CONNECTIVITY USE A 2 WAY JUNCTION BOX.

CONDUITS TO AVOID INGRESS OF CONCRETE.

FIRE RESISTANT CABLE) IN PVC CONDUIT FROM FIRE ALARM DEVICES TO FIRE CABLE IN M.S CONDUIT.

CLIENT/ PROJECT:					
	UNIVE KARAC		TY,		
COLLAR		E (PVT	) LTD A, Karachi, Pahist	an.	
	ELLENT	' ASS	OCIA'	TES	
03	SUIT # 201, 2nd FLC Block, 7 & 8 K.C.H. Tel.No, 92-21- Pax.No, 9 E-mal: excelle	DOR ANUM E S Shahra-E-Pa 34549508,343 2-21-4396343 nt_cs@ychot.co	8LESSING ésal Karachi 826269, im		
02 01 00					
PROJECT STATUS	IDER DF			CHECKED	
DRAWN FAIZAN	CHECKED SAIF A	/	APPROVE	D: V.K	
PROJECT No.:	SCALE: N.T.S	[	DATE:	07-2025	
DI	RAWINGS ENERAL N				
DRAWING NO. REVISION					
E	L-01				

EGEND -			
SYMBOL	DESCRIPTION	TYPE	MOUNTING
6	10 AMP ONE WAY LIGHT SWITCH	SEE SPECS	1000mm AFFL
$\bigtriangleup$	10 AMPS MULTI SWITCHED SOCKET OUTLET	SEE SPECS	150/1000/1200mm AFI
$rac{1}{2}$	13 AMPS 1 GANG INTERNATIONAL SWITCHED SOCKET OUTLET (SIMPLEX)	SEE SPECS	150/1000/1200mm AF
$\boxtimes$	POPUP BOX	SEE SCHUDLE	IN FLOOR
	MULTIPLE OUTLET MOUNTED ON WALL/FURNITURE	SEE SCHUDLE	WALL/FURNITURE
$\square$	FLOOR OUTLET BOX (SQUARE TYPE)	SEE SCHUDLE	RECESSED IN FLOO
	LIGHT & POWER DISTRIBUTION BOARD	SEE SPECS	
	POINT WIRING (CEILING)	SEE SPECS	
R1/DB-GF	CIRCUIT WIRING CKT R1 OF DB-GF	SEE SPECS	
FA	FIRE ALARM WIRING	SEE SPECS	
SP	P.A. SYSTEM WIRING (SPEAKER WIRING)	SEE SPECS	
	CONDUIT RUN IN UNDER FLOOR / GROUND RACEWAY	SEE SPECS	
R1,Y1,B1,	INDICATES LIGHTING CIRCUIT NO.	SEE SPECS	
R1",Y1",B1",	INDICATES A/C POWER CIRCUIT NO.	SEE SPECS	
C1,C2,C3	INDICATES UPS POWER CIRCUIT NO.	SEE SPECS	

SYMBOL	DESCRIPTION	TYPE	MOUNTING
$\nabla / \Xi$	RJ-45 VOICE /TELEPHONE OUTLET	SEE SPECS	150/1000/1200mm AFI
	RJ-45 DATA OUTLET	SEE SPECS	150/1000/1200mm AFI
6	WIFI ACCESS POINT (CEILING MOUNTED)	SEE SPECS	CEILING
SD / 🚱	SENSOR / DETECTOR	SEE SPECS	FALSE CEILING
	FIRE ALARM HEAT SENSOR / DETECTOR	SEE SPECS	FALSE CEILING
ਜ / 🕑	ELECTRONIC SOUNDER/BELL	SEE SPECS	2400mm AFFL
	MANUAL BREAK GLASS STATION	SEE SPECS	1400mm AFFL
FACP	FIRE ALARM CONTROL PANEL	SEE SPECS	1350mm AFFL
	FIRE ALARM END OF LINE RESISTOR	SEE SPECS	
	IP BASED INDOOR FIXED DOME CCTV CAMERA	SEE SPECS	CEILING
NVR	CCTV NETWORK VIDEO RECORDER (NVR)	SEE SPECS	INSTALLED IN RACK
	CEILING SPEAKER	SEE SPECS	FALSE CEILING

#### - LIGHT FIXTURE SCHEDULE -


S.No	PICTOGRAM	SYMBOL/FIX.ID	TYPE	LAMP	MOUNTING			
EM	ERGENCY L	_IGHTING						
01	+× [-*]	EXIT	LED EMERGENCY LIGHT WITH DIRECTIONAL EXIT SIGN	3 WATT LED LAMP	CEILING/WALL MOUNTED			
02		(L)	CEILING RECESSED LED EMERGENCY LIGHT	3 WATT LED LAMPS	CEILING RECESSED			
IND	OOR LIGH	TING						
03		$\sim$	LED TAPE/STRIP WITH POWER SUPPLY UNIT	72 WATT LED STRIP (5 METER REEL)	SURFACE (INDIRECT LIGHT)			
04		•	LED CEILING RECESSED DOWNLIGHT	7 WATT LED LAMP	FALSE CEILING			
05	6	$\oplus igodot$	LED CEILING RECESSED DOWNLIGHT	12 WATT LED LAMP	FALSE CEILING			
06			LED MAGNATIC RAZOR LIGHT	18 WATT LED	CEILING			
07	5	$\Box$	LED MAGNATIC TRACK LIGHT	12 WATT LED	CEILING			
08			WALL LED RECESSED DOWNLIGHT	5 WATT LED LAMP	RECESSED			
			ALUMINUM PROFILE LED LIGHT		SURFACE			

## 


WIRE/CABLE		CONDUIT SIZE					
mm <sup>2</sup>	25mm or 1inch	32mm or 1-1/4inch	38mm or 1-1/2inch	50mm or 2inch			
1.0	18	30	40	50			
1.5	15	25	35	45			
2.5	12	20	30	35			
4	8	12	20	25			
6	6	10	15	20			
10	4	6	10	12			
16	3	5	7	8			
25	2	3	4	6			
35	_	2	3	5			
50	_	2	2	4			


the second second
-------------------


NT/ PROJECT:					
UIT	UNIVE KARAC		IT	Y,	
gn Consultant :					
<b>IB</b> <b>COLLA</b> 14-C, Lare 7, Main K9 T + 99-21-35242629,3 F + 99-21-35857966	DINAL GIRA BORATIV 14-BUKHATI COMMERCIAL PR 15242642,35857957,35857957				an.
	CELLENT MEP CONSULT SUT # 201, 2ad FLC Block, 7& & K.C.H. Tel.No. 92-01 FL.No. 92-01 Construction	ING E OR ANUM S Shahra-E- 34549508,3	NGIN I BLES! Faisal K 4326267	<b>IEERS</b>	
DES	CRIPTION	DATE	DF	RAWN	CHECKED
	DER DR	RAW	IN	G	
WN FAIZAN	CHECKED SAIF A		APP	ROVE	D: N.K
ECT No.:	SCALE: N.T.S		DAT	E:	07-2025
	TRICAL L IXTURE				
WING No.	1 00			REVIS	NON
E	L-02				




	UNIVE KARAC			Y,		
n Consultant :						
COLLA     14-C, Lane 7, Main Kit     14-C, Lane 7, Main Kit     142-21-35242829.92     F +92-21-35957966     W www.najmtilgraml.	DINHI GGRA -BORATIV -Bukkari Commercial, Pr 242642,35657657,35657657 com	E (PV		TD rachi, Palis	an.	-
	ELLENT MEP CONSULT SUTI # 201, 200 FLC Block. 7 & 8 K.C.H. Tel.No. 92-21- Fax.No. 9, E-molt-eccele	ING E	NGI	NEERS	TES	
		D.1-5-5			0050055	-
IECT STATUS	CRIPTION	DATE		RAWN	CHECKED	
	NDER [	DRA				
/N FAIZAN	CHECKED SAIF A	LI.			D: W.K	
ECT No.:	SCALE: N.T.S		DAT		07-2025	
VING TITLE:	DARD EL DETAIL			CAL		
VING No.	L-03			REVIS	SION	








-CEILING & WALL MOUNTED IP CAMERA DETAIL






EN	T/ PROJECT:				
	UH	UNIVE KARAC		ΙΥ,	
igr	Consultant :				
	NA	JIMI			
	IBIUL	1GIR4			
	COLLA	BORATIV h-e-Bukhari Commercial, Phy IS242642,35857957, 358579			istan.
2	CONSULTANTS				
E		CELLENT MEP CONSULT SUIT # 201, 2nd FLC Block. 7 & 8 K.C.H. TeLNo. 92-21- <u>Pax.No.</u> 9, E-molt-excelle	ING EN OR ANUM S Shahra-E-F 34549508 3	GINEERS BLESSING Jaisal Karachi 1326269	
	DES	SCRIPTION	DATE	DRAWN	CHECKED
J	ECT STATUS			1	
	TE		DRA	WING	
N	N	CHECKED		APPROVE	D:
	FAIZAN	SAIF A		DATE:	W.K
	CT No.:	SCALE:			07-2025
w	VING TITLE:				
	STAN	DARD EL DETAIL			-
4	VING No.			REVIS	SION
	_	L-04			













ENT/ PROJECT:					
	UNIVE KARAC		TY,		
ign Consultant:					
NA	JIMII				
<u> 18101</u>	GIR/				
14-C, Lane 7, Main Kh T +92-21-35242629,35 F +92-21-35857986 W www.najmbilgramb	BORATIV -e-Bukhari Commercial, Pr 1242642,35857957, 3585795 com			an.	
	CELLENT MEP CONSULT SUIT # 201, 2nd FLC Block, 7 & 8 K.C.H. TeLNo, 92-21 Fax No, 92 E-mdt excel	ING EN	GINEERS		
3					
2					
)					
V DES OJECT STATUS	CRIPTION	DATE	DRAWN	CHECKED	
TEN	DER DI	RAV	VINC	3	
AWN Faizan	CHECKED Saif Ali		APPROVE W	D: V.K	
DJECT No.:	SCALE: 1/4" = 1'-		DATE:	-2025	
	BINED ( TRICAL				
AWING No.			REVIS		
E	L-06				






					-
	UNIVE		ITY,		
	KARAC	HI.			
ign Consultant:	UMII				
COLLAI	• Bukhari Commercial, Pr 242642,35857957,3585795			tan.	
	CELLENT MEP CONSULT SUTT # 201, 2nd FLC Block, 7 & 8 K.C.H. TFil.No, 92-21- Fax.No, 9 2 -mail.excell	ING E	<b>NGINEERS</b>		
3	E-mail: excelle	nt_s <b>s®ys</b> hoo.	com		
<u>?</u> I					
) V DES	CRIPTION	DATE	DRAWN	CHECKED	
OJECT STATUS	DER DI	RAV	VINC	3	
WN Faizan	CHECKED Saif Ali		APPROVE		
DJECT No.:	SCALE: 1/4" = 1'-		DATE:	-2025	
AWING TITLE:					
LIGH	FING LA	YO	JT - 1		
AWING No.	L-07		REVIS	BION	






ENT/ PROJECT:					
	UNIVE KARAC		TY,		
ign Consultant :					
IVA.	IIMII				
IBIIL	4 GFIR4		].[].[		
COLLAE 14-C, Lane 7, Main Kh T +92-21-35242629,35 F +92-21-35857966 W www.najmbilgramb	BORATIV -e-Bukhari Commercial, Pr 1242642,35857957, 3585795 com	' <b>Е (рv</b> * nase - VI, D,O,H 00	F) LTD IA, Karachi, Pakis	tan.	
			OCIA	TEC	
	CELLENT AEP CONSULT SUIT # 201, 2nd FLC Block. 7 & 8 K.C.H. Tel.No. 92-21- Fax.No. 9. E-mat.excelle	ING EN	GINEERS		
/	CRIPTION	DATE	DRAWAL	CHECKED	
DJECT STATUS	CRIPTION	DATE	DRAWN	CHECKED	
	DER DI	RAV	VINC	3	
WN Faizan	CHECKED Saif Ali		APPROVE W		
JECT No.:	SCALE: 1/4" = 1'-		DATE: 12-07	-2025	
AWING TITLE:					
LIGHTI	NG LAY	ουτ	- 2		
AWING No.			REVIS	SION	
E	L-08				






ENT/ PROJECT:	
UIT UNIVERSITY, KARACHI.	
ign Consultant : DAJINII BUILL GIRANIII COLLABORATIVE (PVT)LTD 145(-Lung 7, Ling Hore Backet) Commercial Press 1-99(-2)-99(20) F 492(-2)-99(20) W www.allignation	
P CONSULTANTS EXCELLENT ASSOCIATES EXCELLENT ASSOCIATES MEDICONSULTING ENGINEERS SULTANTS SULTANTAL ASSOCIATION MELESSION Diversified a Kennel Technological Associations Excellented and the second association Excellented and the second association	
3	
2	
)         Image: Constraint of the second secon	
TENDER DRAWING	
AWN         CHECKED         APPROVED:           Faizan         Saif Ali         W.K	
SCALE:         DATE:           1/4" = 1'-0"         12-07-2025	
AWING TITLE:	
LIGHTING LAYOUT - 3	
AWING No. REVISION	






.IEN	IT/ PROJECT:						
		UNIVE KARAC		IT	Y,		
sigr	Consultant :						
	COLLAI 14-C, Lane 7, Main KP T +92-21-35242629,3 F +92-21-35857966	JIVII GFIRA BORATIV 14-Bukkari Commercial, Pi S42642,35867957, 3596791	<u>(E (PV</u> E (PV 1886 - VI, D.O. 10	/]_() 'T.) L.' H.A. Ka	TD rachi, Palis	an.	
EP (	W www.najmitilgrami	.com					
8		CELLENT MEP CONSULT SUIT # 201, 2nd FLC Block, 7. & 8 K.C.H. Tel.No, 92-21- Pax.No, 9 E-molt-societ	'ING EI	NGI	NEERS		
3							
2				+			
0							1
EV ROJ	DES ECT STATUS	CRIPTION	DATE	DI	RAWN	CHECKED	
	TEN	DER DI	RAV	NI	NG	5	
AW		CHECKED		APF	ROVE		
	Faizan CT No.:	Saif Ali SCALE:		DAT	W E:	.К	
		1/4" = 1'-	ď.		12-07	-2025	
RAV	VING TITLE:						
		NG LAY	OU	Γ-			
RAV	VING No.	1 40			REVIS	SION	
	E	L-10					






ENT/ PROJECT:						
	UNIVE KARAC			Y,		
	JINI GFIRA BORATIV N=Bukkeri Commercial, PP 22/2012/38607867, 30807967070000000000000000000000000000000				tan.	
	CELLENT MEP CONSULT SUTF # 201, 2ad FLC Block, 7 & 8 K.C.H. TeLNo, 92-21- Fac.No, 9 gmail.excele	ING E	NGI	NEERS		-
V DES	CRIPTION	DATE	D	RAWN	CHECKED	-
DJECT STATUS	DER DI	٦A١	N	INC	3	
.WN Faizan	CHECKED Saif Ali		API	PROVE		
JECT No.:	SCALE: 1/4" = 1'-		DA	re:	-2025	
WING TITLE: EMERGENCY LIGHTING LAYOUT						
AWING No.	L-11			REVIS	5101	






ENT/ PROJECT:	UNIVE	RSI	TY,		
	KARAC				
ign Consultant:	JIMII				
COLLAI	GFIRA BORATIV 14-Bukhari Commercial, Pr 2242642,35857957, 3585795		) LTD A, Karachi, Palis	an.	
P CONSULTANTS	CELLENT MEP CONSULT Block, 7 & 8 K.C.H. TELNO, 92-21- Fax.No, 92-21- Fax.No, 92-21- Sax.Mo, 92-21- Fax.No, 92-21- Sax.Mo, 92-21- Fax.No, 92-2	ASS ING EN DOR ANUM F \$ Shahra-E-Pa 34549508.34 2-21-4396843 2-21-4396843	GINEERS	TES	
3					
2					
	CRIPTION	DATE	DRAWN	CHECKED	
OJECT STATUS	DER DI	RAV	VINC	5	
WN Faizan	CHECKED Saif Ali		APPROVE W		
DJECT No.:	SCALE: 1/4" = 1'-	[	DATE:	-2025	
AWING TITLE:	I				
FIRE	ALARM	LAY	DUT		
AWING No.	L-12		REVIS	510N	
C	L-12				





IEN	IT/ PROJECT:						
	UIT	UNIVE	RS	т	Y		
		KARAC			•,		
sian	Consultant :						
	NA	JIMII					
	][B][0[	4 GFIRA		/][	][		
	COLLA 14-C, Lane 7, Main Ki T +92-21-35242629,3 F +92-21-35857986 W www.najmbilgram	BORATIN n-e-Bukhari Commercial, F 5242642,35857967, 358575 .com	/ E (PV hase - VI, D.C 190	(T)   (HA, I	LTD Karachi, Pakisl	ian.	
P (				20	CLA	TEC	
E		SUTT # 201, 2nd FL Block. 7 & 8 K.C.H Tel.No. 92-21 Pax.No.5	<b>FING E</b>	NG 1 BLE Paisal 54326	<b>INEERS</b>		
3		E-mail:excel	ent_as9yshoo	com			
2							
1 0							
v OJ	DES ECT STATUS	CRIPTION	DATE	[	DRAWN	CHECKED	
	TEN	DER D	RA۱	N	INC	5	
AW	N Faizan	CHECKED Saif Al	i	AP	PROVE		
Faizan         Saif Ali         W.K           DJECT No.:         SCALE:         DATE:           1/4" = 1'-0"         12-07-2025							
RAM	/ING TITLE:	1/4 = 1	-0		12-07	-2023	
	ССТУ 8	& SOUN	D L/	۹)	νου	т	
RAM	/ING No.				REVIS	SION	
	E	L-13					






INT/ PROJECT:	UNIVE	RS	ΙТ	Y.		
	KARAC			ĺ		
gn Consultant :						
		A 774	h=C	7		
COLLAI	4 <b>GFIRA</b> borativ	<u>all</u> () 'E (pv	/] <u> </u> TDE	<u>                                     </u>		
14-C, Lane 7, Main Kr T +92-21-35242629,35 F +92-21-35857986 W www.najmbilgraml.	-e-Bukhari Commercial, Pr 5242642,35857957, 3585795 com	nase - VI, D.C 90	.H.A, Ka	rachi, Pakis	tan.	
CONSULTANTS						
	CELLENT AEP CONSULT SUIT # 201, 2nd FLC Block. 7 & 8 K.C.H. Tel.No. 92-21- Pax.No. 92 E-molt-excelle	ING E	NGI	NEERS		
			-			-
/ DES	CRIPTION	DATE			CHECKED	]
JECT STATUS		DATE	10	NAME OF THE OWNER	SHEGKED	-
TEN	DER DI	٦A	N	INC	3	
WN Faizan	CHECKED Saif Ali		APF	PROVE		-
JECT No.:	SCALE: 1/4" = 1'-	Q.	DAT		-2025	-
	VIFI LAY		_			]
		00	1			
WING No.				REVIS	SION	
E	L-14					
				I		J

(	A		В										
		BACK ENTRANCE											
1													
								$ \begin{array}{c}                                     $	+3'-4"		FLOOR LEVEL +2'-6"		$\bigoplus_{\pm 1}^{FLC}$
													_[
	-⊕ <u>FLO</u> +7'	OR LEVEL -6"	+	FLOOR LEVEL +6'-8''	¢	FLOOR LEVEL +5'-10''	-						
(2)	8												
	ROOM 5'-7"x5'-8"		PULL BOX	5			STEP DN.						
(3)	D Q												
		<u>OR LEVEL</u> -6''		<u>FLOOR LEVEL</u> +6'-8''	-	FLOOR LEVEL +5'-10''	- OFLOOR LEVEL +5'-0"						_
		-0		+0-0		+5-10	- +5-0						
													— <u>U</u>
								 FLOOR LEVEL +4'-2''	+3'-4"	$\oplus$	FLOOR LEVEL +2'-6"	-	$\bigoplus_{i=1}^{FLG}$
4													
													$\left \right\rangle$
											/////	///	







IENT/ PROJECT:				
	UNIVE KARAC		ITY,	
sign Consultant :	INMAT			
	G-IRA		<u>/].[].</u>	
	BORATIV Bukhari Commercial, Pr 1242642,35857957, 3585795 2001			tan.
	ELLENT		OCIA	
<u> </u>	IEP CONSULT SUIT # 201, 2nd FLC Block, 7 & 8 K.C.H. Tel.No. 92-21- <u>Pax.No. 9</u> E-molt-excelle	OR ANUM S Shahra-E-I 345495083	BLESSING Paisal Karachi 4376769	<u>}</u>
3				
1 0				
	CRIPTION	DATE	DRAWN	CHECKED
TEN	DER DI	RAV	VINC	3
AWN Faizan	CHECKED Saif Ali		APPROVE	
DJECT No.:	DATE: 12-07	7-2025		
AWING TITLE: COME UT	INED FI		RING	3
AWING No.			REVIS	SION
E	L-15			

(	A		В												
		BACK ENTRANCE													
(1)							Y8/LPDI		+4'-2'		FLOOR LEVEL +3'-4"	i la	F <u>LOOR LEVEL</u> +2'-6"	-	
							R8/LPDB								
(2)	+7	DOR LEVEL ''-6''	+	FLOOR LEVEL +6'-8''	<u> </u>	+5'-10"	+5'-0"								
	8-			5		K									
(3)		4/LPDB		B	7/I PDB		 								
		<u>DOR LEVEL</u>		FLOOR LEVEL	B/LPDB	FLOOR LEVEL +5'-10"									
							Y7/LPDB								
(4)									B6/LPDI +fLOOR LEVEL +4'-2'		Y6/LPD FLOOR LEVEL +3'-4"		R6/LPC FLOOR LEVEL +2'-6"		⊕ <sup>FL</sup>
				<u>i Suly () y</u>	<u>.</u>	<u>, 1976 (</u> , 1988)		a	<u></u> 1 <b>.</b>	<u></u>					






ENT/ PROJECT:						
	UNIVE KARAC			Υ,		
COLLA 14-C. Lano 7, Main M 14-92-1385786 Www.najnetifyanu P CONSULTANTS	CELLENT	hase - VI, D.C 90	(HA)	Karachi, Paliis CIA'	ГЕЅ	
· ·	MEP CONSULT SUIT # 201, 2nd FL Block, 7 & 8 K.C.H Tel.No. 92-21 <u>Fax.No. 5</u> E-molt excell	OOR ANUM .S Shahra E - 34549508,	I BLI Faisal 54326	INCLESS SSING Karachi 269,	_	
1 !			+			
/ DES	CRIPTION	DATE	I	DRAWN	CHECKED	
DJECT STATUS	DER DI	RA۱	N	ING	5	
WN Faizan	CHECKED Saif Ali		AF	PROVE		
NECT No.:	SCALE: 1/4" = 1'-	DATE:		-2025		
AWING TITLE:		<u> </u>		12 07		
RAW & UI	PS POW	/ER	L	ΑΥС	DUT	
AWING No.	L-16			REVIS	SION	





ENT/ PROJECT:	UNIVE	RSI	T	Υ.		
	KARAC			• ,		
ign Consultant :						1
COLLAI 14-C, Lane 7, Main KP T +92-21-35242629,33 E +92-21-35957986	4 GFIRA 3 ORATIV 14-Bukhari Commercial, PI 5242642,35857857, 3585789	AUT) E (PV 1986 - VI, D.O.I 20	/] T) L1 H.A. Kar	FD rachi, Pakis	tan.	
P CONSULTANTS	com					-
	CELLENT AEP CONSULT SUIT # 201, 2nd FL Block, 7, & 8 K.C.H. Tel.No. 92-21- Fax.No. 9 E-mal-societ	ING EN JOR ANUM S Shahra-E-F	BLES!	VEERS	TES	
2						-
1						
V DES OJECT STATUS	CRIPTION	DATE	DF	RAWN	CHECKED	-
TEN	DER DI	RAV	VI	NC	3	
AWN Faizan	CHECKED Saif Ali			ROVE		
	SCALE: 1/4" = 1'-		DAT		-2025	
	ATA LAN	γOU	т			
AWING No.				REVIS	SION	1
E	L-17					



EL-18

# **HVAC WORKS**

\* \* \* \*

## DESIGN DRAWINGS AND BILL OF QUANTITIES

\* \* \* \*

**AUDITORIUM AREA** 



#### LIST OF APPROVED MANUFACTURERS (HVAC)

Equipment & Material shall be supplied only from the approved sources noted below. However in all cases the Contractor shall submit complete technical details of the equipment, material and obtain Consultants approval prior to delivery on site. Where option of "Approved Equivalent" is indicated, it shall be at the discretion of the Consultant to accept the alternate proposal submitted by the Contractor.

S.No.	Equipment/Material	Approved Manufacturers	Country of Origin
1	Paint	Berger	Pakistan
I		ICI	Pakistan
2	Shut Off Valves Danfoss		China
	Supports & Anchors	Fabricate as per approved sample	Pakistan
		Mungo-Norm	Pakistan-China
3	Concrete Fasteners	Rawl plug Co.	UK.
	/Clamps/Threaded Rods/Drop	Fischer	Germany
	In Anchor	Hilti	UK/Germany
		Inka	Turkey
	Piping		
	G.I. Pipe	IIL	Pakistan
4	Drain Pipe	Jeddah	Pakistan
4	DialitiFipe	AGM	UAE
	Copper Piping	Trox	Korea
		Muller-K Type	USA
		Foster	USA
	Vapour barrier coating	Zahabiya	Pakistan
	vapour barrier coating	Ductmate Inc.	USA
		Approved equivalent	Imported
5	Insulation Adhesive	Ductmate Inc.	USA
5	Insulation Adhesive	Zahabiya	Pakistan
		Armaflex	USA
	Closed Cell Foam Insulation	Aerofoam	UAE
		Aeroflex	Thailand
		Superloan	Malaysia
		Afico	Saudi Arabia
	Duct Insulation	Kimco	Kuwait
6		Izocam	Turkey
0	Canvas Jacket	Approved	Pakistan
	Insulation Adhesive	Ductmate Inc.	USA
		Zahabiya	Pakistan

#### LIST OF APPROVED MANUFACTURERS (HVAC)

Equipment & Material shall be supplied only from the approved sources noted below. However in all cases the Contractor shall submit complete technical details of the equipment, material and obtain Consultants approval prior to delivery on site. Where option of "Approved Equivalent" is indicated, it shall be at the discretion of the Consultant to accept the alternate proposal submitted by the Contractor.

S.No.	Equipment/Material	Approved Manufacturers	Country of Origin
		Pakistan Steel	Pakistan
	Sheet Metal	ISL	PAKISTAN
		Imported	As approved
7	P3 Duct	PAL	UAE
		Atco	USA
	Flexible Duct	DEC International	Netherland
		Approved Equivalent	Imported
		Thermec	Pakistan
		EAP	Pakistan
8	Air Devices	Air Guide	Pakistan
		Mehran	Pakistan
		Shan Associates	Pakistan
		Pakistan Cable	Pakistan
	Cables	Fast Cables	Pakistan
	Cables	Universal Cables	Pakistan
		Pioneer Cables	Pakistan
9	Steel Conduits	Hilal Industries	Pakistan
3		IIL	Pakistan
	Control Panel (MCC) Manufacturers	Owner furnished	
		Ezzy	Pakistan
	Cable Tray	Approved Equivalent	Pakistan
10	Air Curtain	SASA/Levenze/AirGuide	Pakistan
		Coolmax	Pakistan
		EFSA Trading	Lahore-Pakistan
	Deef Tep Deekeged Lipite	AirQon Synergies	Lahore-Pakistan
11	Roof Top Packaged Units	Tica	China
		Euroklimat	China
		York	China/Turkey
		SKM	UAE

i

# BILL OF QUANTITIES

## UIT UNIVERSITY (AUDITORIUM AREA)

### HVAC WORKS

## **BILL OF QUANTITIES**

S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1.0	SUPPLY AND INSTALLATION OF HVAC UNITS Installation on site foundation, with vibration isolators, electrical and control connections, Flexible Connector, electrical, earthing and piping connections, control/communication wire connection, thermostat, Complete with safety controls and accessories, operation and maintenance manual, thermostat and installation complete in all respect, Roof Top Package Units, 12 TR Double Skinned Package Unit				
1.1.1	Ambient at 110F/84 WB Ozone Friendly Refrigerant Thermostat with 3 Speeds With Proper Base, Dual Compressor Outdoor Fins of Condensor should have Acraclad/Herasite or Superior Coating Breakers will be Terasaki/ABB/Schneider Europe Only Communication wiring should be supplied and will run in conduit Submittal of Units to be provided to Consultant, Without Consultant Approval, Unit will not be approved	2	Nos.		
1.2	6" HEIGHT CC Foundation pads for AC units. Installer will give complete markings as per actual equipment dimensions at site	Ву	ı Civil		
1.3	Supply and installation of Drain pipe for Units, complete in all respect including supports, insulation and specilities, trap as per requirement of units etc	1	Job		
1.4	Transportation of Equipment to site	1	Job		
1.5	Out door PlatForm of units		lot uired		
1.6	Red Oxide and Paint on Platform		lot uired		
1.7	Commissioning & Testing, and Handing Over	1	Job		
	Sub-total Carried to Summary				

Karachi.

S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
2.0	AIR CONDITIONING DUCT WORK AND ACCESSORIES Supply & Installation of pre insulated duct work of polyurethene form panel with 52kg/m3 density, 20mm thickness, coated on both sides with 60 micron thick aluminum foil, complete with 2 g/m2 layer, including manufacture aluminum/ PVC Hardware, glue, hot diped galvanied hanger and supports, flexible duct connection, complete in all respect, ready to operate, wooden frame if require, sealing of openings, complete in all respect, with Duct Leakage Test	2700	Sq ft		
2.2	Supply & Installation of 26 guage G.I Sheet Metal Duct Work for Cladding of exposed ducts, with galvinized supports & hangers complete in all respects as per schedule, instructions & approval of client.	500	Sq ft		
2.3	Supply and installation of Sound Liner 1" thick 24kg/m3 at Supply and return Air Duct of AHUs, Complete in all Respect	400	Sq ft		
	Sub-total Carried to Summary				
3.0	AIR DEVICES Note: Color of All Air Devices as per Approval of Consultant/ Client / Architect. Contractor must show sample before supply				
3.1	Supply and Installation of Supply Air Diffuser as per Air terminal Schedule				
3.1.1	Round Diffuser, Step Down Cone, 14" diameter with M7 Damper	34	Nos.		
3.1.2	Supply air Disk Valve, 6" Diameter	1	No.		
3.1.3	18 Gauge Volume Control Damper	1320	Sqin		
3.2	Wire Mesh at Return Duct as shown in drawing	1	Job		
3.3	Supply and Installation of Fresh Air Section with Damper and G3 filter and Exhaust Air Section with Damper at Main Return Ducts of Units as per Drawing and requirement	1	Job		
	Sub-total Carried to Summary				

#### UIT UNIVERSITY (AUDITORIUM AREA)

Karachi.

S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
<b>4.0</b> 4.1	ELECTRICAL WORKS Electrical,Power and Earthing Cable (Equipment Supplier to inform exact sizes , Kws of equipment Estimated Power for 15 TR Unit = 20 kw x per unit, TOTAL Power = 50 kw	By ele	ectrical		
4.2	MCC (By Electrical) Contractor will inform complete requirement and load to Electrical	quirement and load to Electrical By electrical			
5.0	MISCELLANEOUS				
5.1	Shop Drawings & Asbuilt Drawings	1	Lot		
5.2	Rigging/Lifting/Shifting of AHUS	1	Job		
5.3	Tagging and Finishing	1	Job		
5.4	Air Balancing of Systems	1	Job		
5.5	15 Days operation and maintenance of log book	1	Job		
	Sub-total Carried to Summary				

#### UIT UNIVERSITY (AUDITORIUM AREA)

#### SUMMARY OF COST

#### HVAC WORKS

S NO.	DESCRIPTION	AMOUNT IN FIGURES (Rs.)
1.0	SUPPLY AND INSTALLATION OF HVAC UNITS	
2.0	AIR CONDITIONING DUCT WORK AND ACCESSORIES	
3.0	AIR DEVICES	
4.0	ELECTRICAL WORKS	
5.0	MISCELLANEOUS	
	TOTAL =	

#### AMOUNT IN RUPEES= \_\_\_\_

#### DECLARATION:

I HAVE CLEARLY SEEN ALL TENDER DOCUMENTS, DRAWINGS, BOQ AND SPECS, AND UNDERSTAND ALL SCENARIO, FOR GIVING FINISHED PROJECT WITH GOOD ENGINEERING PARACTICES

#### NAME OF PERSON (CONTRACTOR)

SIGNATURE OF CONTRATOR ALONG WITH DATE AND COMPANY STAMP

NOTE: QUANTITY BASED BOQ, WILL BE VERIFIED DURING BILLING ALL SAMPLES AND SUBMITTALS MUST BE SHOWN PRIOER TO INSTALLATION

